



ELECTRICAL LIGHTING PLAN
SCALE: 1/8"=1'-0"

MARK	DESCRIPTION	MOUNTING MANUFACTURER	SERIES OR TYPE	VOLT	LAMP(S)
F-1	2x4 TROFFER	GRID	LITHONIA	240V	THREE (3) T8 35W FLUORESCENT
F-2	2x2 TROFFER	GRID	LITHONIA	240V	THREE (3) T8 17W FLUORESCENT
F-3	CAN LIGHT, LED	RECESSED HALO	6 IN. ALUMINUM (C RATED), 10" TALL, AIRTIGHT HOUSING	120V	PHILIPS PAR 28, 100W ECG 3000K LED FLOOD LIGHT
F-4	OUTDOOR BLACK WALL LUMEN	WALL	HAAPTON BAY	120V	VERIFI-STYLE WITH OWNER LITHONIA E12 LED M12, 3000K BACKUP POWER
X-1	EMERGENCY LIGHTING 2 HEAD	WALL	LITHONIA	120V	COMES WITH UNIT
X-2	EXIT SIGN	CEILING	LITHONIA	120V	COMES WITH UNIT
X-3	EMERGENCY LIGHTING WITH EXIT SIGN	WALL	LITHONIA	120V	COMES WITH UNIT

-- LIGHT FIXTURES MARKED WITH "N" SHALL HAVE "N" BULBS & BALLAST WIRED TO NON-SWITCHED CIRCUIT.

REVISIONS	BY
9/22/14	JTL

These documents are the property of FRANK E. GERARVE, JR., ARCHITECT, L.L.C. and are intended for the sole use as indicated on these documents. The removal of the architect's seal or stamp from these documents unless otherwise provided by written agreement of the architect and the client is a violation of the Louisiana Revised Statutes (R.S. 37:1209) and shall be subject to the penalties, fines and/or imprisonment as stated by Louisiana Law.

FRANK E. GERARVE, JR., ARCHITECT, L.L.C.
 A Professional Architectural Limited Liability Company
 Designers Planners Engineers
 9108 CHRETIEN POINT PLACE, RIVER RIDGE, LOUISIANA 70123
 Telephone: (504) 737-2821 Facsimile: (504) 737-2822

Slidell Little Theatre
 2024 Nellie Drive
 Slidell, Louisiana 70458

Light fixture with:

DAMMON
ENGINEERING, INC.
Architects & Engineers

Chief Architect: Kevin J. Kitchin, NCARB
 Chief Engineer: Brian Mastich, PE
 www.dammonengineering.com
 dammoneng@slidell.littheatre.net
 Slidell, LA 70458 P: 985.641.2990

DAMMON L.L.C.
DESIGNED C.K.D.
DATE 9/9/14
SCALE NOTED
JOB NO. E-2