

ELECTRICAL POWER PLAN

SCALE 3/16" = 1'



- LEGEND**
- ⊖ - RECEPTACLE 200A 115V
 - ⊖ - GFI RECEPTACLE 20A
 - ⊖ - WEATHER PROOF GFI RECEPTACLE 20A
 - ⊖ - RECEPTACLE 20A AT DECK ABOVE
 - ⊖ - FLOOR RECEPTACLE
 - ⊖ - JUNCTION BOX
 - ⊖ - DISCONNECT
 - ⊖ - POWER PANEL
 - ⊖ - TELEPHONE/DATA


CLECO Power LLC - Electrical Load Summary

Project Name: Tabernacle Baptist Church
 Project Address: 2445 Fourth Avenue
 City / Town: St. Tammany Parish - Slidell, Louisiana

Intended Use: Church
 Requested Service: 240 Volts 1Ø Phase 3 Wires
 Service Entrance Size: 400 Amps
 HVAC Tonnage: 19 Tons
 Largest Motor: N/A HP (Note: Motors above 20 hp may require reduced voltage starting and are never recommended for use with 120/240V, 3 Ø, 4W services.)

Total Building Square Footage: 4,425 Square Feet
 Individual Unit Square Footage: N/A Square Feet (Multiple Occupancy)
 Individual Unit Designation: N/A (Multiple Occupancy)

LOAD SOURCE	1Ø - kVA	3Ø - kVA	or	1Ø - kW	3Ø - kW
Building Lighting	12.204	-	or	-	-
Electric Water Heating	7.200	-	or	-	-
Heat Pumps	-	-	or	-	-
Supplemental Heat System	-	-	or	-	-
Air Conditioning	57.600	-	or	-	-
Electrical Heating (Primary) - AHUs	60.000	-	or	-	-
Cooking	-	-	or	-	-
Refrigeration	160	-	or	-	-
Receptacles (Standard)	-	-	or	-	-
Receptacles (Computer)	8.480	-	or	-	-
Total Motors (Exclude HVAC)	-	-	or	-	-
Parking Lot / Exterior Lighting	1.220	-	or	-	-
Miscellaneous -	-	-	or	-	-
Other (Specify)	-	-	or	-	-



DAMMON ENGINEERING, INC.
 CHIEF ENGINEER
 EMMETT DAMMON, P.E.
 CHIEF ARCHITECT
 ROBERT WILTSE

1095 FLORIDA AVENUE
 SUDDLE, LA. 70458
 OFFICE: 985-649-5832
 FAX: 985-641-5950
 WEBSITE: WWW.DAMMONENGINEERING.COM
 EMAIL: DAMMONENG@Bellsouth.net

ARCHITECTURE
 ENGINEERING
 STUDIES
 PLANNING
 INVESTIGATION
 EXPERT WITNESS

NEW CHURCH
 TABERNACLE BAPTIST CHURCH
 2445 FOURTH ST.
 SUDDLE, LA

ELECTRICAL POWER PLAN

REV:

SCALE AS NOTED

JOB#: 2050

DATE: 2-8-10

SHEET 22

E-1

OF 25