



STATE OF LOUISIANA

OFFICE OF STATE FIRE MARSHAL, CODE ENFORCEMENT, AND BUILDING SAFETY INSPECTION REPORT
 This inspection is intended for your safety and the safety of the citizens of Louisiana. Your cooperation is greatly appreciated.

District: **BATON ROUGE**

Event Code : **554155-1**

STRUCTURE ID. 282163	OCCUPANCY 26	EXT.	PARISH 17	BLDGS. 1	STORIES 1	# INSP. 1	BADGE 194	SCHED. INSP. DATE 11/13/2013	INSP. TYPE GE	ACT. INSP. DATE 11/13/2013	BEGIN TIME 09:00 AM
CONST. TYPE	FACILITY CODE Z-9999999	PROJECT ID. 433047-1	PROJECT TYPE ARCH	SMOKE DET <input type="checkbox"/> PARTL <input type="checkbox"/> COMP <input type="checkbox"/> NONE			FIRE ALARM <input type="checkbox"/> PARTL <input type="checkbox"/> COMP <input type="checkbox"/> NONE		HOOD <input type="checkbox"/> PARTL <input type="checkbox"/> COMP <input type="checkbox"/> NONE		CAPACITY
ANNIVERSARY DATE		YEAR BUILT 0	SQ. FOOTAGE 0		AUTO SPRK <input type="checkbox"/> PARTL <input type="checkbox"/> COMP <input type="checkbox"/> NONE			FIRE ALARM <input type="checkbox"/> PARTL <input type="checkbox"/> COMP <input type="checkbox"/> NONE		BLDG. POWER <input checked="" type="checkbox"/> GAS <input checked="" type="checkbox"/> ELECTRIC	
TRADE						OWNER					
NAME WOODHOUSE SPA						NAME ERIN WARNER					
ADDRESS I-10 @ PICARDY LANE						ADDRESS 796 INTERSTATE 10 SERVICE RD #230					
CITY BATON ROUGE			STATE LA			CITY SLIDELL			STATE LA		
ZIP 70802-		PHONE				ZIP 70461-		PHONE			
CODE SECTION	REQUIREMENTS (CODE VIOLATIONS)									CORRECTION DATE	
Note:	B2009reno										
(Comment)	Construction visit conducted at the request of the undersigned. Items discussed include, but may not be limited to, the following: (1) Concealed combustibles present above perimeter, storefront wall. This area shall be protected in accord. with NFPA 13. Any additional heads or added work shall be submitted to OSFM plan review. (2) Tenant separation wall shall be completed on both sides as shown on reviewed drawings. (3) Nail salon room shall comply with OSFM requirements, a copy of which was provided.										
(Continued...)											
Signature and Title of person to whom requirements were explained.						I, MARKJEWETT, hereby certify that this is a true report as a result of my inspection.					
						SIGNATURE OF INSPECTOR 				TIME OUT 10:30 AM	
R.S. 40:1621 Whoever fails to comply with any order issued by the Fire Marshal or his authorized representative under any provision of Part III, Chapter 7, of Title 40 of the Louisiana Revised Statutes of 1950, R.S. 40:1569 excepted, shall be fined not more than five hundred dollars or imprisoned, for not more than six months or both. Each day's violation of an order constitutes a separate offense and may be punished as such at the discretion of the court.											

SEE LAST PAGE OF ORDER FOR RIGHTS OF APPEAL.

DPSFM 7055 (Lotus Notes reproduction 11/99)

MARK.JEWETT@LA.GOV

March 20, 1998
(Revised)

**FIRE MARSHAL GUIDELINES FOR USE AND STORAGE
OF FLAMMABLE LIQUIDS IN NAIL SALONS**

The following guidelines apply to all Nail Salons. These guidelines provide an acceptable level of fire protection while continuing to meet the requirements of NFPA 101 Life Safety Code:

I. Ventilation

- A. Ventilation must be at a rate of not less than 1 cubic foot per minute (**1 CFM**) per square foot of floor area.
- B. Ventilation must be done by **mechanical means**, with discharge or exhaust to a safe external (outside) area without recirculation.
- C. Ventilation shall be **continuous** any time flammable liquids are utilized. Intake and Exhaust must take place from opposite sides of the room or building.

II. Storage and Handling

- A. All approved storage cabinets and storage areas must be rated for storage of flammable liquids.
- B. No more than **2 U.S. gallons** of flammable liquids may be kept in the facility at any time.
- C. All flammable liquids must be kept in storage cabinets when not in use.
- D. No more than **14 ounces** of flammable liquids (in closed containers) may be kept at work stations. Each station will be limited to not more than **7 ounces** of flammable liquids in open containers.

III. Disposal

- A. Disposal of flammable liquids must be in accordance with D.E.Q. regulations, in listed flammable liquid containers.
- B. Materials contaminated with flammable liquids shall be placed in **metal containers with self-closing cover devices**.

(Continued on Page 2)

IV. Open Flames

- A. No Smoking signs shall be posted on all walls in building.
- B. No cooking or open flames shall be permitted in building.
- C. Any fuel-fired equipment shall be enclosed in a 1 hour fire-rated enclosure.

Thank you for your continuing cooperation in this matter.

Sincerely,

V. J. Bella
State Fire Marshal

VJB/mlr