

DURA-RIB ROOF					
STANDARD		OPTIONAL LONG LIFE		OPTIONAL STAINLESS STEEL CAP	
ROOF SCREW	LAP SCREW	ROOF SCREW	LAP SCREW	ROOF SCREW	LAP SCREW
SD125W_ or #17A NO. 12-14 X 1 1/4 S.D. SCREW W/WASHER	SD87W_ or #4A 1/4-14 X 7/8 S.D. SCREW W/WASHER	SDW125_ or #3 NO. 12-14 X 1 1/4 S.D. SCREW W/WASHER	SDW87_ or #4 1/4-14 X 7/8 S.D. SCREW W/WASHER	SDW125S_ or #3SS NO. 12-14 X 1 1/4 S.D. SCREW W/WASHER	SDW87S_ or #4SS 1/4-14 X 7/8 S.D. SCREW W/WASHER
OPTIONAL LENGTH STANDARD		OPTIONAL LENGTH LONG LIFE		OPTIONAL LENGTH STAINLESS STEEL CAP	
ROOF SCREW	LAP SCREW	ROOF SCREW	LAP SCREW	ROOF SCREW	LAP SCREW
SD150W_ or #17B NO. 12-14 X 1 1/2 S.D. SCREW W/WASHER	SD87W_ or #4A 1/4-14 X 7/8 S.D. SCREW W/WASHER	SDW150_ or #3A NO. 12-14 X 1 1/2 S.D. SCREW W/WASHER	SDW87_ or #4 1/4-14 X 7/8 S.D. SCREW W/WASHER	SDW150S_ or #3ASS NO. 12-14 X 1 1/2 S.D. SCREW W/WASHER	SDW87S_ or #4SS 1/4-14 X 7/8 S.D. SCREW W/WASHER

DURA-RIB AND STARMARK WALL / WINDWARD PARTITION			
STANDARD		OPTIONAL STANDARD WITH WASHER	
WALL SCREW	LAP SCREW	WALL SCREW	LAP SCREW
SD125_ or #61 NO. 12-14 X 1 1/4 S.D. SCREW NO WASHER	SD87_ or #38 1/4-14 X 7/8 S.D. SCREW NO WASHER	SD125W_ or #17A NO. 12-14 X 1 1/4 S.D. SCREW W/WASHER	SD87W_ or #4A 1/4-14 X 7/8 S.D. SCREW W/WASHER
OPTIONAL LENGTH STANDARD		OPTIONAL LENGTH STANDARD WITH WASHER	
WALL SCREW	LAP SCREW	WALL SCREW	LAP SCREW
SD150_ or #60 NO. 12-14 X 1 1/2 S.D. SCREW NO WASHER	SD87_ or #38 1/4-14 X 7/8 S.D. SCREW NO WASHER	SD150W_ or #17B NO. 12-14 X 1 1/2 S.D. SCREW W/WASHER	SD87W_ or #4A 1/4-14 X 7/8 S.D. SCREW W/WASHER

NON-WINDWARD PARTITION	
PARTITION SCREW	LAP SCREW
SD125_ or #61 NO. 12-14 X 1 1/4 S.D. SCREW NO WASHER	SD50_ or #271 NO. 8-18 X 1/2 S.D. SCREW NO WASHER

LINER	
LINER SCREW	LAP SCREW
SD125_ or #61 NO. 12-14 X 1 1/4 S.D. SCREW NO WASHER	SD50_ or #271 NO. 8-18 X 1/2 S.D. SCREW NO WASHER

FACADE	
FACADE SCREW	LAP SCREW
SD125_ or #61 NO. 12-14 X 1 1/4 S.D. SCREW NO WASHER	SD87_ or #38 1/4-14 X 7/8 S.D. SCREW NO WASHER

SOFFIT	
SOFFIT SCREW	LAP SCREW
SD125_ or #61 NO. 12-14 X 1 1/4 S.D. SCREW NO WASHER	SD87_ or #38 1/4-14 X 7/8 S.D. SCREW NO WASHER

BACK PANEL	
BACK PANEL SCREW	LAP SCREW
SD125_ or #61 NO. 12-14 X 1 1/4 S.D. SCREW NO WASHER	SD87_ or #38 1/4-14 X 7/8 S.D. SCREW NO WASHER

NOTES:

(1.) SPECIAL COLORED AND NON STANDARD SCREW PART NUMBERS LISTED ON PACKING LIST AS SPEC_.

(2.) DURA-RIB ROOF/WALL AND STARMARK WALL FASTENER LENGTH; "STANDARD" 1 1/4" ROOF/WALL SCREWS FOR ATTACHING PANEL TO LIGHT STRUCTURAL STEEL MEMBERS (MAXIMUM .21" THICKNESS), ON NON-INSULATED OR INSULATED BUILDING WITH A NON-RIGID BLANKET INSULATION WITH AN "R" VALUE UP TO AND INCLUDING "R-13", UP TO 4" THICK. "OPTIONAL LENGTH" 1 1/2" ROOF/WALL SCREWS FOR ATTACHING PANEL TO LIGHT STRUCTURAL STEEL MEMBERS (MAXIMUM .21" THICKNESS), ON AN INSULATED BUILDING WITH A NON-RIGID BLANKET INSULATION WITH AN "R" VALUE GREATER THAN "R-13" BUT LESS THAN "R-19", UP TO 6" THICK.

STARSHIELD ROOF		
CLIP SCREW	STANDARD	
ATTACHMENT TO COLD FORMED FRAMING UP TO .21" MAXIMUM THICKNESS. (1 SCREW PER CLIP STANDARD, 2 SCREWS PER CLIP AT ROOF REQUIRING FACTORY MUTUAL APPROVAL.)	SPLICE SCREW	LAP SCREW
SD1415 or #142 1/4-14 X 1 1/2 (GALVALUME/ACRYLIC) S.D. SCREW NO WASHER	SD125W_ or #17A NO. 12-14 X 1 1/4 S.D. SCREW W/WASHER	SD87W_ or #4A 1/4-14 X 7/8 S.D. SCREW W/WASHER
ATTACHMENT TO BAR JOIST FRAMING AND LIGHT STRUCTURAL STEEL UP TO 1/2" MAXIMUM THICKNESS. (2 SCREWS PER CLIP TO BAR JOIST AND/OR FACTORY MUTUAL APPROVAL.)	OPTIONAL LONG LIFE	
SD125T4 or #6A NO. 12-24 X 1 1/4 (UNPAINTED) S.D. SCREW NO WASHER	SDW125_ or #3 NO. 12-14 X 1 1/4 S.D. SCREW W/WASHER	SDW87_ or #4 1/4-14 X 7/8 S.D. SCREW W/WASHER
ATTACHMENT TO BAR JOIST FRAMING AND LIGHT STRUCTURAL STEEL UP TO 1/2" MAXIMUM THICKNESS. (2 SCREWS PER CLIP TO BAR JOIST AND/OR FACTORY MUTUAL APPROVAL.)	OPTIONAL STAINLESS STEEL CAP	
SD125T5 or #55 NO. 12-24 X 1 1/4 (UNPAINTED) S.D. SCREW NO WASHER	SDW125S_ or #3SS NO. 12-14 X 1 1/4 S.D. SCREW W/WASHER	SDW87S_ or #4SS 1/4-14 X 7/8 S.D. SCREW W/WASHER

STRUCTURAL	
ATTACHMENT OF SHEETING ANGLES, SAG ANGLES, BRACE ANGLES, EAVE STRUT ADAPTORS, ETC. TO COLD FORMED AND LIGHT STRUCTURAL STEEL MEMBERS UP TO .21" MAXIMUM THICKNESS. (STANDARD UNLESS SPECIFIED OTHERWISE ON STANDARD AND/OR CUSTOM ERECTION DRAWINGS.)	SD125_ or #61 NO. 12-14 X 1 1/4 (GALVALUME/ACRYLIC) S.D. SCREW NO WASHER
ATTACHMENT OF SHEETING ANGLES, SAG ANGLES, BRACE ANGLES, EAVE STRUT ADAPTORS, ETC. TO COLD FORMED AND LIGHT STRUCTURAL STEEL MEMBERS UP TO 1/2" MAXIMUM THICKNESS. (USE ONLY AT LOCATIONS SPECIFIED ON STANDARD AND/OR CUSTOM ERECTION DRAWINGS.)	SD125T5 or #55 NO. 12-24 X 1 1/4 (UNPAINTED) S.D. SCREW NO WASHER
ATTACHMENT OF LIGHT STRUCTURAL STEEL MEMBERS AS SPECIFIED BY DESIGN. PRE-DRILLING HOLES (7/32"Ø) REQUIRED. (USE ONLY AT LOCATIONS SPECIFIED ON STANDARD AND/OR CUSTOM ERECTION DRAWINGS.)	SB125 11/32" SCRU-BOLT X 1 1/4 (UNPAINTED) S.T. SCREW NO WASHER

RIVETS	
POP 1/8"Ø POP RIVET (Aluminum Open End Rivet) (UNPAINTED)	#14
1/8"Ø x 3/16" POP RIVET (All Stainless Steel)	POPAL 3/16"Ø POP RIVET (Aluminum Closed End Rivet) (UNPAINTED)
BULBTITE 3/16"Ø DIAMETER BULB-TYPE RIVET (UNPAINTED) W/WASHER	

TRIM FASTENER	
STANDARD	
SD50_ or #271 NO. 8-18 X 1/2 S.D. SCREW NO WASHER	
OPTIONAL	
SD87_ or #38 1/4-14 X 7/8 S.D. SCREW NO WASHER	

Ch'd	By	Description	Date	Revision

STAR BUILDING SYSTEMS
An ISO Company

P.O. BOX 94910
OKLAHOMA CITY, OK 73143
(405) 656-2010

Project Name & Location:
PINNACLE CASINO -
MANHATTAN CONSTRUCTION
BATON ROUGE, LA

Customer:
CASEY CIVIL LLC
COMMERCIAL
MANDEVILLE, LA

Drawing Status:
 Preliminary
 (Not For Construction)
 For Approval
 (Not For Construction)
 For Construction Permit
 For Erector Installation

Scale: NOT TO SCALE

Drawn by:

Checked by:

Project Engineer:

Job Number: 12-B-63841

Sheet Number: R10 of 10

The engineer whose seal appears hereon is an employee for the manufacturer for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project.

FASTENER APPLICATION CHART	70.04.19
	08/28/08