



REBAR SPLICE


SCALE: 1/2" = 1'-0"



A SECTION
SCALE: 1/2" = 1'-0" EXTERIOR GRADE BEAM




B SECTION
SCALE: 1/2" = 1'-0" INTERIOR GRADE BEAM



C SECTION
SCALE: 1/2" = 1'-0" EXTERIOR GRADE BEAM

GENERAL FOUNDATION NOTES

- ALL DIMENSIONS ARE EDGE OF CONCRETE (EOC) TO EDGE OF CONCRETE (EOC) UNLESS NOTED OTHERWISE.
- VERIFY ALL PLUMBING ROUGH-IN LOCATIONS AND DOUBLE UP ON FLOOR JOIST IN THOSE AREAS.
- CONCRETE MIX SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI AT 28 DAYS. CONCRETE MIX SHALL BE IN ACCORDANCE WITH ACI-318.
- ALL CONVENTIONAL REINFORCING STEEL SHALL MEET ASTM-A615 (GRADE 60).
- ONE LAYER OF POLYETHYLENE VAPOR BARRIER SHALL BE PLACED UNDER ALL CONCRETE. VAPOR RETARDER TO BE MINIMUM 10 MIL THICKNESS; ASTM E 1745 CLASS A, PERMEANCE LESS THAN 0.01 PERMS, EQUAL TO STEGO INDUSTRIES STEGO WRAP, ECOSHIELD-E 15 MIL BY EPRO, OR IRONBAR 15 BY FLATIRON FILMS. PROVIDE APPROPRIATE ACCESSORIES FOR A COMPLETE SYSTEM.
- ALL REINFORCING STEEL AND MESH SHALL BE SECURELY SUPPORTED TO PREVENT BOTH VERTICAL AND HORIZONTAL MOVEMENT DURING CONCRETE PLACEMENT.
- THE CONTRACTOR SHALL VERIFY ALL DROPS, OFFSETS, BRICK LEDGES, DIMENSIONS AND CONFIGURATIONS.
- GRADE BEAM DIMENSIONS MAY VARY BY -5%, +20%.
- FILL, AS A MINIMUM QUALITY, SHALL BE 40% CLAY AND 60% SANDY MIXTURE, PLACED IN 6" LIFTS AND COMPACTED TO A MINIMUM OF 95% STANDARD PROCTOR. FOOTINGS ARE DESIGNED TO USE SOIL WITH A BEARING PRESSURE OF 2000 LBS. PER SQUARE FOOT OR MORE. IT IS RECOMMENDED THAT THE OWNER VERIFY ALLOWABLE SOIL BEARING PRESSURE CAPACITY BY CONTRACTING THE SERVICES OF A SOILS ENGINEERING COMPANY.
- ALL SOIL BELOW SLAB SHALL RECEIVE TERMITE TREATMENT.



FOUNDATION PLAN
SCALE: 1/2" = 1'-0"

DAMMON ENGINEERING, INC.
LOUISIANA & MISSISSIPPI

Chief Engineer: Brian Mistich, PE
554 Old Spanish Trail
Slidell, LA 70458
www.dammonengineering.com
info@dammon.com
PH: 985.649.5832

| REVISIONS | DATE |
|-----------|------|
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |



BRETT CABRIRAC


LOT 5 SQUARE 24
ROBERT STREET
SLIDELL, LA 70458

DATE: 01-24-2025
DRAWN BY: BAY
CHECKED BY: CSD


SHEET TITLE:
FOUNDATION PLAN

DRAWING NUMBER:
S101


SHEET No: 6 of 8




8 FRAMING PLAN
SCALE: 1/4" = 1'-0"



9 ROOF FRAMING PLAN
SCALE: 3/16" = 1'-0"



10 SECTION PLAN
SCALE: 1/4" = 1'-0"



11 STUCCO DETAIL
SCALE: N.T.S.

| NO. | DESCRIPTION | DATE |
|-----|-------------|------|
| | | |
| | | |
| | | |
| | | |
| | | |



BRETT CABRIRAC

LOT 5 SQUARE 24
ROBERT STREET
SLIDELL, LA 70456

JOB No: 01-24-2023
DATE: 01-24-2023
DRAWN BY: BAY
CHECKED BY: CAC

SHEET TITLE: FLOOR FRAMING AND SECTION
DRAWING NUMBER: **S102**

SHEET No: 7 of 8

TABLE S102.7 - HEADER SPANS FOR INTERIOR LOAD-BEARING WALLS

| HEADERS SUPPORTING | SIZE | DROPPED HEADER | | | RAISED HEADER | | |
|---|----------|----------------------|--------|--------|----------------------|--------|-------|
| | | BUILDING WIDTH (FT.) | | | BUILDING WIDTH (FT.) | | |
| | | 12 | 24 | 36 | 12 | 24 | 36 |
| ONE FLOOR ONLY (SINGLE CENTER BEARING WALL) | (2) 2x4 | 4'-0" | 2'-10" | 2'-4" | 4'-1" | 2'-10" | 2'-4" |
| | (2) 2x6 | 5'-11" | 4'-3" | 3'-5" | 6'-1" | 4'-4" | 3'-6" |
| | (2) 2x8 | 7'-1" | 5'-2" | 4'-4" | 7'-4" | 5'-5" | 4'-5" |
| | (2) 2x10 | 7'-11" | 6'-0" | 5'-0" | 9'-2" | 6'-6" | 5'-3" |
| | (2) 2x12 | 8'-6" | 6'-7" | 5'-7" | 10'-4" | 7'-7" | 6'-3" |
| | (3) 2x8 | 8'-5" | 6'-4" | 5'-3" | 9'-8" | 6'-10" | 5'-7" |
| | (3) 2x10 | 9'-3" | 7'-11" | 6'-10" | 11'-5" | 8'-11" | 6'-7" |
| | (3) 2x12 | 9'-11" | 7'-8" | 6'-7" | 13'-6" | 9'-6" | 7'-4" |
| | (4) 2x8 | 9'-5" | 7'-2" | 6'-0" | 11'-2" | 7'-11" | 6'-5" |
| | (4) 2x10 | 10'-3" | 7'-11" | 6'-4" | 13'-3" | 9'-4" | 7'-8" |
| (4) 2x12 | 11'-0" | 8'-7" | 7'-4" | 15'-7" | 11'-0" | 9'-0" | |

TABLE S102.8 - HEADER SPANS FOR EXTERIOR LOAD-BEARING WALLS RESISTING WIND LOADS EXP "C"

| SIZE | 120 MPH | 130 MPH | 140 MPH | 150 MPH | 160 MPH | 170 MPH | 180 MPH | 195 MPH |
|----------|---------|---------|---------|---------|---------|---------|---------|---------|
| (2) 2x4 | 5'-1" | 4'-8" | 4'-4" | 4'-1" | 3'-10" | 3'-7" | 3'-5" | 3'-2" |
| (2) 2x6 | 6'-3" | 5'-9" | 5'-4" | 5'-0" | 4'-8" | 4'-5" | 4'-2" | 3'-10" |
| (2) 2x8 | 6'-10" | 6'-4" | 5'-11" | 5'-6" | 5'-2" | 4'-10" | 4'-7" | 4'-3" |
| (2) 2x10 | 7'-4" | 6'-10" | 6'-4" | 5'-11" | 5'-6" | 5'-2" | 4'-11" | 4'-6" |
| (2) 2x12 | 7'-10" | 7'-3" | 6'-4" | 6'-3" | 5'-11" | 5'-7" | 5'-3" | 4'-10" |
| (3) 2x8 | 8'-5" | 7'-4" | 7'-2" | 6'-4" | 6'-4" | 5'-11" | 5'-7" | 5'-2" |
| (3) 2x10 | 9'-0" | 8'-4" | 7'-4" | 7'-3" | 6'-4" | 6'-4" | 6'-0" | 5'-7" |
| (3) 2x12 | 9'-7" | 8'-11" | 8'-3" | 7'-8" | 7'-3" | 6'-10" | 6'-5" | 5'-11" |
| (4) 2x8 | 9'-8" | 9'-0" | 8'-4" | 7'-4" | 7'-3" | 6'-10" | 6'-6" | 6'-0" |
| (4) 2x10 | 10'-5" | 9'-7" | 8'-11" | 8'-4" | 7'-10" | 7'-4" | 6'-11" | 6'-5" |
| (4) 2x12 | 11'-7" | 11'-1" | 10'-3" | 9'-6" | 8'-11" | 8'-4" | 7'-10" | 6'-10" |

TABLE S102.9 - SILL OR BOTTOM PLATE TO FOUNDATION CONNECTIONS RESISTING UPLIFT LOADS - 130 MPH WIND EXP "C"

| BOTTOM PLATE TO FOUNDATION ANCHOR BOLT CONNECTION RESISTING | FOUNDATION SUPPORTING | MAXIMUM ANCHOR BOLT SPACING (INCHES) | |
|---|-----------------------|--------------------------------------|---------------------|
| | | 8' END ZONES | INTERIOR ZONES |
| UPLIFT LOADS | 1 - 3 STORIES | 50 INCHES ON CENTER | 58 INCHES ON CENTER |

NOTE: A MINIMUM OF ONE ANCHOR BOLT SHALL BE PROVIDED WITHIN 6 TO 12 INCHES OF EACH END OF EACH PLATE

TABLE S102.10 - BOTTOM PLATE TO FOUNDATION CONNECTIONS (ANCHOR BOLTS) RESISTING LATERAL & SHEAR LOADS - EXP "C"

| BOTTOM PLATE TO FOUNDATION ANCHOR BOLT CONNECTION RESISTING | FOUNDATION SUPPORTING | MAXIMUM ANCHOR BOLT SPACING (INCHES) | |
|---|-----------------------|--------------------------------------|---------------------|
| | | 1/2" Ø ANCHOR BOLTS | 5/8" Ø ANCHOR BOLTS |
| UPLIFT LOADS | 1 STORY | 31 INCHES ON CENTER | 48 INCHES ON CENTER |

TABLE S102.11 - FULL HEIGHT STUD REQUIREMENT FOR HEADERS OR WINDOW SILL PLATES IN EXTERIOR WALLS EXP "C"

| HEADER SPAN (FEET) | WALL STUD SPACING (INCHES) | | |
|--------------------|----------------------------|----------|----------|
| | 12" O.C. | 16" O.C. | 24" O.C. |
| 2 | 1 | 1 | 1 |
| 4 | 2 | 2 | 1 |
| 6 | 3 | 3 | 2 |
| 8 | 4 | 3 | 2 |
| 10 | 5 | 4 | 3 |
| 12 | 6 | 5 | 3 |
| 14 | 7 | 6 | 4 |
| 16 | 8 | 6 | 4 |




TABLE S102.5 - JACK STUD REQ - INT LOADBEARING WALLS

| HEADER SUPPORTING | HEADER SPAN (FT) | ROOF SPAN (FEET) | | | | | | | | | | | |
|---------------------------------|------------------|------------------|---|---|---------|---|---|---------|---|---|---|---|---|
| | | 12 FEET | | | 24 FEET | | | 36 FEET | | | | | |
| | | HEADER WIDTH | | | | | | | | | | | |
| ONE FLOOR ONLY (CENTER BEARING) | 2 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| | 4 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| | 6 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 2 | 1 | 1 |
| | 8 | 1 | 1 | 1 | 1 | 2 | 1 | 1 | 1 | 2 | 2 | 2 | 1 |
| | 10 | 1 | 1 | 1 | 1 | 2 | 2 | 1 | 1 | 3 | 2 | 2 | 2 |
| | 12 | 1 | 1 | 1 | 1 | 2 | 2 | 2 | 1 | 3 | 2 | 2 | 2 |
| | 14 | 2 | 1 | 1 | 1 | 3 | 2 | 2 | 2 | 4 | 3 | 3 | 2 |
| | 16 | 2 | 1 | 1 | 1 | 3 | 2 | 2 | 2 | 4 | 3 | 3 | 2 |
| | 4 | 1 | 1 | 1 | 1 | 2 | 1 | 1 | 1 | 3 | 2 | 2 | 2 |
| | 6 | 2 | 1 | 1 | 1 | 3 | 2 | 2 | 2 | 4 | 3 | 2 | 2 |
| TWO FLOORS (CENTER BEARING) | 2 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| | 4 | 1 | 1 | 1 | 1 | 2 | 1 | 1 | 1 | 3 | 2 | 2 | 2 |
| | 6 | 2 | 1 | 1 | 1 | 3 | 2 | 2 | 2 | 4 | 3 | 2 | 2 |
| | 8 | 2 | 2 | 1 | 1 | 3 | 2 | 2 | 2 | 5 | 3 | 3 | 3 |
| | 10 | 2 | 2 | 2 | 1 | 4 | 3 | 3 | 2 | 6 | 4 | 4 | 3 |
| | 12 | 3 | 2 | 2 | 2 | 5 | 3 | 3 | 3 | 7 | 5 | 4 | 4 |
| | 14 | 3 | 2 | 2 | 2 | 6 | 4 | 4 | 3 | 8 | 5 | 5 | 4 |
| | 16 | 4 | 3 | 2 | 2 | 6 | 4 | 4 | 3 | 9 | 6 | 6 | 5 |

TABLE S102.6 - JACK STUD REQ - EXTERIOR LOADBEARING WALLS

| HEADER SUPPORTING | HEADER SPAN (FT) | ROOF LIVE LOAD 20 PSF | | | | GROUND SNOW LOAD 30 PSF | | | | | |
|---|------------------|-----------------------|------|----|----|-------------------------|------|----|----|---|---|
| | | 3" | 4.5" | 5" | 6" | 3" | 4.5" | 5" | 6" | | |
| ROOF AND CEILING | 2 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| | 4 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| | 6 | 2 | 1 | 1 | 1 | 2 | 1 | 1 | 1 | 1 | 1 |
| | 8 | 2 | 2 | 2 | 1 | 2 | 2 | 2 | 1 | 1 | 1 |
| | 10 | 3 | 2 | 2 | 2 | 3 | 2 | 2 | 2 | 2 | 2 |
| | 12 | 3 | 2 | 2 | 2 | 3 | 2 | 2 | 2 | 2 | 2 |
| | 14 | 4 | 3 | 2 | 2 | 4 | 3 | 2 | 2 | 2 | 2 |
| | 16 | 4 | 3 | 3 | 2 | 4 | 3 | 3 | 2 | 2 | 2 |
| | 2 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| | 4 | 2 | 1 | 1 | 1 | 2 | 1 | 1 | 1 | 1 | 1 |
| ROOF, CEILING, AND ONE CENTER BEARING FLOOR | 6 | 2 | 2 | 2 | 1 | 3 | 2 | 2 | 2 | 2 | 2 |
| | 8 | 3 | 2 | 2 | 2 | 3 | 2 | 2 | 2 | 2 | 2 |
| | 10 | 4 | 3 | 2 | 2 | 4 | 3 | 3 | 2 | 2 | 2 |
| | 12 | 4 | 3 | 3 | 2 | 5 | 3 | 3 | 3 | 3 | 3 |
| | 14 | 5 | 4 | 3 | 3 | 5 | 4 | 3 | 3 | 3 | 3 |
| | 16 | 6 | 4 | 3 | 3 | 6 | 4 | 4 | 3 | 3 | 3 |

HEADER WIDTH - 3" (2-2X), 4.5" (3-2X), 5", 6.5" (4-2X) EACH 1/2" PLYWOOD SPACER BETWEEN




TABLE S102.3 - NAILING SCHEDULE

| DESCRIPTION | NUMBER OF COMMON NAILS | NUMBER OF BOX NAILS | SPACING |
|---|------------------------|---------------------|--------------------|
| WALL FRAMING | | | |
| TOP PLATE TO TOP PLATE (FACE NAILED) | 2-16d | 2-16d | PER FOOT |
| TOP PLATE AT INTERSECTION (FACE) | 4-16d | 5-16d | JOINTS - EACH SIDE |
| STUD TO STUD (FACE-NAILED) | 2-16d | 2-16d | 24" O.C. |
| HEADER TO HEADER (FACE NAILED) | 16d | 16d | 16" O.C. EDGES |
| TOP OR BOTTOM PLATE TO STUD (END) | SEE TABLE | SEE TABLE | PER STUD |
| BOTTOM PLATE TO FLOOR JOIST, BANDJOIST, END JOIST OR BLOCKING | 2-16d | 2-16d | PER FOOT |
| ROOF SHEATHING | | | |
| WOOD STRUCTURAL PANELS | 8d | 10d | SEE TABLE S102.1 |
| DIAGONAL BOARD SHEATHING | | | |
| 1'x6" OR 1'x8" | 2-8d | 2-10d | PER SUPPORT |
| 1'x10" OR WIDER | 3-8d | 3-10d | PER SUPPORT |

TABLE S102.4 - BUILDING ENVELOPE REQUIREMENTS

| ROOFS | OPAQUE ELEMENTS | | ASSEMBLY MAXIMUM | INSULATION MIN. R-VALUE |
|--------------------|--------------------------------|----------------|------------------|-------------------------|
| | INSULATION ENTIRELY ABOVE DECK | METAL BUILDING | U-0.048 | R-20.0 c.i. |
| WALLS, ABOVE GRADE | METAL BUILDING | U-0.0265 | R-19 | |
| | ATTIC AND OTHER | U-0.027 | R-30 | |
| | MASS | U-0.151 @ | R-5.7 c.i. @ | |
| FLOORS | METAL BUILDING | U-0.113 | R-13.0 | |
| | STEEL-FRAMED | U-0.124 | R-13.0 | |
| | WOOD-FRAMED AND OTHER | U-0.089 | R-13.0 | |
| SLAB-ON-GRADE | MASS | U-0.107 | R6-3 c.i. | |
| | STEEL JOIST | U-0.052 | R-19.0 | |
| | WOOD FRAMED AND OTHER | U-0.051 | R-19.0 | |
| OPAQUE DOORS | UN-HEATED | F-0.130 | NR | |
| | SPRINGING | U-0.700 | NR | |
| | NON-SPRINGING | U-1.450 | NR | |

c.i. = CONTINUOUS INSULATION; NR = NO INSULATION REQUIREMENT
@ = EXCEPTION APPLIES

ROOF UNDERLAYMENT NOTES

- FOR ROOF SLOPES FROM TWO UNITS VERTICAL IN 12 UNITS HORIZONTAL (17-PERCENT SLOPE), UP TO FOUR UNITS VERTICAL IN 12 UNITS HORIZONTAL (33-PERCENT SLOPE), UNDERLAYMENT SHALL BE TWO LAYERS APPLIED IN THE FOLLOWING MANNER:
 - APPLY A 19 INCH STRIP OF UNDERLAYMENT FELT PARALLEL WITH AND STARTING AT THE EAVES, FASTENED SUFFICIENTLY TO HOLD IN PLACE. STARTING AT THE EAVE, APPLY 36 INCH WIDE SHEETS OF UNDERLAYMENT, OVERLAPPING SUCCESSIVE SHEETS 18 INCHES, AND FASTENED SUFFICIENTLY TO HOLD IN PLACE.
- FOR ROOF SLOPES OF FOUR UNITS VERTICAL IN 12 UNITS HORIZONTAL (33-PERCENT SLOPE) OR GREATER, UNDERLAYMENT SHALL BE ONE LAYER APPLIED IN THE FOLLOWING MANNER:
 - UNDERLAYMENT SHALL BE APPLIED SHINGLE FASHION, PARALLEL TO AND STARTING FROM THE EAVE AND OFFSET 2 INCHES, FASTENED SUFFICIENTLY TO HOLD IN PLACE. END LAPS SHALL BE OFFSET BY 6 FEET.

SHINGLE APPLICATION & FASTENING NOTES

- ASPHALT STRIP SHINGLES SHALL HAVE A MINIMUM OF SIX FASTENERS PER SHINGLE WHERE THE ROOF IS IN ONE OF THE FOLLOWING CATEGORIES:
 - THE BASIC WIND SPEED IS 110 MPH OR GREATER AND THE EAVE IS 20 FEET OR HIGHER ABOVE GRADE.
 - THE BASIC WIND SPEED IS 120 MPH OR GREATER.
 - SPECIAL WIND ZONES.

GENERAL UPLIFT CONNECTION NOTES

ROOF ASSEMBLY TO WALL ASSEMBLY:
UPLIFT CONNECTIONS SHALL BE FROM RAFTER OR TRUSS TO WALL STUD. WHEN RAFTERS OR TRUSSES ARE NOT LOCATED DIRECTLY ABOVE STUDS, RAFTERS SHALL BE ATTACHED TO THE WALL PLATE AND THE WALL TOP PLATE SHALL BE ATTACHED TO THE WALL STUD WITH UPLIFT CONNECTIONS. UPLIFT CONNECTIONS SHALL BE IN ACCORDANCE WITH TABLE S102.10.

WALL ASSEMBLY TO WALL ASSEMBLY:
STORY TO STORY UPLIFT CONNECTIONS FROM UPPER STORY WALL STUD TO LOWER STORY WALL STUD. WHEN UPPER STORY WALL STUDS ARE NOT LOCATED DIRECTLY ABOVE LOWER WALL STUDS, THE STUDS SHALL BE ATTACHED TO A COMMON MEMBER IN THE FLOOR ASSEMBLY BY UPLIFT CONNECTIONS. UPLIFT CONNECTIONS SHALL BE IN ACCORDANCE WITH TABLE S102.11.

WALL ASSEMBLY TO FOUNDATION:
FIRST FLOOR WALL STUDS SHALL BE CONNECTED TO THE FOUNDATION, SILL, PLATE, OR BOTTOM PLATE. A MINIMUM OF A 1-1/4" x 20 GA. ASTM A653 GRADE 33 STEEL STRAP SHALL BE NAILED TO THE WALL STUDS AND HAVE A MINIMUM EMBEDMENT OF 1 INCHES IN CONCRETE FOUNDATIONS AND SLABS-ON-GRADE, 15 INCHES IN MASONRY BLOCK FOUNDATIONS, OR BE LAPPED UNDER THE BOTTOM PLATE, 3 INCH SQUARE WASHERS SHALL BE USED ON THE ANCHOR BOLTS AND ANCHOR BOLT SPACINGS SHALL NOT EXCEED THE REQUIREMENTS. STEEL STRAPS EMBEDDED IN OR IN CONTACT WITH SLAB-ON-GRADE OR MASONRY BLOCK FOUNDATIONS SHALL BE HOT-DIPPED GALV. AFTER FABRICATION, OR MANUF. FROM G185 OR 2450 GALV. STL. CONNECTIONS SHALL BE IN ACCORDANCE WITH TABLE S102.12.

TABLE S102.1 - ROOF SHEATHING OR CLADDING REQUIREMENT - 130 MPH WIND LOAD EXP "C"

| SHEATHING LOCATION | RAFTER / TRUSS SPACING | MAX NAIL SPACING FOR 8d COMMON NAILS OR 10d BOX NAILS (INCHES OC) | |
|---------------------|------------------------|---|----|
| | | E | F |
| INTERIOR ZONE | 12" OC | 6 | 12 |
| | 16" OC | 6 | 12 |
| | 24" OC | 6 | 12 |
| PERIMETER EDGE ZONE | 12" OC | 6 | 12 |
| | 16" OC | 6 | 12 |
| | 24" OC | 6 | 6 |

110 MPH WIND - EXPOSURE 'C' TYPICAL
E = NAIL SPACING AT PANEL EDGES, INCHES.
F = NAIL SPACING AT INTERMEDIATE SUPPORTS IN THE PANEL FIELD, INCHES.

TABLE S102.2 - WALL SHEATHING OR CLADDING REQUIREMENT - 130 MPH WIND LOAD EXP "C"

| SHEATHING LOCATION | STUD SPACING | MAX NAIL SPACING FOR 8d COMMON NAILS OR 10d BOX NAILS (INCHES OC) | |
|---------------------|--------------|---|----|
| | | E | F |
| INTERIOR ZONE | 12" OC | 6 | 12 |
| | 16" OC | 6 | 12 |
| | 24" OC | 6 | 12 |
| PERIMETER EDGE ZONE | 12" OC | 6 | 12 |
| | 16" OC | 6 | 12 |
| | 24" OC | 6 | 12 |

110 MPH WIND - EXPOSURE 'C' TYPICAL
E = NAIL SPACING AT PANEL EDGES, INCHES.
F = NAIL SPACING AT INTERMEDIATE SUPPORTS IN THE PANEL FIELD, INCHES.

DESIGN CRITERIA
THE CONSTRUCTION FOR SAID RESIDENCE, WHERE BASIC WIND SPEED IS 130 MILES PER HOUR, WIND EXPOSURE ZONE C, IS DESIGNED IN ACCORDANCE WITH: AMERICAN FOREST AND PAPER ASSOCIATION (AF&PA) WOOD FRAME CONSTRUCTION MANUAL FOR ONE AND TWO FAMILY DWELLINGS (MFCM) 2001 EDITION AS WELL AS THE INTERNATIONAL RESIDENTIAL CODE (IRC) 2021 EDITION

DAMMON ENGINEERING, INC.

LOUISIANA & MISSISSIPPI

Chief Engineer: Brian Metch, PE
554 Old Spanish Trail
Slidell, LA 70458
www.dammonengineering.com
info@dammonengineering.com
PH: 985-649-5832

| # | DESCRIPTION | DATE |
|---|-------------|------|
| | | |
| | | |
| | | |

BRETT CABRERA

LOT 9 SQUARE 24
ROBERT STREET
SLIDELL, LA 70458
JOB NO: 07-24-2023
DATE: 07-24-2023
DRAWN BY: CKD
CHECKED BY: BAW

SHEET TITLE:
TYPICAL CONNECTION DETAILS, SCHEDULES, AND NOTES

DRAWING NUMBER:
S103

SHEET No: 5 of 8