



ROOF PLAN
SCALE 1/4" = 1'-0"

IRC REQUIREMENTS FOR ROOF ASSEMBLIES

- R905.10 METAL ROOF PANELS:** THE INSTALLATION OF METAL ROOF PANELS SHALL COMPLY WITH THE PROVISIONS OF THIS SECTION.
- R905.10.1 DECK REQUIREMENTS:** METAL ROOF PANEL ROOF COVERINGS SHALL BE APPLIED TO SOLID OR SPACED SHEATHING, EXCEPT WHERE THE ROOF COVERING IS SPECIFICALLY DESIGNED TO BE APPLIED TO SPACED SUPPORTS.
- R905.10.2 SLOPE:** MINIMUM SLOPES FOR METAL ROOF PANELS SHALL COMPLY WITH THE FOLLOWING.
1. THE MINIMUM SLOPE FOR LAPPED, NONSOLDERED-SEAM METAL ROOFS WITHOUT APPLIED LAP SEALANT SHALL BE THREE UNITS VERTICAL IN 12 UNITS HORIZONTAL (25-PERCENT SLOPE).
 2. THE MINIMUM SLOPE FOR LAPPED, NONSOLDERED-SEAM METAL ROOFS WITH APPLIED LAP SEALANT SHALL BE ONE-HALF VERTICAL UNIT IN 12 UNITS HORIZONTAL (4-PERCENT SLOPE). LAP SEALANTS SHALL BE APPLIED IN ACCORDANCE WITH THE APPROVED MANUFACTURER'S INSTALLATION INSTRUCTIONS.
 3. THE MINIMUM SLOPE FOR STANDING-SEAM ROOF SYSTEMS SHALL BE ONE-QUARTER UNIT VERTICAL IN 12 UNITS HORIZONTAL (2-PERCENT SLOPE).
- R905.10.3 MATERIAL STANDARDS:** METAL-SHEET ROOF COVERING SYSTEMS THAT INCORPORATE SUPPORTING STRUCTURAL MEMBERS SHALL BE DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL BUILDING CODE. METAL-SHEET ROOF COVERINGS INSTALLED OVER STRUCTURAL DECKING SHALL COMPLY WITH TABLE R905.10.3.01. THE MATERIALS USED FOR METAL-SHEET ROOF COVERINGS SHALL BE NATURALLY CORROSION RESISTANT OR PROVIDED WITH CORROSION RESISTANCE IN ACCORDANCE WITH THE STANDARDS AND MINIMUM THICKNESSES SHOWN IN TABLE R905.10.3.02.
- R905.10.4 ATTACHMENT:** METAL ROOF PANELS SHALL BE SECURED TO THE SUPPORTS IN ACCORDANCE WITH THIS CHAPTER AND THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. IN THE ABSENCE OF MANUFACTURER'S INSTRUCTIONS, THE FOLLOWING FASTENERS SHALL BE USED:
1. GALVANIZED FASTENERS SHALL BE USED FOR STEEL ROOFS.
 2. THREE HUNDRED SERIES STAINLESS STEEL FASTENERS SHALL BE USED FOR COPPER ROOFS.
 3. STAINLESS STEEL FASTENERS ARE ACCEPTABLE FOR METAL ROOFS.

ROOFING NOTES

1. ALL ROOF SHEATHING SHALL BE 15/32" EXPOSURE 1, 24/0 APA RATED PANELS. FASTEN WITH NAILS AT 6" O.C. AT ALL FRAMING MEMBERS.
2. METAL ROOF SHALL BE INSTALLED PER MANUF. SPECS. & RECOMMENDATIONS.
3. LOCATE WATER HEATER IN ATTIC OVER A WALL OR WITHIN 12 INCHES OF A WALL.
4. ROOF BRACING SUPPORT RAFTERS AS REQUIRED TO LIMIT SPANS PER NOTES ON DWG. A-0 WITH PURLINS OF EQUAL SIZE AS RAFTERS SUPPORT PURLING WITH 2x BRACING AT 4FT MAX SPACING. NOT ALL PURLING & BRACING SHOWN.

ROOF PLAN

PLANS FOR:
JEFF LAPORTE MECHANICAL CO.
LOT 5, PINEWOOD PARK
EAST, ST. TAMMANY PARISH, LA

DATE:
4-8-21

DesignTech
Residential Planners, Inc.
St. Tammany Parish, LA.

COVINGTON 985-871-7211 SLIDELL 985-847-0600

CODE	LIVING	AREA U. B.	INDEX
A3	1815	3047	12471

DESIGNED BY	DRAWN BY	CHECKED BY	REVISED
DMH	JMC	DMH	4-23-21

A-3

© Copyright, 2021, an unpublished work by DesignTech Residential Planners, Inc. ALL RIGHTS RESERVED.
EMAIL: houseplans@designtechusa.com

Although every effort has been made in preparing these plans, the contractor must check all details for accuracy or errors and be responsible for same. Purchaser assumes the risk of any errors, omissions or mistakes during construction due to the fact that DesignTech does not perform field supervision nor select building materials, subcontractors and/or products/equipment. All notes, specifications and other information on the plans are included as instructed by and/or with the approval of Purchaser and without warranty of any kind whatsoever. PLANS HAVE BEEN PREPARED FOR USE BY KNOWLEDGEABLE AND EXPERIENCED LICENSED CONTRACTORS. This drawing contains valuable, confidential, proprietary, trade secret information of DesignTech Residential Planners, Inc. No reproduction or other use of the drawing or any of its contents is permitted without consent of DesignTech Residential Planners, Inc.