



SPECIFIC NOTES THIS SHEET:

1 CONTINUE TO SECOND FLOOR STAIRWAY LIGHT FIXTURES.

- GENERAL NOTES THIS SHEET:**
1. ALL FIXTURES TYPE E UNLESS NOTED OTHERWISE.
 2. ALL WIRING SHALL BE 3/4" C: 2-#12 AWG AND 1-#12 GRD UNLESS NOTED OTHERWISE.
 3. ALL CONDUIT SHALL CONTAIN MINIMUM #12 AWG GROUND WIRE UNLESS NOTED OTHERWISE.
 4. ALL MOUNTING HEIGHTS SHOWN ARE TO BOTTOM OF FIXTURE. WHERE MOUNTING HEIGHTS FOR FIXTURES VARY, REFERENCE DIMENSION NEXT TO FIXTURE.
 5. MOUNT TYPE E FIXTURES IN CAGES 105, ELEC 113, AND MECH 114 AT 10'-0" AFF.
 6. MOUNT TYPE E FIXTURES IN ARMORY 107 AT 8'-6" AFF.
 7. FOR TYPE I FIXTURES IN HEAD 109 AND 111, REFERENCE ARCHITECTURAL ELEVATIONS FOR MOUNTING HEIGHT.

OPERATIONS/MAINTENANCE BLDG 2440/2441
 SCALE: 1/8"=1'-0"
 0 4 8 16'
 PLAN NORTH

THESE PLANS AND SPECIFICATIONS HAVE BEEN PREPARED BY OR UNDER OUR DIRECT SUPERVISION, AND WE ARE AWARE OF ALL REGULATORY REQUIREMENTS. WE ARE NOT GENERALLY ADMINISTERING THE WORK.

SCHLAFLY ENGINEERING LLC
 PER: [Signature]
 REG. # 27699

<p>SCHLAFLY ENGINEERING LLC 121 SOUTH GENOIS STREET NEW ORLEANS, LA 70119 PH: 504-885-7947 FAX: 504-885-7930 M. KIMBALL SCHLAFLY, P.E. LA REG 27699</p>		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND NAVAL AIR STATION JACKSONVILLE MISSISSIPPI JOHN C. STENNIS SPACE CENTER	NAVAL FACILITIES ENGINEERING COMMAND NAVAL AIR STATION JACKSONVILLE MISSISSIPPI SOF RIVERINE AND COMBATANT CRAFT OPERATIONS FACILITY BLDG 2440/2441 1ST FLOOR - LIGHTING
		DESIGNED BY: R. WILSON CHECKED BY: T. ARMBR CHIEF ENGINEER: P. DAMON	DATE: SEPTEMBER 4, 2009