

GENERAL NOTES

1. INSULATION AND INSULATION ASSEMBLIES SHALL MEET THE REQUIREMENTS OF SECTION 719.
- A. CONCEALED INSULATION SHALL HAVE A FLAME SPREAD OF 0-25 AND SMOKE DEVELOPED INDEX OF 0-450. EXCEPT THAT IN COMBUSTIBLE (WOOD FRAME) CONSTRUCTION.
- B. FACING SHALL COMPLY WITH IBC 2006.
2. CONTRACTOR TO VERIFY ALL SITE CONDITIONS AND DIMENSIONS PRIOR TO CONSTRUCTION.
3. MATERIALS SHALL BE NEW AND U.L. LISTED.
4. NO WORK SHALL BE CONCEALED UNTIL APPROVED BY LOCAL INSPECTORS.
5. CONSTRUCTION SHALL COMPLY WITH ALL PARISH, STATE, AND LOCAL CODES.
6. CONTRACTOR TO GUARANTEE WORK FOR ONE YEAR.
7. CONTRACTOR SHALL FURNISH WATER AND POWER FROM EXISTING SOURCES.
8. ANY EXTERIOR CAULKING SHALL BE THIOKAL CAULK.
9. PAINT GRADE TO SHALL BE SHERWIN WILLIAMS OR EQUIVALENT. ALL WORK TO RECEIVE 3 COATS. COLOR SELECTION BY OWNER.
10. PROVIDE CLEANUP ON A REGULAR BASIS. NO TRASH STORED IN BUILDING.
11. USE 6" STUDS, OR 4" STAGGERED STUDS AT ALL PLUMBING WALLS.
12. PROVIDE GALVANIZED METAL PAN WITH DRAIN AT WATER HEATER LOCATION.
13. INTERIOR LOCKS ON DOORS IN MEANS OF EGRESS SHALL NOT REQUIRE THE USE OF A KEY, SPECIAL KNOWLEDGE, OR SPECIAL DEVICE TO OPEN IN THE DIRECTION OF EGRESS.
- ALL DOORS SHALL HAVE LEVER TYPE HANDLES.
14. INTERIOR WALLS AND CEILINGS SHALL HAVE A FLAME SPREAD OF 0-200 AND A SMOKE DEVELOPMENT RATING OF 0-450.
15. ALL WORK SHALL COMPLY WITH THE LATEST EDITION OF ALL LOCAL, STATE, AND NATIONAL CODES COVERING THE TYPE OF WORK BEING PERFORMED.
16. PROVIDE PORTABLE FIRE EXTINGUISHERS IN ACCORDANCE WITH NFPA 101. SEE APPENDIX "E" OF NFPA 101 FOR DISTRIBUTION OF EXTINGUISHERS.
17. ALL FIRE WALLS SHALL EXTEND TIGHT TO ROOF DECK AND BE SEALED WITH AN APPROVED FIRE CAULK.
18. ALL ELECTRICAL, MECHANICAL, AND PLUMBING MATERIALS PENETRATING FIRE WALLS SHALL BE FIRE CAULKED. (PENETRATIONS THROUGH RATED CONSTRUCTION SHALL BE SEALED WITH A MATERIAL CAPABLE OF PREVENTING THE PASSAGE OF FLAMES AND HOT GASES WHEN TESTED IN ACCORDANCE WITH ASTM-E814.)

DOOR & HARDWARE SCHEDULE


NO.	SIZE	TYPE		FRAME	HINGE	LOCK			ACCESS.			REMARKS												
		S. C. WOOD	H. C. WOOD	BI-FOLD	SOUND BI-FOLD	ROLL-UP DOOR	ALUMINUM	HOLLOW METAL	STEEL	BUTT	TRACK		NONE	PASSAGE	PRIVACY	DEADBOLT	KEYED HANDLE	PUSH FULL	NONE	THRESHOLD	WEATHERSTRIP	DOOR STOP	CLOSER	EXISTING VIEW LITE
1	3/0x8/0	●																						SEE NOTE #1
2	2/0x7/0			●																				BIFOLD CLOSET DOOR
3	3/0x7/0	●																						SEE NOTE #2
4	3/0x7/0	●																						SEE NOTE #3
5	3/0x7/0	●																						SEE NOTE #4
6	4/0x7/0	●																						1 HR. FIRE-RATED DOOR
7	3/0x7/0	●																						1 HR. FIRE-RATED DOOR
8	PR. 2/4x7/0			●																				BIFOLD CLOSET DOOR
9	PR. 3/0x7/0			●																				BIFOLD CLOSET DOOR
10	PR. 2/6x7/0			●																				SEE NOTE #5
11	10' WIDE			●																				SEE NOTE #6

NOTES:

1. 3'-0"x8'-0" EXISTING DOOR WITH ALUMINUM FRAME RE-USED FROM EXISTING FLOOR PLAN.
2. 3'-0"x7'-0" EXISTING DOOR WITH HOLLOW METAL FRAME & VIEW LITE RE-USED FROM EXISTING FLOOR PLAN.
3. 3'-0"x7'-0" EXISTING RESTROOM DOOR RELOCATED FROM EXISTING FLOOR PLAN.
4. NEW 3'-0"x7'-0" DOOR TO MATCH ALL EXISTING RESTROOM DOORS.
5. NEW PAIR OF 2'-6" BIFOLD "SOLID, SOUND-PROOF" DOORS.
6. NEW OVERHEAD ROLL-UP DOOR TO BE CHAIN OPERATED AND TO MATCH OTHER EXISTING ROLL-UP DOORS ON REAR OF BUILDING. VERIFY SIZE W/OWNER PRIOR TO ORDER AND INSTALLATION OF SAME.

ROOM FINISH SCHEDULE

NAME	FLOOR			BASE			WALL			CEILING			REMARKS	
	CARPET TILE	V.C.T.	CERAMIC TILE	SHEET VINYL	CONC. W/SEALER	VINYL BASE	CERAMIC TILE	NONE	GYP. ED. PAINTED	CERAMIC TILE TO 42" HT.	FRP	2"x2" SUSP. ACoust.		GYP. ED. PAINTED
WAITING AREA	●													EXISTING
BRANCH MANAGER	●													EXISTING
OPS MANAGER	●													EXISTING
BREAK ROOM		●												EXISTING
COPY/FAX AREA	●													EXISTING
WORK AREA	●													EXISTING
CORRIDOR	●													EXISTING
REPAIR ROOM		●												EXISTING
MENS RESTROOM			●											EXISTING
WOMENS RESTROOM			●											EXISTING
CORRIDOR	●													EXISTING
CORRIDOR	●													EXISTING
CONFERENCE ROOM	●													EXISTING
JANITOR		●												EXISTING
PHONE ROOM		●												EXISTING
NEW REPAIR ROOM		●												EXISTING
STORAGE		●												EXISTING
MENS RESTROOM			●											EXISTING
WOMENS RESTROOM			●											EXISTING
CORRIDOR	●													EXISTING
CORRIDOR	●													EXISTING
MEETING ROOM	●													EXISTING
CLOSET		●												EXISTING
CLOSET		●												EXISTING
EQUIPMENT SPECIALIST	●													EXISTING
EQUIPMENT SPECIALIST	●													EXISTING
CORRIDOR	●													EXISTING
MEDICAL DISPLAY AREA			●											EXISTING
CORRIDOR	●													EXISTING
CLOSET		●												EXISTING
CORRIDOR	●													EXISTING
CORRIDOR	●													EXISTING
NEW BREAK ROOM		●												EXISTING
NEW CEREC STG.	●													EXISTING
CORRIDOR	●													EXISTING
EQUIPMENT SPECIALIST	●													EXISTING
RECEPTION	●													EXISTING
FOYER	●													EXISTING
EQUIPMENT SPECIALIST	●													EXISTING
CORRIDOR	●													EXISTING
EXISTING CONFERENCE	●													EXISTING
COPY/SUPPORT	●													EXISTING
CUSTOMER SERVICE	●													EXISTING
CUSTOMER SERVICE	●													EXISTING
BOOK KEEPERS	●													EXISTING
CORRIDOR	●													EXISTING
BRANCH MANAGER	●													EXISTING
OPS MANAGER	●													EXISTING
SERVICE MANAGER	●													EXISTING
SVC. SCHED.	●													EXISTING
CORRIDOR	●													EXISTING
PARTS	●													EXISTING
SALES/TECHS	●													EXISTING
ORDER/ASSEMBLY				●									●	OPEN TO DECK
DENTAL WAREHOUSE				●									●	OPEN TO DECK
MEDICAL WAREHOUSE				●									●	OPEN TO DECK



DAMMON ENGINEERING, INC.

CHIEF ENGINEER
EMMETT
DAMMON, P.E.

CHIEF ARCHITECT
ROBERT
WILTSE

1095 FLORIDA AVENUE
SLIDELL, LA. 70458
OFFICE: 985-649-5832
FAX: 985-641-5950

WEBSITE:
WWW.DAMMONENGINEERING.COM

EMAIL:
DAMMONENG@BELLSOUTH.NET

ARCHITECTURE

ENGINEERING

STUDIES

PLANNING

INVESTIGATION

EXPERT WITNESS

OFFICE &
WAREHOUSE
EXPANSION &
RENOVATION

PATTERSON
DENTAL SUPPLY
107 MALLARD ST.
SAINT ROSE, LA
70087

SCHEDULES
& NOTES

REV:

SCALE: AS NOTED

JOB#: 2076

DATE: 11-05-10

SHEET 5

A-2

PRELIMINARY (NOT FOR CONSTRUCTION)

OF 11