

- 1) The dwgs have been revised to state the 140 mph with 3-second gust.
- 2) The laundry room walls shall be rated to the underside of the deck and shall be sprinkled.
- 3) All exterior walls shall be rated using the design #U356. See detail on the revised plans.
- 4) Contractor shall comply.
- 5) Contractor shall comply.
- 6) All corridor walls shall be separated from the floor to the under side of the deck using GA file #WP3514.
- 7) All walls separating the units shall be rated from the floor to the bottom of the deck using GA file #WP3514.
- 8) See sheet A-5 for the draft compartments that are installed every 3000 s.q. ft. And we are also using exception #3 of section 717.4.2.
- 9) 5% of the rooms are required to be accessible.  
We have a total of three rooms that are accessible.
- 10) Contractor shall comply.
- 11) Dwgs are revised to meet current standards.
- 12) Contractor shall supply shop drawings for the sprinkler system and submit for approval to the city of Biloxi fire prevention department.