

GLAZED PORCELAIN

PALATINA™



daltile[®]
DESIGN WITH CONFIDENCE™

PALATINA™

GLAZED PORCELAIN



floor • wall • countertop

Enjoy the best of both worlds with Daltile's Palatina Glazed Porcelain Collection. Featuring a natural travertine visual with balanced graphic movement and color variation; this unique tile collection gives off the look and elegance of natural stone, but with the ease of maintenance of ceramic tile. Available in an array of complementary neutral colors, this tile adds warmth and style to any room.

floor • wall • countertop

PALATINA™

GLAZED PORCELAIN

Field Tile



CORINTH CREAM PT95



TEMPLE BEIGE PT96



OLYMPUS BROWN PT97

CREATIVE IDEAS

Color			
	CORINTH CREAM PT95	TEMPLE BEIGE PT96	OLYMPUS BROWN PT97
Accent			
	FASHION ACCENTS DAMASK LIGHT FA14 Decorative Accent 2 x 8	MASSALIA COPPER MS92 Frieze Accent Strip 1 x 6	FASHION ACCENTS ILLUMINI LAKE F015 Decorative Accent 12 x 12

Backsplash Design Ideas



Backsplash features Olympus Brown 12 x 12 field tile with Stonegate 2 x 12 decorative accent.

Pattern Ideas



BRICK PATTERN



DIAMOND



CHECKERBOARD



Photo features Temple Beige 12 x 12 field tile.

PALATINA™

GLAZED PORCELAIN

SIZES

		SQ.FT. CARTON	PIECES PER CARTON
18 x 18 Field Tile	(17-1/2" x 17-1/2") (44.53 cm x 44.53 cm)	17.38	8
12 x 12 Field Tile	(11-1/2" x 11-1/2") (29.56 cm x 29.56 cm)	9.90	10

RESIDENTIAL USAGE

FLOORS	WALLS	COUNTERTOPS	EXTERIOR PATIOS	EXTERIOR POOL DECKS
F	W	C	EP	

COMMERCIAL USAGE

	INTERIOR			EXTERIOR	
	RESIDENTIAL	LIGHT COMMERCIAL	COMMERCIAL	RESIDENTIAL	COMMERCIAL
Floors/Patios	✓	✓	✓	✓	
Walls/Backsplashes	✓	✓	✓	✓	✓
Countertops	✓	✓	✓	✓	✓
Pool Decking					
Pool Linings	✓	✓	✓	✓	✓

Suitable for freezing and non-freezing climates when proper installation methods are followed.

NOTES

Use of a latex modified thin-set is recommended for installation.

Since there are variations in all fired ceramic products, the tile and trim supplied for your particular installation may not match these samples. Final color selection should be made from actual tiles and trim and not from tile and trim samples or color reproductions. Manufactured in accordance with ANSI A137.1 standards.

For additional information refer to "Factors to Consider" at: www.daltile.com/CommercialFactors.

Application requirements vary for decorative tile.

Water, oil, grease etc. create slippery conditions. Floor applications with exposure to these conditions require extra caution in product selection. Not for use on ramps.

TRIM

TYPE	NUMBER	SIZE	PCS. PER CARTON
Bullnose	S-43C9	3 x 12	30

SHADE VARIATION



HIGH (V3)

Color variation from tile to tile and within each tile.

INSTALLATION

THICKNESS	GROUT JOINT RECOMMENDATION
3/8"	3/16" Floor

SLIP RESISTANCE (WET) : 3

The higher the rating, the higher the slip resistance.

1	< .50
2	.50 - .59
3	≥ .60

TEST RESULTS

	ASTM#	RESULT
Water Absorption	C373	<0.5%
Breaking Strength	C648	325 lbs
Scratch Hardness	MOHS	8.0
Chemical Resistance	C650	Resistant
Coefficient of Friction	C1028	Wet: ≥0.60 Dry: ≥0.70
Abrasion Resistance	C1027	4



daltile
greenworks™
ENVIRONMENTAL LEADERSHIP THAT WORKS

By their very design, Daltile products can help make it easier for you to earn LEED™ points and/or points towards many industry leading green home building programs. From using recycled material content to establishing manufacturing facilities within 500 miles of your project, we help ensure you don't have to compromise your design to be environmentally conscious. For detailed information, visit daltilegreenworks.com.



EXTERIOR
PRODUCT

CERTIFIED
PORCELAIN™
TILE
0.05% or less water absorption



7834 C. F. Hawn Freeway | Dallas, TX 75217 | 214.398.1411 800.933.TILE

For more information about Daltile products and services, visit our website at daltile.com



daltile®

©2011 Dal-Tile Corporation (311) 55DTPALATINA