



ADDENDUM NO. 1

15 March 2013

Textron Marine & Land Systems
Building #3 - 2nd Floor Renovations
19401 Chef Menteur Hwy.
New Orleans, LA 70129

1. Specification Section 09680 Carpet, Part 2, Paragraph 2.1, Replace "12' wide broadloom" with 22 Oz. Carpet Tile.
2. Rooms 240 IT Help Desk; 241 Server Room & 251 Mis Lan Hub Area shall have a Clean Room Ceiling System.
3. Sheet A-3, Interior Wall #1 detail – existing wall height is approximately 10', new wall height above is approximately 10'. Use 20 gauge hat channels. Use standard 20 gauge 3-5/8" drywall studs.
4. Sheet A-3, Interior Wall #2 detail – Use standard 20 gauge 3-5/8" drywall studs.