

1858

STATE OF LOUISIANA
Department of Public Safety and Corrections
Office of State Fire Marshal Code Enforcement and Building Safety
8181 Independence Boulevard
Baton Rouge, Louisiana 70806
225-925-4920

H "BUTCH" BROWNING
FIRE MARSHAL

AMENDED LETTER

ROBERT WILTSE, ARCHITECT
DAMMON ENGINEERING INC
1095 FLORIDA AVE
SLIDELL, LA 70458-0000

RE: P0358362
PLATFORM CRANE
60461 DOSS DRIVE
SLIDELL, LA 70458

NFPA 101, 2006

BUSINESS

Dear Applicant:

This is to advise that the previous review letter dated 12/17/2008 for this project is hereby amended as follows:

- 1. **13:11.2.3.3 Room Design Method.**
 - 13:11.2.3.3.3 To utilize the room design method, all rooms shall be enclosed with walls having a fire-resistance rating equal to the water supply duration indicated in Table 11.2.3.1.2.**
 - 13: 11.2.3.3.5 Minimum protection of openings shall be as follows:**
 - (1) Light hazard -- non-rated automatic or self closing doors
 - (2) Light hazard with no opening protection -- Where openings are not protected, calculations shall include the sprinklers in the room plus two sprinklers in the communicating space nearest each such unprotected opening unless the communicating space has only one sprinkler, in which case calculations shall be extended to the operation of that sprinkler. The selection of the room and communicating space sprinklers to be calculated shall be that which produces the greatest hydraulic demand. For light hazard occupancies with unprotected openings in walls, a minimum lintel depth of 8 in. is required for openings and the opening shall not exceed 8 ft in width. It shall be permitted to have a single opening of 36 in or less without a lintel, provided there are no other openings to adjoining spaces.
 - (3) Ordinary and extra hazard -- Automatic or self-closing doors with appropriate fire-resistance ratings for the enclosure.

NOTE : 13:11.2.3.1.3 The lower duration value of Table 11.2.3.1.2 shall be acceptable only where the sprinkler system waterflow alarm device(s) and supervisory device(s) are electrically supervised and such supervision is monitored at an approved, constantly attended location.

POR document compliance with the room design mwthod to the inspector

- 2. **NOTE: Please enclose a copy of this letter with future submittals or other correspondence pertaining to this project.**

This review applies to the work indicated on the drawings or specifications.

This review shall in no way permit or authorize any omissions or deviations from the specific requirements of the adopted codes, rules and regulations in accordance with R.S. 40:1574.1(B).

The above amended review is valid if construction starts within 180 days from the above date of the original review letter.

Occupancy of the project will not be permitted until we receive the completed certificate and a satisfactory inspection of the completed construction has been made by this office.

To arrange for inspection of the project, please contact the District Office at the phone number below, two (2) to three (3) weeks in advance. Approved plans must be available on job site at time of inspection. Certificate of completion must be provided to inspecting Deputy for final inspection.

REVIEWED BY:
DONNA LEBLANC
MECHANICAL ENGINEER

CC:
Rdg Properties
Jefferson Sprinkler Inc
Property Insurance Association*
St Tammany Fire Protection District No 1*
City Of Slidell*
New Orleans District* 5042194600