

LEGEND	
A	#5 @ 6" O.C. @ C/L SLAB
B	#5 @ 8" O.C. @ C/L SLAB
C	#4 @ 12" O.C. @ 3'-6"
D	#4 @ 12" O.C.
E	#3 @ 12" O.C.
F	#3 @ 12" O.C. EACH WAY, BOTTOM.
B-1	2-#5 T&B W/ 2 #3 @ 6" EACH END REMAINDER @ 24" O.C. (W=16", D=16")
B-2	3-#5 T&B W/ 2 #3 @ 6" EACH END REMAINDER @ 24" O.C. (W=24", D=16")

NOTE:
C.J. = CONTROL JOINT
TERMINATE BEAM & SLAB REINFORCING AT C.J.

- NOTES:
- ALL PILING TREATED ASTM D25 W/ 8" MIN. BUTT & 6" MIN. TIP DRIVEN 40" BELOW EXISTING GROUND SURFACE.
 - CONCRETE: $f'_c = 4000$ PSI @ 28 DAYS.
ALL PUMPED CONCRETE TO CONTAIN HIGH RANGE WATER REDUCER.



FOUNDATION PLAN AT POOL

1/8" = 1' - 0"

Waggoner & Ball Architects
 2200 PRYTHANA STREET
 NEW ORLEANS, LOUISIANA 70130
 T 504-524-5308 F 504-524-5314
 www.wabarchitects.com

COPYRIGHT © 2009 by Waggoner & Ball Architects, APC
 All rights reserved. No part of the work covered by the copyright herein may be reproduced or used in any form or by any means - graphic, electronic or mechanical, including photocopying, recording, taping or information storage and retrieval systems - without written permission of the copyright holder.

**Pool and Landscape for the
 SOUTHERN YACHT CLUB**
 105 N. ROADWAY DRIVE
 NEW ORLEANS, LOUISIANA 70124
 PROJECT NO.: 0605

SHEET TITLE:	
Foundation Plan	
DATE:	October 9, 2009
DRAWN BY:	
REVISION:	

S501