

ALL COMPLETED WORK SHALL BE SMOOTH WITH SIDEWALK ELEVATION WITH NO PROJECTIONS ABOVE SIDEWALK ELEVATION.

- NOTES:
1. CONTRACTOR SHALL CONSTRUCT A 6" WIDE x 4" DEEP TRENCH DRAIN THE LENGTH OF SIDEWALK ON THE NORTH END OF BUILDING. LEAVE A 1/2" WIDE KEY WAY EACH SIDE TO SUPPORT GRATE.
 2. SLOPE INVERT .8% TO .9% TOWARD DRAINAGE DITCH.
 3. CONCRETE MIX SHALL OBTAIN A MINIMUM STRENGTH OF 3,000 PSI IN 30 DAYS.
 4. INSTALL A METAL GRATE AT THE TOP OF THE TRENCH. GRATE SHALL BE A HEAVY DUTY, HEEL PROOF, ANTI SLIP GRATE WITH LOCKABLE COVER.




1 TRENCH DRAIN

SCALE: 1"=1'-0"

DRAINAGE ANALYSIS FOR THE
EL PASO MEXICAN RESTAURANT
 200 WEST GLORIA SWITCH ROAD
 CARENCRO, LA 70520

JOB No:	2269	DATE:	4/2/2020
DRAWN BY:	DD	CHECKED BY:	BAM

C1.4.1



DAMMON ENGINEERING, INC.

554 Old Spanish Trail Suidell, LA 70458 (985) 649-5832

CHIEF ENGINEER: BRIAN A. MISTICH, P.E.
 554 OLD SPANISH TRAIL
 SUIDELL, LA 70458

dammonengineering.com
 info@dammonengineering.com
 PHONE: 985-649-5832