FILE NAME: J:\— RESTAURANT\Dickie Brennan Napoleon\Current Drawings\E103 – Panel Sched Riser.dwg PLOT DATE & TIME: Tuesday, July 22, 2025 10:57:54 AM

PANEL SCHEDULE

PANEL: MDP
LOCATION: ELECTRICAL ROOM
FEEDER SOURCE: UTILITY
AIC = 25,000
VOLTAGE: 208/120V, 800A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SIEMENS TYPE P5 PANELBOARD, W/ SURGE PROTECTION DEVICE

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION / LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION / LOCATION	THHN WIRE SIZE	CKT NO
1					5400	3500					2
3	#6	AHU-1, NAPOLEON DINING ROOM	60	3	5400	3500	3	30	AHU-2, DRYADES DINING ROOM	#10	4
5					5400	3500					6
7					5400	5100					8
9	#6	AHU-3, LOUNGE	60	3	5400	5100	3	50	AHU-4, PRIVATE DINING ROOM	#8	10
11					5400	5100					12
13					5400	5400					14
15	#6	AHU-5, KITCHEN	60	3	5400	5400	3	60	AHU-6, KITCHEN	#6	16
17					5400	5400					18
19		SPACE		1							20
21		SPACE (HIGH LEG)		1			3		PREPARED SPACE		22
23		PANEL "L1"	200	2	9680						24
25					8040						26
27		SPACE (HIGH LEG)		1			3		PREPARED SPACE		28
29		SPACE		1							30
31											32
33		PREPARED SPACE		3			3		PREPARED SPACE		34
35											36
37					32130						38
39		PANEL "KP"	400	3	27000		3		PREPARED SPACE		40
41					32250						42

SOLID NEUTRAL / NEUTRAL WIRE (W) — TOTAL CONNECTED LOAD (VA) =198,700 — GROUND BUS / GROUND WIRE (G)

AΦ = 71,370 | BΦ = 57,200 | CΦ = 71,130

PANEL SCHEDULE

PANEL: KP-1
LOCATION: ELECTRICAL ROOM
FEEDER SOURCE: PANEL MDP #35/37/39
AIC = 22,000
VOLTAGE: 208/120V, 400A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SIEMENS TYPE P2 PANELBOARD

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION / LOCATION	BREAKER AMP	BREAKER POLE	LOAD (kva)	LOAD (kva)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION / LOCATION	THHN WIRE SIZE	CKT NO
1					3000	3000					2
3	#10	SMALL VENT HOOD EXHAUST	30	3	3000	3000	3	30	LARGE VENT HOOD EXHAUST	#10	4
5					3000	3000					6
7					3000	3000					8
9	#10	SMALL VENT HOOD MAKE UP AIR	30	3	3000	3000	3	30	LARGE VENT HOOD MAKE UP AIR		10
11					3000	3000					12
13					6000	720	1	15	GAS RANGE, 36"W GRIDDLE TOP LARGE HOOD	#12	14
15	#6	DISH WASHER	60	3	6000				SHUNT TRIP		
17					6000	1800	1	15	GAS RANGE, CONVECTION OVEN LARGE HOOD	#12	16
19		SPACE		1					SHUNT TRIP		
21		SPACE (HIGH LEG)		1			1		SPACE (HIGH LEG)		18
		SHUNT TRIP					1		SPACE		20
23	#12	VULCAN GAS FRYER, SMALL HOOD	15	1	720	200	1	20	GAS FLOOR FRYER, LARGE HOOD	#12	22
		SHUNT TRIP							SHUNT TRIP		
25	#12	VULCAN GAS CONVECTION OVEN, SMALL HOOD	15	1	170	200	1	20	GAS FLOOR FRYER, LARGE HOOD	#12	24
27		SPACE		1					SHUNT TRIP		
29		SPACE (HIGH LEG)		1			1		SPACE (HIGH LEG)		26
		SHUNT TRIP					1		SPACE		28
31	#12	CLEAVELAND POWERPAN, TILTED SKILLET, SMALL HOOD	15	1	700		1		SPACE		30
		SHUNT TRIP					1		SPACE (HIGH LEG)		32
33	#12	UNDER COUNTER REFRIGERATOR, LARGE HOOD	15	1	300		1		SPACE		34

SOLID NEUTRAL / NEUTRAL WIRE (W) — TOTAL CONNECTED LOAD = 58,810 — GROUND BUS / GROUND WIRE (G)

AΦ = 20,340 | BΦ = 18,000 | BΦ = 20,470

PANEL SCHEDULE

PANEL: KP-2
LOCATION: ELECTRICAL ROOM
FEEDER SOURCE: PANEL MDP #35/37/39
AIC = 22,000
VOLTAGE: 208/120V, 400A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SIEMENS TYPE P2 PANELBOARD

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION / LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION / LOCATION	THHN WIRE SIZE	CKT NO
37	#12	COOLER, OYSTER BAR	15	1	420	420	1	15	COOLER, OYSTER BAR	#12	38
39		SPACE (HIGH LEG)		1			1		SPACE (HIGH LEG)		40
41	#12	GLASS WASHER COCKTAIL BAR	15	1	420	860	1	15	GLASS FROSTER COCKTAIL BAR	#12	42
43	#12	COOLER, 52" WIDE, BAR	15	1	420	330	1	15	COOLER, 48" WIDE, BAR	#12	44
45		SPACE (HIGH LEG)		1			1		SPACE (HIGH LEG)		46
47	#12	SANDWICH/SALAD PREP REFRIG. KITCHEN	15	1	700	800	1	15	SANDWICH/SALAD PREP REFRIG. KITCHEN	#12	48
49	#12	SANDWICH/SALAD PREP REFRIG. KITCHEN	15	1	700	500	1	15	WAITER STATION	#12	50
51		SPACE (HIGH LEG)		1			1		SPACE (HIGH LEG)		52
53		SPARE	20	1			1	20	SPARE		54
55		SPARE	20	1			1	20	SPARE		56
57		SPACE (HIGH LEG)		1			1		SPACE (HIGH LEG)		58
59		SPACE		1			1		SPACE		60
61		SPACE		1			1		SPACE		62
63		SPACE (HIGH LEG)		1			1		SPACE (HIGH LEG)		64
65	#12	SPACE	20	1			1		SPACE		66
67	#12	SPACE	20	1			1		SPACE		68
69		SPACE (HIGH LEG)		1			1		SPACE (HIGH LEG)		70
71		SPACE		1			1		SPACE		72
73					3000	3000					74
75	#10	WALK IN COOLER	30	3	3000	3000	3	30	WALK IN FREEZER	#10	76
77					3000	3000					78

SOLID NEUTRAL / NEUTRAL WIRE (W) — TOTAL CONNECTED LOAD = 32,570 — GROUND BUS / GROUND WIRE (G)

AΦ = 11,790 | BΦ = 9,000 | BΦ = 11,780

PANEL SCHEDULE

PANEL: L1
LOCATION: ELECTRICAL ROOM
FEEDER SOURCE: PANEL MDP # 25/27
AIC = 22,000
VOLTAGE: 208/120V, 250A, 1Φ, 3W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SIEMENS TYPE P1 PANELBOARD

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION / LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION / LOCATION	THHN WIRE SIZE	CKT NO
1	#12	RECEPT, LARGE PRIVATE DINING ROOM 1 AND COCKTAIL LOUNGE	20	1	1080	1300	1	20	LIGHTS, PRIVATE DINING ROOM 1	#12	2
3	#12	RECEPT, LARGE PRIVATE DINING ROOM 1 CORRIDOR AND BAR	20	1	1260	1400	1	20	LIGHTS, COCKTAIL LOUNGE AND OYSTER BAR	#12	4
5	#12	RECEPT, DRYADES DINING ROOM	20	1	1260	1300	1	20	LIGHTS, DRYADES DINING ROOM, AND BAR	#12	6
7	#12	RECEPT, OFFICES AND KITCHEN	20	1	1080	1000	1	20	LIGHTS, PRIVATE DINING ROOM, CORRIDOR AND RESTROOMS	#12	8
9	#12	RECEPT, SMALL PRIVATE DINING ROOM, CORRIDOR AND RESTROOMS	20	1	1260	1400	1	20	LIGHTS, KITCHEN AND OFFICE	#12	10
11	#12	RECEPT, NAPOLEON DINING ROOM	20	1	1260	1500	1	20	LIGHTS, NAPOLEON DINING ROOM	#12	12
13	#12	RECEPT, LARGE PRIVATE DINING ROOM, WATER STATION, KITCHEN	20	1	1080	1000	1	20	EXTERIOR LIGHTING	#12	14
15	#12	ROOF TOP WATER HEATERS	20	1	540		1	20	SPARE		16
17		SPARE	20	1			1	20	SPARE		18
19		SPARE	20	1			1	20	SPARE		20
21		SPACE	20	1			1	20	SPACE		22
23		SPACE	20	1			1	20	SPACE		24
25		SPACE	20	1			1	20	SPACE		26
27		SPACE	20	1			1	20	SPACE		28
29		SPACE	20	1			1	20	SPACE		30
31		SPACE	20	1			1	20	SPACE		32
33		SPACE	20	1			1	20	SPACE		34
35		SPACE	20	1			1	20	SPACE		36
37		SPACE	20	1			1	20	SPACE		38
39		SPACE	20	1			1	20	SPACE		40
41		SPACE	20	1			1	20	SPACE		42

SOLID NEUTRAL / NEUTRAL WIRE (W) — TOTAL CONNECTED LOAD (VA) = 17,720 — GROUND BUS / GROUND WIRE (G)

AΦ = 9,680 | BΦ = 8,040

DAMMON ENGINEERING, INC.
LOUISIANA & MISSISSIPPI
Chief Engineer: Brian Mistich, PE
554 Old Spanish Trail
Slidell, LA 70458
www.dammonengineering.com
info@dammonengineering.com
PH: 985.649.5832

REVISIONS
#	DESCRIPTION	DATE

SEAL:

RESTAURANT
PASCAL'S MANALE
1838 NAPOLEON AVENUE, NEW ORLEANS, LA 70115

JOB No: 2024 | DATE: 07/21/2025
DRAWN BY: DD/JTL | CHECKED BY: BAM

The above drawings and specifications, designs and arrangements represented thereby are and shall remain the property of Dammon Engineering, and no part thereof shall be copied, disclosed to others, or used in connection with any work or project other than the specific project for which the have been prepared and developed without written consent of Dammon Engineering. Visual contact with these drawings or specifications shall constitute conclusive evidence of acceptance of these restrictions.

SHEET TITLE: ELECTRICAL PANEL SCHEDULES

DRAWING NUMBER: E103