

STATE OF LOUISIANA
Department of Public Safety and Corrections
Office of State Fire Marshal Code Enforcement and Building Safety
8181 Independence Boulevard
Baton Rouge, Louisiana 70806
225-925-4920

H "BUTCH" BROWNING
FIRE MARSHAL

AMENDED LETTER

ROBERT WILTSE
DAMMON ENGINEERING INC
1095 FLORIDA AVE
SLIDELL, LA 70458-0000

RE: P0372882
CHILD DEVELOPMENT COUNCIL OF
ACADIANA
HWY 167
OPELOUSAS, LA 70571

NFPA 101, 2006

BUSINESS
ASSEMBLY 300 OCCUPANTS OR LESS

Dear Applicant:

This is to advise that the previous review letter dated 11/25/2009 for this project is hereby amended as follows:

1. **Regarding item no. 13 of original review letter for this project:**
 - a) **The occupancy is mixed, SEPARATED, Group B and Group A-3. The occupancies are separated in accordance with 508.3.3 with 2-hour fire barriers per Table 508.3.3.**

2. **Regarding item no. 15 of original review letter for this project:**
 - a) **The Professional of Record has furnished documentation addressing Fire Protection Systems. The building is not provided with an automatic sprinkler system or a fire alarm system. The systems are not required (the building is separated, by 2-hour fire barriers, into 2 fire areas with an occupant load in each area of less than 300 persons).**

3. **Regarding item no. 19 of original review letter for this project:**
 - a) **The following additional documentation has been provided to indicate compliance with Code:**
 - a) **Gravity Load Data:**
 - Floor live loads = 100psf (50psf @ office area).
 - Corridor live loads = 100psf.
 - Roof live loads = 20psf.
 - b) **Wind Design Data:**
 - The internal pressure coefficient = +/-0.18.
 - Design wind pressures used for the design of exterior components and cladding = 33.6psf.
 - c) **Flood Design Data:**
 - The construction documents indicate "no BFE requirements".

4. **NOTE: The rest of the original review letter for this project shall remain applicable. Please enclose a copy of this letter with future submittals or other correspondence pertaining to this project.**

This review applies to the work indicated on the drawings or specifications.

This review shall in no way permit or authorize any omissions or deviations from the specific requirements of the adopted codes, rules and regulations in accordance with R.S. 40:1574.1(B).

The above amended review is valid if construction starts within 180 days from the above date of the original review letter.

Occupancy of the project will not be permitted until we receive the completed certificate and a satisfactory inspection of the completed construction has been made by this office.

To arrange for inspection of the project, please contact the District Office at the phone number below, two (2) to three (3) weeks in advance. Approved plans must be available on job site at time of inspection. Certificate of completion must be provided to inspecting Deputy for final inspection.

REVIEWED BY:
JOHN WHITAKER
ARCHITECT

CC:
Child Development Council Of Acadiana
Opelousas Fire Chief*
Margaret Doucet*
Lafayette District* 3378861273