



Luminaire Schedule									
Symbol	Qty	Label	Arrangement	LLF	Description	Lum. Lumens	Arr. Lum. Lumens	Lum. Watts	Arr. Watts
	7	EM	SINGLE	0.950	SURELITES: SELW25	34	34	0.405	0.405
	15	EX	SINGLE	0.950	SURELITES: APX70R	34	34	0.405	0.405
	67	F1	SINGLE	0.950	METALUX: 24CZ-LD5-60-UNV-L840-CD1-U	6221	6221	52.17	52.17
	2	F1B	SINGLE	0.950	METALUX: 24CZ-LD5-45-UNV-L840-CD1-U	4558	4558	35.69	35.69
	3	F1BE	SINGLE	0.950	METALUX: 24CZ-LD5-45-UNV-L840-CD1-U-EL7W	4558	4558	35.69	35.69
	20	F1E	SINGLE	0.950	METALUX: 24CZ-LD5-60-UNV-L840-CD1-U-EL7W	6221	6221	52.17	52.17
	1	F2	SINGLE	0.950	PORTFOLIO: LD6B20D010 EU6B10208040 6LBM11	1889	1889	20.8	20.8
	4	F2E	SINGLE	0.950	PORTFOLIO: LD6B20D010 EU6B10208040 6LBM11-EIM	1889	1889	20.8	20.8
	20	F3	SINGLE	0.950	PORTFOLIO: LD8B20D010 ER8B20840 8LBM01	2174	2174	21.3	21.3
	12	F3E	SINGLE	0.950	PORTFOLIO: LD8B20D010 ER8B20840 8LBM01-EIM	2174	2174	21.3	21.3
	3	F4	SINGLE	0.950	METALUX: 4BCLED-LD4-20SL-F-UNV-L840-CD1-U	2099	2099	21.8	21.8
	11	F5	SINGLE	0.950	METALUX: 4SNLED-LD5-40SL-UNV-L840-CD1-U	4084	4084	27.7	27.7
	13	F6	4FT TANDEM	0.950	CORELITE: DWI-WA-5L35-1D-UNV-8	4646	9292	45.9	91.8

Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
CLASSROOM 5 126_Workplane	Illuminance	Fc	59.42	73.8	38.3	1.55	1.93
CONF 123_Workplane	Illuminance	Fc	54.85	66.3	46.0	1.19	1.44
CORR 103_Workplane	Illuminance	Fc	31.94	48.4	15.7	2.03	3.08
CORR 104_Workplane	Illuminance	Fc	22.29	26.2	17.8	1.25	1.47
CORR 120_Workplane	Illuminance	Fc	36.62	58.0	17.9	2.05	3.24
DATA 108_Workplane	Illuminance	Fc	42.58	51.7	35.5	1.20	1.46
JAN 107_Workplane	Illuminance	Fc	30.55	34.2	28.6	1.07	1.20
OFC 121_Workplane	Illuminance	Fc	36.12	47.5	29.7	1.22	1.60
PORCH_Planar	Illuminance	Fc	14.47	20.6	7.0	2.07	2.94
STAFF LNG 118_Workplane	Illuminance	Fc	52.78	68.3	39.4	1.34	1.73
STAFF TLT 116_Workplane	Illuminance	Fc	38.58	48.3	28.6	1.35	1.69
WAITING 125_Workplane	Illuminance	Fc	38.38	49.6	19.2	2.00	2.58
WOMEN RR 109_Workplane	Illuminance	Fc	38.39	51.5	21.6	1.78	2.38