

# BP36V42-3U

## External Battery Pack for UPS Systems



### Model #: BP36V42-3U

- ▶ Extends runtime of select compatible Tripp Lite UPS Systems with 36V DC external battery connector
- ▶ Provides daisy-chain compatibility for multiple connected battery packs
- ▶ Simple installation; 3U rackmount, tower and stack adaptable
- ▶ 2-year warranty

## DESCRIPTION

BP36V42-3U rack/tower external battery pack offers extended battery runtime when used in conjunction with compatible Tripp Lite systems. Multi-use form factor supports configuration in stacking, upright tower and rackmount applications using only 3 rack spaces (3U). Includes heavy gauge cabling with high current DC connector for simple installation. Additional output connector allows multiple BP36V42-3U battery packs to be daisy-chained to the UPS for even longer extended run operation.

Compatible UPS systems - SMART1500RMXL2Ua, SMX1500RTXL2U and other Tripp Lite UPS systems that specify the use of this battery pack.

## KEY BUYING POINTS

- Offers extended-run UPS operation when used in conjunction with compatible Tripp Lite UPS systems
- Supports stacking or rackmount installation using only 3 rack spaces (3U)
- Includes heavy gauge cabling with high current DC connectors for simple installation
- Attractive all-black color scheme
- Additional output connector allows multiple battery packs to be daisy-chained to the UPS for even longer extended run operation
- 2 year warranty

## TYPICAL APPLICATIONS

- Ideal means of lengthening the battery runtime provided by compatible Tripp Lite UPS systems. Battery pack may be ordered at time of original UPS purchase or sourced at a later date to extend runtime performance if site power conditions deteriorate and longer battery runtime is desired.

## PACKAGE INCLUDES

- External battery pack
- Mounting hardware
- Warranty information
- Instruction manual

## COMPLETE SPECIFICATIONS

### BATTERY

**Expandable battery runtime:** Includes a second input/output connector to daisy-chain multiple battery packs

**DC system voltage:** 36V DC

**Typical battery lifespan:** 4-6 years typical (North America)  
**Connects to UPS via:** Detachable cable with UPS specific DC connector (36 in length, 6 gauge)

## **PHYSICAL**

**Shipping weight (lbs):** 165.35  
**Shipping weight (kg):** 75.1  
**Unit weight (lbs):** 127.87  
**Unit weight (kg):** 58.1  
**Unit Dimensions (HWD/in):** 5.25 x 17.5 x 25  
**Unit Dimensions (HWD/cm):** 13.3 x 44.45 x 63.5  
**Shipping Dimensions (HWD/in):** 11.25 x 23 x 31.5  
**Shipping Dimensions (HWD/cm):** 28.6 x 58.42 x 80.01  
**Material of construction:** Steel  
**Form factors supported:** Stacking, upright tower and 3U rackmount form factors supported

*The policy of Tripp Lite is one of continuous improvement.  
Specifications are subject to change without notice.  
Therefore, your product may vary slightly from what is currently listed.*



**Tripp Lite World Headquarters**  
1111 W. 35th Street  
Chicago, IL 60609 USA

**Customer Support**  
(773) 869-1234

© 2006 Tripp Lite. All Rights Reserved.