

Effective Date: May 1, 2000

To: Property Owner

RE: Miscellaneous Drainage
Slidell Job No. 100-1

In reference to the installation of culverts in front of your property, the following is required according to City Ordinances and City Engineering policies:

1. The pipes required shall be new 15" (minimum) **reinforced** concrete pipe of Bell and Spigot type with "O" ring rubber gaskets. The City Engineer's Office will verify, with the owner, the pipe size to be used. The equivalent arch sizes are required when adequate ground cover (3" minimum) can not be achieved with round pipe. The owner must verify the pipe size with the Engineering Department.
2. The bells of the pipes shall be laid upstream.
3. All joints shall be wrapped with geotextile fabric.
4. All pipes shall require a 3" **compacted** sand or limestone base.
5. Catch basins shall be installed at each property line at a minimum size of 3' x 3' with 24" x 24" grate, unless approved otherwise.
6. Inspection by the Engineering Department is required before backfilling the pipes. One (1) working days notice is required for scheduling of inspections. The inspection will be performed within two (2) working days of the request. The requests are to be scheduled with the Department secretary at 646-4270. A letter of acceptance or denial will be issued to the owner within two (2) working days of the request for inspection.
7. It is the property owner's responsibility to install all culverts and catch basins in accordance with the City of Slidell codes, manufacturer's recommendations and standard engineering practices.
8. The property owner must submit plans of the drainage system for review and approval.
7. Failure to comply with the above requirements will result in the removal and re-installation of culverts or correction of any defects at the owner's expense.

Stanley P. Polivick, P.E.
City Engineer