



## GENERAL NOTES

1. CONTRACTOR TO REMOVE ALL COMPONENTS PERTAINING TO THE FOLLOWING ITEMS:
  - A. ELECTRICAL PANELS, OUTLETS, SWITCHES & WIRES.
  - B. TELEPHONE TERMINALS, HUBS & LINES.
  - C. WATER & SEWER LINES.
  - D. A/C UNITS, DUCTS & REGISTERS.
  - E. ALL EXTERIOR SIDING AND WINDOWS.
  - F. ALL FLOORING AND SUB-FLOORING.
  - G. ALL WALLS SHADED IN
2. REMOVE ALL WALLS CLOUDED IN.
3. REMOVE EXISTING PLYWOOD FROM FLOOR WHERE ONE & TWO LAYERS HAVE BEEN INSTALLED. INSPECT FOR DAMAGE OF FRAMING AND INSTALL NEW IF NECESSARY. INSTALL 3/4" T&G PLYWOOD. ALL FLOORS SHALL BE AT SAME ELEVATION.
4. ALL EXTERIOR WOOD SIDING, WINDOWS AND INSULATION SHALL BE REMOVED.
5. TEXTRON WILL REMOVE ALL COMMUNICATION EQUIPMENT FROM WORK AREA.