



Test Specifications and Results for Parterre Solid Vinyl Plank and Tile Flooring

Parterre "Quizno's Q-Maple & Q-Green" Standards

Characteristic	Test Specification* and Result
Size	18" x 18" and 4" x 36"
Composition	100% luxury solid vinyl PVC
Total Thickness	3mm (1/8" nominal) 0.5mm wearlayer
Squareness	ASTM F-1700-99, Class III, Type B -- Meets Spec.
Flexibility	ASTM F-1700-99, Class III, Type B -- Meets Spec.
Dimensional Stability	ASTM F-1700-99, Class III, Type B -- Meets Spec.
Residual Indentation	ASTM F-1700-99, Class III, Type B -- Meets Spec.
Resistance to Chemicals	ASTM F-1700-99, Class III, Type B -- Meets Spec.
Heavy Metal Presence / Absence	ASTM F- 963-96a, Clause 4.3.5 -- Meets Spec. (Lead, Antimony, Arsenic, Barium, Cadmium, Chromium, Mercury and Selenium).
Flame Spread Resistance	ASTM E-648-00 (Critical Flux) -- Meets Spec. (Class I).
Smoke Generation Resistance, Flaming Mode	ASTM E-662-01 (NBS Smoke Chamber) -- Meets Spec. (Less than 450).
Smoke Generation Resistance, Non-Flaming Mode	ASTM E-662-01 (NBS Smoke Chamber) -- Meets Spec. (Less than 450).
Slip Resistance (Static Coefficient of Friction)	ASTM D-2047-99 (James Machine) -- Meets Spec. (Complies with ADA recommendations).
Slip Resistance (Static Coefficient of Friction)	ASTM C-1028-96 -- Meets Spec. (Complies with ADA recommendations).
Static Load Limit	ASTM F-970-00, Armstrong Modification** -- 750 psi.
Abrasion Resistance	ASTM D-3884-01 with H-18 wheels and 1,000gm load. ***
Abrasion Resistance	ASTM F-510-99. ****
Resistance to Light	ASTM F-1700-99 -- Meets Spec.
Resistance to Heat	ASTM F-1700-99 -- Meets Spec.
Shore Hardness	ASTM D-1415-99 (Durometer) -- 98-99.
Shore Hardness	ASTM D-2240-00 (Durometer) -- 98-99.
Underfloor Heating	Suitable for installing over underfloor heating.
Subfloor Irregularities	Products conform to subfloor irregularities and will not break or crack during installing or use.
Recycled Vinyl Content	Approximately 35%.
Recyclability	Can be recycled.
OSHA Requirements	In Compliance.
Product Warranty	10-Years, Limited.

* Issue date most current at time of testing.

** Based on industry accepted, Armstrong standard test method modification.

*** Wear through of wearlayer @ 24,000 cycles with wheel cleaning / dressing after each 6,000 test cycles. Weight loss is 0.046gm; thickness loss is 0.0005in.



Quizno's Flooring Installation Information Sheet

The following list of items will be supplied by owner, on site, for your installation...

Flooring

Q-Green 18" x 18" x 3mm solid vinyl tile 36 sq. ft. per carton. (Full Cartons only)
Q-Maple 4" x 36" x 3mm solid vinyl plank 36 sq. ft. per carton. (Full Cartons only)
Q-Sand 6' x 29' 6" x 2mm solid vinyl sheet 19.76 sq. yd. per roll. (Full Rolls only)

Installation Supplies

Parterre #449 wet set / tack set, one-part, acrylic / latex adhesive, 4 gallon pail
Parterre SSA 669 liquid seam sealer for vinyl sheet, pint can
Parterre SSB 669 applicator bottle for liquid seam sealer.

Initial Maintenance Supplies

Taski Vision Matte Floor Finish, 2.5 gallon bottle
Taski Profi Floor Cleaner, 1 gallon bottle

Notes to flooring contractors

1. All flooring, adhesive and maintenance products are supplied by owner. No pricing will be quoted by Parterre to contractors.
2. Samples of flooring are not available from Parterre. Flooring is in custom designs and colors and is property of Quizno's. Contact Quizno's Area Director with any concerns or questions that relate to this paragraph.
3. Technical installation information is available directly from Parterre by calling 888-338-1029.
4. Trench cuts in concrete slabs should be filled with Mapei PRP145 Mapecem Premix. Allow minimum 24 hours for surface to become dry before installing flooring. Product manufacturer's instructions should be followed completely. Mapei tech support is available by phone at 800-992-6273.



Quizno's Flooring Installation Information Sheet
Page 2 of 2

5. "Q Logo" is supplied by owner and is cut from flooring planks and delivered to jobsite as a complete unit ready to be placed into position according to project plan. This "Q Logo" involves no cutting and should involve no cost to the contractor or charge to Quizno's.
6. Because owner supplies flooring, adhesive and maintenance products, there should be no charges for these items in flooring contractor's quotation.
7. Acclimatizing of flooring and adhesive is necessary to achieve a proper installation.
8. Owner will provide proper amount of adhesive for the flooring. Adhesive spread rate is 190-220 sq. ft. per gallon. Adhesive provided is ideal for vinyl tile, plank and sheet flooring.
9. Floor cleaner and finish will be provided by owner and should be applied after installation. Floor cleaner coverage is 15-20,000 sq ft per one gallon bottle and floor finish coverage is 4,000 – 5,200 per 2.5 gallon bottle. Four coats are required.
10. Installation instructions are found on Parterre's website at www.parterreflooring.com or by contacting Parterre customer service at 888-338-1029.

###

Parterre Vinyl Flooring Systems
Brooklyn Navy Yard Building 292 Suite 410
Brooklyn, NY 11205
(w) 888-338-1029 (t) 718-858-4001 (f) 718-858-0330
www.parterreflooring.com