



ELECTRICAL LEGEND

SYMBOL	DISCRPTION
	SATCO #62-1054 45W/LED/1X4/FLUSH/3K/WH 45 WATT, 3000K LED, 1'X4" SURFACE MOUNTED LIGHT (ELECTRICAL BOX IN CENTER)
	LITHONIA #EERG-HO-RD-M6 EMERGENCY COMBINATION EXIT/FLOOD LIGHT W/ MIN. 90 MINUTE BATTERY BACK-UP (WALL MOUNT)
	LITHONIA #ERE-SGL-WP REMOTE EMERGENCY LIGHT HEAD (GRAY)
	SATCO #S9013 4" (7 WATT) 4000K LED W/P CAN LIGHT FIXTURE
	INTERMATIC #E1500 PROGRAMMABLE ASTRONOMICAL TIMER SWITCH (LIGHT ALMOND)
	LUTRON #MSOPS5MLA, (1) POLE OCCUPANCY SENSOR SWITCH W/ MANUAL OVERRIDE -WALL MOUNTED
	PASS & SEYMOUR #3232-LA SPEC. GRADE, GROUNDING TYPE, RECEPT (LIGHT ALMOND) -GFI WERE NOTED -UP 18" UNLESS NOTED
	ELECTRICAL DISTRIBUTION LOAD CENTER W/ MAIN DISCONNECT-120/240V., SINGLE PHASE, 100 AMP CAPACITY, SQ. 'D' #Q0120M100-UP 48" TO CENTER W/ (1) 1-1/2" CONDUIT THRU FLOOR W/ (1) 3/4" CONDUIT THRU FLOOR
	#5400 SERIES CONTINUOUS ELECTRIC WIREMOLD (IVORY) W/ RECEPTS AND COMMUNICATION JACK COVERS 48" O.C. AND 3/4" CONDUIT THRU FLOOR AT EACH END OF PRESSBOX FOR ACCESS-UP 14"
	2 1/2" GROMMETED HOLE THRU COUNTER
	ROOF ELECTRICAL ACCESS- 2'X4" WATERPROOF FASCIA MOUNTED JUNCTION BOX W/ 3/4" EMT CONDUIT TO ENTRANCE PANEL FOR (FUTURE USE) (WEATHER-RESISTANT RECEPTACLES IN WEATHERPROOF ENCLOSURES TO BE INSTALLED ON GUARD RAILS BY EC)
	ZONELINE #AZ45E07DAB 3.5 KW ELECTRIC WALL MOUNT W/ DRAIN KIT HEAT/COOL UNIT-UP 7" 7,000 BTU COOL 11,700 BTU HEAT

DOOR/WINDOW SCHEDULE

SYMBOL	DISCRPTION
(A)	36"x80" CECO "VERSA" POLYURETHANE CORE 18 GA. GALVANIZED HOLLOW METAL DOOR W/ STEEL FRAMES, HYDRAULIC CLOSER, WEATHERSTRIP, ALUMINUM ADA THRESHOLD, BALL BEARING HINGES, 10" WINDOW AND COMMERCIAL LEVER HANDLED LOCKSET.
(B)	36"x80"x1 3/8" SOLID-CORE PRE-HUNG INTERIOR DOOR W/ MATCHING WOOD JAMB AND CASING, 1 1/2" PAIR MORTISED BUTT HINGES, AND PASSAGE LOCKSET. (ALL DOORS EQUIPPED W/ LEVER HANDLE LOCKSETS)
(C)	(2) 62 1/4"x48" WINGUARD #HR7710A SERIES ALUMINUM HORIZONTAL ROLLER WINDOW W/ 13/16" LIG (1/8" ANN-3/8" AIR-5/16" ANN/ANN LAMINATED) IMPACT-RESISTANT GLASS, GRAY TINT AND SCREENS (MULLED TO CREATE 125 1/2" CLEAR SPAN)
(D)	24"x44"x1/4" TEMPERED SAFETY GLASS PICTURE WINDOW -MOUNT AT FRONT WINDOW HEADER HEIGHT

CROSS SECTION
SCALE: 3/4"=1'-0"

REAR ELEVATION

PRELIMINARY LAYOUT
NATIONAL RECREATION SYSTEMS
FT. WAYNE, IN

FINISH SCHEDULE	
INTERIOR	COLOR
WALL BOARD:	---
SPRAY TEXTURED CEILING:	WHITE
PLASTIC LAMINATE COUNTER:	---
FLOOR MOLDING:	---
VINYL COMPOSITION TILE:	---
SOLID-CORE BIRCH INTERIOR DOOR:	STAINED FRUITWOOD
EXTERIOR	
ROOF MEMBRANE:	BALTIC GRAY
SIDING:	---
BOTTOM STARTER TRIM:	---
FASCIA:	---
SOFFIT:	---
WINDOWS:	---
DOORS:	---

APPROVED FOR PRODUCTION _____ DATE _____	DWN. BY: GJK	REVISION	DATE
Return approved drawing as soon as possible, so that production can be scheduled.	CHK. BY:		
NOTE: Manufacturer not responsible for local permits and occupancy requirements.	DATE: 2/10/22		
	SCALE: 1/4"=1'		
	DWG. NO: MF022-22		

This drawing and all information contained herein is the property of MOBILE FACILITY ENGINEERING, INC. and is not to be reproduced without the express written permission of this manufacturer. We assume no responsibility for unauthorized use of this drawing. Mobile Facility Engineering is not responsible for local permits and occupancy requirements.

CUSTOMER: SALMEN HIGH SCHOOL	TITLE: FLOOR, CROSS SECTION
ADDRESS: SLIDELL, LA	SHT #1
ATTN:	
PROJECT: 848 PRESSBOX	

MOBILE FACILITY ENGINEERING, Inc.
306 W. STATE STREET - CASSOPOLIS, MICHIGAN 49031 • PHONE: 269/445-3838 - FAX: 269/445-2251
www.mfeinc.com

mfe SINCE 1962
Mobile Offices and Modular Buildings
• MANUFACTURING
• SALES
• LEASING