

**PACKAGED A/C SCHEDULE - BOYET JUNIOR HIGH GYM**

**ROOFTOP UNIT**

TAG	AREA SERVED	Make/Model	Model / Size	Nominal Tonnage	Total CFM	OA CFM	External SP ("WC)	FAN		COOLING				FILTERS	HEAT		POWER			MCA	MOP	REMARKS
								QTY	HP	TMBH	SMBH	EDB	EWB		KW	STAGE	VAC	PH	Hz			
AHU-1	Gym	Trane	TSJ180_3	15	6900	2680	0.6	2	3	200.7	125.9	83.5	71.1	MERV-8	36	2	208	3	60	132	150	1, 2, 3, 4
AHU-2	Gym	Trane	TSJ180_3	15	6900	2680	0.6	2	3	200.7	125.9	83.5	71.1	MERV-8	36	2	208	3	60	132	150	1, 2, 3, 4

**NOTES:**

- 1 Cooling capacities to be rated in accordance with AHRI standard 210/290 for ASHRAE standard design weather conditions in New Orleans, LA.
- 3 Install units in accordance with manufacturer's recommendations.
- 2 Provide controls per attached drawings and specifications
- 4 Provide new filters after commissioning and final acceptance.