



NEW MODIFIED BITUMEN ROOFING ASSEMBLY
OVER EXISTING TECTUM DECK

NEW PRE-FINISHED METAL
GUTTER

EXISTING STEEL BEAM -
PREP AND PAINT INTERIOR
AND EXTERIOR

NEW 6" UNFACED BATT
INSULATION OVER PREFINISHED
METAL CEILING PANELS

NEW 6" METAL STUD
WALL WITH TINTED
STUCCO FINISH ON
METAL LATH OVER 1/2"
GYPSUM SHEATHING ON
THE EXTERIOR AND 5/8"
GYPSUM BOARD OVER
7/8" HAT CHANNELS ON
THE INTERIOR

5
A8.1

ALIGN FACE OF
5/8" GYPSUM
BOARD WITH
INSIDE FACE OF
MASONRY WALL

NEW ROOFING MEMBRANE
ASSEMBLY & INSULATION
TO REPLACE EXISTING -
SEE ROOF DETAILS

NEW 6" UNFACED BATT
INSULATION SECURED W/
POULTRY NETTING

NEW DUCTWORK.
REFER TO
MECHANICAL DRAWINGS.
ATTACH DIRECTLY
TO UNDERSIDE OF
EXIST. BEAM - PER
STRUCTURAL DRAWINGS.

NEW STEEL
LINTEL &
INFILL
MASONRY

PATCH &
REPAIR
EXISTING
CEMENT
STUCCO
FINISH

NEW SUSPENDED
CEILING SYSTEM.
REFER TO
REFLECTED
CEILING PLAN

7'-6"±

NEW DOOR
ASSEMBLY/
MASONRY WALL
BEYOND

NEW BASE
AS SCHEDULED

INFILL VOID W/
CONCRETE TOPPING.
APPLY NEW FLOOR
FINISH AS SCHEDULED