

ABBREVIATIONS									
SYMBOLS USED AS ABBREVIATIONS:									
∠	ANGLE	EXP	EXPANDED METAL PLATE	MECH	MECHANICAL	STSM	STANDING SEAM		
CL	CENTERLINE	EXP	EXPOSED	MED	MEDIUM	SUS	SUSPENDED		
[CHANNEL	EXST	EXISTING	MET	METAL	SV	SHEET VINYL		
d	PENNY	EXT	EXTERIOR	MFR	MANUFACTURE(ER)	SYM	SYMMETRY(YY)(ICAL)		
⊥	PERPENDICULAR			MH	MANHOLE	SYN	SYNTHETIC		
PL	PLATE	FA	FIRE ALARM	MICRO	MICROWAVE	SYS	SYSTEM		
Ø	ROUND	FAS	FASTEN	MIN	MINIMUM				
ABBREVIATIONS:									
A	FRESH AIR	FBD	FIBERBOARD	MISC	MISCELLANEOUS	T	TREAD		
ABV	ABOVE	FBO	FURNISHED BY OTHERS	MMB	MEMBRANE	TEL	TELEPHONE		
AC	AIR CONDITIONING	FD	FLOOR DRAIN	MO	MASONRY OPENING	THK	THICKNESS		
ACT	ACOUSTICAL TILE	FE	FIRE EXTINGUISHER	MOV	MOVABLE	THR	THRESHOLD		
ADD	ADDENDUM	FEC	FIRE EXTINGUISHER AND CABINET	MOUNT	MOUNT(ED)(ING)	TKBD	TACKBOARD		
ADH	ADHESIVE	FF	FACTORY FINISH	MULL	MULLION	TOL	TOLERANCE		
ADJ	ADJUSTABLE	FFL	FINISHED FLOOR LINE	MWK	MILLWORK	TOS	TOP OF STEEL		
AF	ABOVE FINISHED FLOOR	FHC	FIRE HOSE CABINET			TPD	TOILET PAPER DISPENSER		
AGG	AGGREGATE	FIN	FINISH(ED)	N	NORTH	TRI	TRIPLE		
ALT	ALTERNATE	FJT	FLUSH JOINT	NAT	NATURAL	TSL	TOP OF SLAB		
ALUM	ALUMINUM	FLG	FLASHING	NIC	NOT IN CONTRACT	TV	TELEVISION		
ANC	ANCHOR	FLR	FLOOR	NL	NAILABLE	TW	TOP OF WALL		
ANOD	ANODIZED	FLUOR	FLUORESCENT	NMT	NONMETALLIC	TYP	TYPICAL		
ARCH	ARCHITECTURAL	FLX	FLEXIBLE	NOM	NOMINAL				
ASPH	ASPHALT	FND	FOUNDATION	NR	NOISE REDUCTION	UC	UNDERCOUNTER		
AUTO	AUTOMATIC	FOC	FACE OF CONCRETE	NRC	NOISE REDUCTION COEFFICIENT	UNF	UNFINISHED		
		FOF	FACE OF FINISH	NTS	NOT TO SCALE	UNO	UNLESS OTHERWISE NOTED		
		FOM	FACE OF MASONRY			UR	URNAL		
		FOS	FACE OF STUDS	OA	OVERALL	UT	UNDERCUT		
BC	BRICK COURSE	FPL	FLOOR PLATE	OC	ON CENTER(S)				
BD	BOARD	FR	FRAMED/FRAMING	OD	OUTSIDE DIAMETER	VB	VAPOR BARRIER		
BEL	BELOW	FRG	FIRE-RESISTANT COATING	OFCI	OWNER FURNISHED,	VCJ	VERTICAL CONTROL JOINT		
BG	BUMPER GUARD	FRG	FORGED		CONTRACTOR INSTALLED	VCT	VINYL COMPOSITION TILE		
BJT	BED JOINT	FRT	FIRE-RETARDANT	OFI	OWNER FURN. AND INSTALLED	VERT	VERTICAL		
BIT	BITUMINOUS	FTG	FOOTING	OH	OVERHEAD	VF	VINYL FABRIC		
BLDG	BUILDING	FUR	FURRED	OJ	OPEN-WEB JOIST	VIF	VERIFY IN FIELD		
BLK	BLOCK			OPG	OPENING	VIN	VINYL		
BLKG	BLOCKING	GA	GAUGE	OPH	OPPOSITE HAND	VJ	V-JOINT(ED)		
BM	BENCH MARK	GALV	GALVANIZED	OPP	OPPOSITE	VNR	VENEER		
BO	BY OTHERS	GC	GENERAL CONTRACTOR			VOJ	VERIFY ON JOB		
BOT	BOTTOM	GD	GRADE	PB	PANIC BAR	VR	VAPOR BARRIER		
BRG	BEARING	GF	GROUND FACE	PERF	PERFORATE(D)	VRM	VERMICULITE		
BRDG	BRIDGE/BRIDGING	GI	GALVANIZED IRON	PERI	PERIMETER	VWB	VINYL WALL BASE		
BS	BOTH SIDES	GKT	GASKET	PFB	PREFABRICATE(D)	VT	VINYL TILE		
BW	BOTH WAYS	GL	GLASS/GLAZING	PFN	PREFINISHED				
		GP	GALVANIZED PIPE	PL	PLATE	W	WEST		
CAB	CABINET	GPL	GYP SUM LATH	P/L	PROPERTY LINE	W/	WITH		
CCTV	CLOSED CIRCUIT TELEVISION	GPPL	GYP SUM PLASTER	PLAM	PLASTIC LAMINATE	WB	WOOD BASE		
CEM	CEMENT/CEMENTITIOUS	GSS	GALVANIZED STEEL SHEET	PLAS	PLASTER	WC	WATER CLOSET		
CER	CERAMIC	GT	GROUT	PNL	PANEL	WD	WOOD		
CFLG	COUNTERFLASHING	GVL	GRAVEL	PRF	PREFORMED	WH	WALL HUNG		
CG	CORNER GUARD	GWB	GYP SUM WALL BOARD	PRL	PROPERTY LINE	WM	WIRE MESH		
CHBD	CHALKBOARD			PSF	POUNDS PER SQUARE FOOT	WP	WATERPROOFING		
CJT	CONTROL JOINT	HB	HOSE BIB	PSI	POUNDS PER SQUARE INCH	WPT	WORKING POINT		
CK	CAULKING	HBD	HARDBOARD	PTD	PAINT(ED)	WFS	WATERSTOP		
CLG	CEILING	HVC	HANDICAPPED	PT	POINT	WSCT	WAINSCOT		
CLR	CLEAR	HC							

SYMBOLS

PLAN NORTH
DRAWING NUMBER
DRAWING TITLE
TRUE NORTH
DRAWING SCALE

ROOM NAME
ENTRY
ROOM TAG
DRAWING SCALE

PARTITION TYPE TAG
ELEVATION TAG
WINDOW - LOUVER OPENING DESIGNATION,
REFERENCE WINDOW SCHEDULE
DOOR OPENING DESIGNATION,
REFERENCE DOOR SCHEDULE
KEY NOTE (SHEET SPECIFIC)
DETAIL TAG
SECTION TAG
COLUMN GRID IDENTIFIER
REVISION TAG + CLOUD

AREA OF DETAIL TO BE ENLARGED

DETAIL NUMBER

SHEET NUMBER

DETAIL NUMBER

SHEET NUMBER

COLUMN GRID IDENTIFIER

REVISION TAG + CLOUD

MATL. DESIGNATIONS

CONCRETE

BRICK MASONRY

WOOD

FIRE TREATED WOOD (ROUGH), CONTINUOUS

FIRE TREATED WOOD SHIM

PLYWOOD

GYPSTUM BOARD, PLASTER, GROUT

MIRROR IN ELEVATION

METAL

RIGID INSULATION

BATT INSULATION

TERRAZZO

COMPACT FILL

MARBLE

CONCRETE MASONRY UNITS

VICINITY MAP

PROJECT STATISTICS	
SQUARE FOOTAGE	
FIRST FLOOR	3,941
SECOND FLOOR	3,941
TOTAL ENCLOSED SPACE	7,882
PROJECT LOCATION: 1808 FRONT ST, SLIDELL, LA 70458	
OWNER: SLIDELL CHAMBER OF COMMERCE 118 W HALL AVE. SLIDELL, LA 70460	
GENERAL NOTES	
<div>1. ALL MATERIALS AND WORK, INCIDENTAL TO THE CONSTRUCTION OF THIS PROJECT, SHALL CONFORM TO ALL GOVERNING CODES, AND REGULATIONS OF AGENCIES IN AUTHORITY.</div> <div>2. CONTRACTOR SHALL PROVIDE ALL PUBLIC PROTECTIONS NECESSARY AS REQUIRED BY LAW.</div> <div>3. THE DRAWINGS, SPECIFICATIONS AND ANY SUBSEQUENTLY ISSUED ADDENDA, AMENDMENTS OR SUCH CHANGE ORDERS APPROVED BY THE OWNER AND THE CONTRACTOR ARE PART OF THESE CONTRACT DOCUMENTS.</div> <div>4. DO NOT SCALE DRAWINGS. CONSULT WITH THE ARCHITECT REGARDING ANY ITEMS IN THE CONTRACT DOCUMENTS THAT REQUIRE CLARIFICATION.</div> <div>5. VERIFY LOCATION OF ALL EQUIPMENT WITH THE ARCHITECT, PRIOR TO INSTALLATION.</div> <div>6. TRASH SHALL BE REMOVED FROM THE SITE NOT LESS THAN TWICE MONTHLY.</div> <div>7. THE GENERAL CONTRACTOR SHALL VERIFY EXISTING CONDITIONS PRIOR TO COMMENCING WORK AND REPORT ANY AND ALL DISCREPANCIES TO THE ARCHITECT.</div> <div>8. CONTRACTOR VEHICLES AND EQUIPMENT NECESSARY FOR CONSTRUCTION MAY BE PARKED ON THE SITE. OTHER VEHICLES PARKED ON THE SITE REQUIRE THE OWNER'S PERMISSION.</div> <div>9. WORK INDICATED AS 'NOT IN CONTRACT', 'NIC', OR 'BY OTHERS', SHALL BE PERFORMED BY OWNER'S SEPARATE CONTRACTORS. THE GENERAL CONTRACTOR SHALL COOPERATE TO THE FULLEST EXTENT WITH ALL OTHER CONTRACTORS AND ASSIST IN COORDINATING THE WORK BY SEPARATE CONTRACTORS WITH THE WORK OF THIS CONTRACT.</div> <div>10. NAMING A CERTAIN BRAND, MAKE OR MANUFACTURER IS TO DESIGNATE THE GENERAL STYLE, TYPE, CHARACTER AND QUALITY STANDARD OF THE PRODUCT DESIRED. SUBSTITUTION REQUESTS MUST BE SUBMITTED PRIOR TO BIDDING.</div> <div>11. ALL MATERIALS/EQUIPMENT SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS. WORK NOT CONSISTENT WITH MANUFACTURER'S RECOMMENDATIONS WILL BE REJECTED BY OWNER/ARCHITECT.</div>	

[illegible]