



NOTE
 ALL ATTIC OPEN AREA SHALL BE DIVIDED INTO
 DRAFT STOPS USING WALL OR TRUSSES W/ GYP. BD.
 ONE SIDE AND SEALED W/ APPROVED CAULK TO
 SEAL TIGHT TO STRUCTURE AND SHEATHING
 ALL FLOOR JOIST SHALL BE BRIDGED W/ CROSS
 OR SOLID WOOD BLKING AT A MAX. OF 8'-0" OC.

BUILDING #2
 ROOF FRAMING PLAN
 SCALE: 3/16" = 1'-0"



LEGEND
 2X HEADER - SEE SHEET (A-17)
 2X6 STRICK BUILT UP EXTENSIONS SPACED AT 24" OC
 PRE - FAB. ENGINEERED ROOF TRUSSES SPACED AT 24" OC

OF -	SHEET F-10	DATE: 07/28/00	JOB No.: -	SCALE: AS NOTED	FILE: -	<p align="center">"CAMELLIA GARDENS"</p> <p align="center">DAMMON ENGINEERING, INC.</p> <p align="center">ARCHITECTS - ENGINEERS</p> <p align="center">819 ROBERT ROAD SLIDELL, LA. 70458</p>	<p align="center">MARK DEVELOPMENT, LLC.</p> <p align="center">CAMELLIA GARDENS POSSUM HOLLOW ROAD SLIDELL, LA</p>
------	---------------	----------------	------------	-----------------	---------	--	--