



NOTE
 ALL ATTIC OPEN AREA SHALL BE DIVIDED INTO DRAFT STOPS USING WALL OR TRUSSES W/GYP. BD. ONE SIDE AND SEALED W/ APPROVED CAULK TO SEAL TIGHT TO STRUCTURE AND SHEATHING
 ALL FLOOR JOIST SHALL BE BRIDGED W/ CROSS OR SOLID WOOD BLKING AT A MAX. OF 8FT OC.

2x6 STICK BUILT IN APPENDAGES TRANSITIONS OR CONNECTING BRIDGES

2x6 STICK BUILT IN APPENDAGES TRANSITIONS OR CONNECTING BRIDGES

BLDG #1
 ROOF FRAMING PLAN
 SCALE: 3/16" = 1'-0"



LEGEND
 2X HEADER - SEE SHEET (A-17)
 2X6 STICK BUILT IN APPENDAGES SPACED AT 24" OC
 PRE - FAB. ENGINEERED ROOF TRUSSES SPACED AT 24" OC

REVISED 01/03/01

DAMMON ENGINEERING, INC. ARCHITECTS - ENGINEERS 819 ROBERT ROAD SLIDELL LA. 70458	"CAMELLIA GARDENS"	MARK DEVELOPMENT, LLC. CAMELLIA GARDENS POSSUM HOLLOW ROAD SLIDELL, LA
SCALE: AS NOTED FILE: - JOB No.: - DATE: 03/24/00	SHEET F-9	