



NOTE:

- 1) ALL ATTIC AREAS SHALL BE DIVIDED INTO AREAS NOT TO EXCEED 300 SQ. FT. APPROVED FIRE CHALK & SEAL TIGHT TO ROOF SHEATHING
- 2) ALL FIRE WALLS SHALL EXTEND TIGHT TO ROOF SHEATHING & SEALED WITH APPROVED FIRE CHALK & SEAL
- 3) ALL ELECTRICAL, MECHANICAL & PLUMBING PENETRATING FIRE WALLS SHALL ALSO BE FIRE CALKED.

LEGEND

UNIT SIZES

- 8 - 2 BR. UNITS @ 850 S.F.
- 2 - 1 BR. UNITS @ 565 S.F.
- 2 - 1 BR. HANDICAPPED UNIT @ 616 S.F.

NOTE:

- 1) SINGLE STORY BLDG. EXTERIOR WALLS AND CORRIDOR WALLS SHALL BE 4" STUDS
- 2) ALL WALLS SEPARATING UNITS SHALL BE 6" STUDS
- 3) ALL PLUMBING WALLS SHALL BE 6" STUDS

REVISED 01/03/01
REVISED 11/20/01

FILE: --
SCALE: AS NOTED
JOB No.: --
DATE: 07/28/00
SHEET
A-4
OF --

"CAMELLIA GARDENS"

DAMMON ENGINEERING, INC.

ARCHITECTS - ENGINEERS

819 ROBERT ROAD SLIDELL, LA. 70458

MARK DEVELOPMENT, LLC.

CAMELLIA GARDENS
POSSUM HOLLOW ROAD
SLIDELL, LA