



FCW Series

Exterior architectural decorative die cast aluminum wall mount

corporate
t 800 900 1730
f 630 889 8106
775 W Belden Ave
Addison, IL 60101

Architectural

Catalog Number

Series	Voltage	Source/Wattage	Ballast	Finish	Accessories
FCW4106	120V	13Q 100 INC	E Electronic	BK Black	EC E-coat
FCW4106P	277V	26PL	M Magnetic	WH White	EMR Emergency back-up, remote (PL only)
	347V (Canada)	32T		CC Custom color	F Fuse
		▷42T			PE Photo Eye
					PMA Single arm pole (fitted for 2-3/8" tenon)

▷ Recommended lamping

Product Information

Listing: U.L. listed for wet locations.

Housing: Including shade, arm and wall canopy are marine grade corrosion resistant heavy walled high pressure die-cast aluminum construction.

Gasket: Neoprene continuous closed cell gasket to seal out contaminants.

Fasteners: Captive and recessed stainless steel, tamper resistant, hex socket screws.

Diffuser: Impact resistant UV stabilized stipple frosted polycarbonate diffuser globe. (Glass lens enclosure.)

Socket: PL: Four pin plug-in type compact fluorescent lamp holder (lamp by others). Holder assures precise optical alignment. **HID:** Medium or G12 base 4KV pulse rated

Socket: PL: Four pin plug-in type compact fluorescent lamp holder (lamp by others). Holder assures precise optical alignment. HID: Medium or G12 base 4KV pulse rated

