



Project:	_____
Location:	_____
Item #:	_____
Quantity:	_____

V-Series Freezers

VF MODELS —

Stainless steel front.
Aluminum sides and interior.

VF-1

VF-2

VF-3



VF-2

Standard Features

- Stainless Steel Fronts for Durability
- Polished Aluminum Sides
- Energy Efficient ABS Thermal Breakers Around Door Jamb
- 5" Diameter Casters
- Recessed Interior Lighting
- Exterior Dial Thermometer
- Lifetime Self-Closing Camlift Hinges with 110° Stay-Open Feature
- Self-Adjusting Magnetic Door Gaskets
- Heavy-Duty Cylinder Locks
- Durable and Energy Efficient ABS Interior Door Liners
- Field Reversible Door Swing
- Door Opening Accepts 20" Wide Pan(s)
- Epoxy Coated Shelves Adjustable on 1" Centers
- Automatic Non-Electric Condensate Disposal System
- Environmentally Friendly R-404A Refrigerant
- Anti-Corrosion Coated Evaporator Coil
- Cord and Plug Attached on 115V Models 12 Amps or Less
- Automatic Defrost

Optional Features:

- Rod Type Pan Slides
- Stainless Steel Angle Type Pan Slides
- Heavy-Duty Swivel Casters with Brakes
- Two Half Doors in Place of One Full Length Door
- Change Door Swing
- Solar Digital Thermometer
- 6" Adjustable Legs

Cabinet:

Victory's Value Packed V-Series Freezers are constructed of heavy gauge, polished stainless steel and aluminum to maintain an attractive appearance and maximum durability for years to come.

Interiors feature coved corners that are easy to clean and maintain. An average of over 2½ inches of foamed-in-place polyurethane insulation throughout the cabinet assures the food storage compartment remains well insulated promoting energy efficiency. The bottom of the storage compartment is made of heavy gauge metal with 3 ½ inches of polyurethane insulation for exceptional strength. Interior lighting is recessed.

Doors:

The self-closing doors stay open at 110° facilitating loading. Each door has a cylinder lock.

Shelving:

Heavy-duty, epoxy coated steel shelves are mounted on pilaster strips and are adjustable on 1" increments. Wide door openings accommodate two 12" x 20", or one 18" x 26" pans/trays per level.

Refrigeration:

All components of the self-contained refrigeration system are mounted on top of the cabinet. The air circulating fans and the forced convection cooling coil are contained in an insulated housing separate from the product zone allowing for maximum food storage capacity. All condensate water is disposed of automatically by the energy efficient non-electric condensate evaporator, no plumbing is required.

The R-404A refrigerant used is environmentally friendly.

Approvals:




Victory Refrigeration specification sheets are available online at www.victory-refrig.com.


CHARACTERISTICS	ONE SECTION Reach-In	TWO SECTION Reach-In	THREE SECTION Reach-In
Width, Overall	26 1/2	52 1/4	77 1/4
Depth, Overall (incl. handles)	33 1/4	33 1/4	34 1/2
Height, Overall (incl. adj. legs)	83 1/4	83 1/4	83 1/4
Depth, Open Door 90°	56 1/2	56 1/2	56 1/2
Clear Door Opening, Width	21 1/4	21 1/4	21 1/4
Clear Full Door Opening, Height	54	54	54
Clear Half Door Opening, Height	25 1/4	25 1/4	25 1/4
Capacity Net (cubic feet)	21.0	45.4	69.0
No. of Full Doors	1	2	3
No. of Half Doors	2	4	6
No. of Shelves	3	6	9
Shelf Area (square feet)	17.1	36.0	54.2
Cabinet Voltage	115/60/1	115/60/1	115/60/1
Feed Wires	2	2	3
Condensing Unit Voltage	115/60/1	115/60/1	208-230/60/1
Condensing Unit Size (HP)	1/2	1/2	1/2
Total Amperes	8.5	12.0	12.9
Plug, NEMA	5-15P	5-15P	Hardwire

Crated dim. & wts.	Ht.	Width	Depth	Cu. Ft.	Lbs.
One Section	83	34 1/2	43	82.2	315
Two Section	83	59	43	143.3	465
Three Section	73	86	43	204.4	620

Dimensional tolerance ± 1/4" Metric dimensions (MM)



Continuous product development may necessitate specification changes and design without notice.

 Victory participates in the KCL CADalog, the most current source of CAD symbols for foodservice designers worldwide. Symbols include standard equipment in plan, side, front and 3-D views, layered for FEDA/FCSI recommended guidelines.