

15.2.1. Off-Street Parking Regulations for All Districts, Except the CBD Districts and Vieux Carré Districts.

Except as otherwise provided in this Ordinance, when any building or structure is heretofore or hereafter erected, structurally altered, or converted, for the uses listed in Column 1 of Table 15.A below, when uses are located in the districts in Column 2, accessory off-street parking spaces shall be provided as required in Column 3 or Column 4 or as required in subsequent sections of this article.

Interpretation of Table 15.A appears in Section 15.2.2.

**Table 15.A**  
**Off-Street Parking Regulations for All Districts,**  
**Except the CBD District and Vieux Carré Districts**  
 (Explanatory notes appear at end of Table)

Column 1	Column 2 <sup>1</sup>	Column 3	Column 4
<i>Use or Use of Category</i>	<i>District</i>	<i>Spaces Required per Basic Measuring Unit</i>	<i>Additional Requirements</i>
Single-family dwelling	RS Districts	2 per dwelling unit	
	All other districts	1 per dwelling unit	
Two-, three-, and four-family dwellings	All districts	1 per dwelling unit	
Town house	All districts	1 per dwelling unit	
Multiple-family dwelling with five or more dwelling units:			
a. Efficiency units	All districts	1 per dwelling unit	
b. One bedroom dwellings	All districts	1.5 per dwelling unit	
c. Two bedroom dwellings	All districts	1.5 per dwelling unit	
d. Three or more bedroom dwellings	All districts	2.5 per dwelling unit	
Rooming, boarding or lodging house	All districts	1 per each 250 square feet of floor area	
Apartment hotel	Medium density districts	1 per dwelling unit or suite	
	High density districts	1 per dwelling unit or suite	
Hotel	Medium density districts	1 per dwelling unit or suite	
	High density districts	1 per dwelling unit or suite	
Tourist home, motel or motor lodge	All districts	1 per dwelling unit or suite	2 for office

THIS WILL NEED:

Foundation Plan

Piling Plan

Roof Framing Plan

Survey w/ Tree, Topo, Utilities

STRAPPING Sheet

Chuck:-

Pls. call

Michael w/ Design

RE: Beulaland

626-1950

Michael  
w/ Design  
Contractors