



101:12.3.2-... SELF
CLOSING DOORS...
D.K.

101:7.2.2.4.1
~~101:7.2.2.4.1~~

101:12.2.2.2
PANIC HARDWARE.

13" MIN.
101:7.1.7.2.2

101:7.2.2.4.1

FLOOR PLAN
SCALE: 1/4" = 1'

GA FILE NO. WP 1072 GENERIC

ONE LAYER 5/8" TYPE X GYPSUM WALLBOARD OR GYPSUM VENEER BASE APPLIED PARALLEL OR AT RIGHT ANGLES TO EACH SIDE OF 3-5/8" STEEL STUDS 24" O.C. WITH 1" TYPE S DRYWALL SCREWS 8" O.C. AT VERTICAL JOINTS AND 12" O.C. AT FLOOR AND CEILING RUNNERS AND INTERMEDIATE STUDS.

JOINTS STAGGERED 24" ON EACH SIDE AND ON OPPOSITE SIDES. SOUND TESTED WITH 3-12" GLASS FIBER FRICTION FIT IN STUD SPACE. (NON-LOAD BEARING)

1 HOUR FIRE 45 TO 49 STC SOUND

THICKNESS:	4-7/8"
APPROX. WEIGHT:	6 PSF
FIRE TEST:	SEE WP 1200 (FM WP-45, 6-19-88); CSU T-1770, 8-81; ULC 79T484, 79T500, 79T497, 8-12-81, ULC DESIGN W415)
SOUND TEST:	NRCC 816-NV, 2-3-81

13" MIN.
101:7.1.7.2.2

MAY 09 2011
#39 7460
STATE FIRE MARSHAL
AS PER REVIEW LETTER
BY JIMMY B. SANDNER

DA
ENGI
C
C
554
SL
OFFI
FA
WWW.D
DAMM
FI
645
PEA
REV:
SCAL
JOB#
DATE:
SHEE
OF 1