



1 FLOOR PLAN-SECOND FLOOR
3/16"=1'-0"

THIS FLOOR SPRINKLED

ROOM FINISH SCHEDULE

NAME	FLOOR	BASE	WALL	CEILING	REMARKS
100 ENTRANCE	VCT				
101 CORRIDOR	CONC. W/SEALER			CLG. HGT.	
102 STAIRS	CERAMIC TILE				
103 WOMEN	CONCRETE				
104 MEN	VINYL BASE				
105 CORRIDOR	CERAMIC TILE				
106 DATA	NONE				
107 FUTURE BUILD-OUT	GYP. BD				
108 ELEV.	CERAMIC TILE				
109 HALL					
110 ELEV. EQUIP.	GYP. BD. PAINTED				
111 SPRINKLER	2'x2' SUSP. ACOUST.				
201 CORRIDOR					
202 WOMEN					
203 MEN					
204 CORRIDOR					
205 DATA					
206 FUTURE BUILD-OUT					
207 SPRINKLER					

DOOR & HARDWARE SCHEDULE

NO.	SIZE	TYPE	FRAME	HINGE	LOOK	ACCESS.	REMARKS
1	PRE 3/0x7/0	SOLID WOOD					
2	3/0x7/0	HOLLOW MTL.					1-HR
3	3/0x7/0	STOREFRONT					VENTED
4	3/0x7/0		STEEL				1-HR
5	2/0x7/0		ALUMINUM				
6	3/0x7/0		WOOD				
7	3/0x7/0			DBL SWING			

WINDOW SCHEDULE

NO.	SIZE	TYPE	FRAME	GLASS	LITES	ACCESS.	REMARKS
1	7/4x6/0	FIXED					
2	9/0x6/0	VERT. SLIDE					
3	9/0x6/0	HORIZ. SLIDE					
4	9/0x6/0	STEEL					
5	9/0x6/0	STEEL					
6	9/0x6/0	ALUM.					
7	9/0x6/0	WOOD					
8	9/0x6/0	TINTED					
9	9/0x6/0	PLAIN					
10	9/0x6/0	INSULATED					
11	9/0x6/0	2/2					
12	9/0x6/0	NONE					
13	9/0x6/0	SCREEN					
14	9/0x6/0	SHUTTER					
15	9/0x6/0	NONE					
16	9/0x6/0	ALARM					