

CLASSIFICATION / SECTION 311 STORAGE GROUP S

**SECTION 311
STORAGE GROUP S**

**2006 International Building Code® / CHAPTER 3 USE AND OCCUPANCY
CLASSIFICATION / SECTION 311 STORAGE GROUP S / 311.1 Storage Group S.**

311.1 Storage Group S.

Storage Group S occupancy includes, among others, the use of a building or structure, or a portion thereof, for storage that is not classified as a hazardous occupancy.

**2006 International Building Code® / CHAPTER 3 USE AND OCCUPANCY
CLASSIFICATION / SECTION 311 STORAGE GROUP S / 311.2 Moderate-hazard
storage, Group S-1.**

311.2 Moderate-hazard storage, Group S-1.

Buildings occupied for storage uses that are not classified as Group S-2, including, but not limited to, storage of the following:

- Aerosols, Levels 2 and 3
- Aircraft repair hangar
- Bags: cloth, burlap and paper
- Bamboos and rattan
- Baskets
- Belting: canvas and leather
- Books and paper in rolls or packs
- Boots and shoes
- Buttons, including cloth covered, pearl or bone
- Cardboard and cardboard boxes
- Clothing, woolen wearing apparel
- Cordage
- Dry boat storage (indoor)
- Furniture
- Furs
- Glues, mucilage, pastes and size
- Grains
- Horns and combs, other than celluloid
- Leather
- Linoleum
- Lumber

*technically Hubcap
is not a repair
garage*

Motor vehicle repair garages complying with the maximum allowable quantities of hazardous materials listed in Table 307.1(1) (see Section 406.6)

I-Quest 2006 Codes Complete Collection

Photo engravings
Resilient flooring
Silks
Soaps
Sugar
Tires, bulk storage of
Tobacco, cigars, cigarettes and snuff
Upholstery and mattresses
Wax candles

**2006 International Building Code® / CHAPTER 3 USE AND OCCUPANCY
CLASSIFICATION / SECTION 311 STORAGE GROUP S / 311.3 Low-hazard storage,
Group S-2.**

311.3 Low-hazard storage, Group S-2.

Includes, among others, buildings used for the storage of noncombustible materials such as products on wood pallets or in paper cartons with or without single thickness divisions; or in paper wrappings. Such products are permitted to have a negligible amount of plastic trim, such as knobs, handles or film wrapping. Storage uses shall include, but not be limited to, storage of the following:

Aircraft hangar
Asbestos
Beverages up to and including 12-percent alcohol in metal, glass or ceramic containers
Cement in bags
Chalk and crayons
Dairy products in nonwaxed coated paper containers
Dry cell batteries
Electrical coils
Electrical motors
Empty cans
Food products
Foods in noncombustible containers
Fresh fruits and vegetables in nonplastic trays or containers
Frozen foods
Glass
Glass bottles, empty or filled with noncombustible liquids
Gypsum board
Inert pigments
Ivory
Meats
Metal cabinets
Metal desks with plastic tops and trim
Metal parts
Metals