

# DAMMON ENGINEERING, INC.

dammonengineering.com

CONSULTING

DESIGN

STUDIES

EXPERT WITNESS

1095 Florida Ave.  
Slidell, LA 70458

P.O. Box 2830  
Slidell, LA 70459  
ADDENDUM # 2

985-649-5832  
FAX 985-641-5950

June 28, 2007

TO: All plan holders of record  
Housing Authority of Slidell

Please note the following changes to the plans for the Housing Authority of Slidell:

1. During the bidder conference on June 27, 2007 the following was reviewed and specific questions were asked.

Question: Do you require that all metal door frames be replaced?

Answer: If the metal is not damaged or rusty the existing frame may be used. Clean and paint.

Question: Is it required that all gas pipes be completely removed?

Answer: All visible gas lines are to be removed. Gas lines overhead or concealed may remain. Any gas lines not removed must remain open with no cap. The gas regulator shall be removed.

The following is added to the bid:

2. Remove and replace all fascia at roofline of building, all sides. Replace all drip edge on roof.
3. Where window A/C unit is to be removed from west wall of building, replace with brick that is removed when installing new windows. Work brick into regular pattern.
4. Where walls are to be removed, or where rough spots on floor exist, use acrylic floor patch to fill any voids. Chip out concrete and install cap on any pipes behind abandoned, prior to patching floor.
5. Demolish cabinets in and on wall of offices and remove fur down to ceiling (kitchen fur down to remain). Patch as required.
6. Remove all borders on walls and patch as required.
7. The Housing Authority will, prior to contract award, perform any mold remediation required.
8. Change order on drawing E-1, in room 105. There are eight wall receptacles on circuit PL1-18. Remove four of these receptacles and create a new 20 A circuit with these four receptacles.

In addition to forms furnished in the packet distributed at the walk through, include:


1. "affidavit" (attached)
2. "Contractors State License Number." Fill out attached form and show license number on face of bid envelope.

Both forms are enclosed herein. We are also including a "Bid Checklist" for your convenience.

**\*\*REMINDER \*\*** Bids will be received until 2:00 p.m., Thursday, July 19, 2007 at Dammon Engineering, Inc.

Contractor must acknowledge receipt of addendum(s) in bid.

Sincerely,



Emmett G (Pete) Dammon, PE