



LEGEND

- REMOVE WALL
- (R) — REMOVE DOOR FOR NEW WALL
- ▨ — REMOVE DUCTWORK
- EXISTING DUCTWORK TO REMAIN
- (R1) — REMOVE WINDOW

NOTE: ALL DOORS SHALL BE REPLACED. SEE DWG A-1.

DEMOLITION PLAN
SCALE: 1/4"=1'-0"

- DEMOLITION NOTES:**
1. DRYWALL TO BE REMOVED AND REPLACED
 4. 1'-0" UP FROM FLOOR EXCEPT IN KITCHEN WHERE ALL DRYWALL WILL BE REMOVED AND REPLACED.
 2. ALL KITCHEN CABINETS TO BE REMOVED AND REPLACED
 3. ALL GAS LINES TO BE REMOVED AND CAPPED AT OUTSIDE OF EXTERIOR WALLS.
 4. ALL GAS WATER HEATERS TO BE REMOVED AND REPLACED WITH ONE 50 GAL. ELECTRIC WATER HEATER.
 5. ALL CEILING TILES & OVERHEAD INSULATION TO BE REMOVED AND REPLACED
 6. CEILING TILE GRID TO BE CLEANED AND REUSED
 7. ALL INTERIOR AND EXTERIOR DOORS TO BE REPLACED
 8. EXISTING DUCTWORK SHALL BE REMOVED WHERE SHOWN. REMAINING DUCTWORK SHALL BE CLEANED AND REUSED. ALL OPENINGS IN DUCTWORK WILL BE CARPED WHERE DUCTS AND VENTS ARE REMOVED.

SCALE(S) NOTED
FILE:
JOB NO. 1882
DATE: 6-4-07
SHEET 3
D-1
OF 13

HOUSING AUTHORITY OF SLIDELL
DAMMON ENGINEERING, INC.
1095 FLORIDA AVENUE 985-849-5852 SLIDELL, LA. 70458
DAMMONENGINEERING.COM

DEMOLITION PLAN
RENOVATE ADMINISTRATION BLDG.
1250 DR. MLK DRIVE
SLIDELL, LA