



# COMcheck Software Version 3.5.3 Envelope Compliance Certificate

## 90.1 (2004) Standard

Report Date: 08/22/08

Data filename: C:\Program Files\Check\COMcheck\ECB-5103 r1 LA.ck

### Section 1: Project Information

Project Type: **New Construction**

Project Title : ECB-5103 r1 LA Business

Construction Site:

Owner/Agent:

Eubanks Custom Builders  
Hwy 19 North  
Butler, GA 31006

Designer/Contractor:

Eubanks Custom Builders  
Hwy 19 North  
Butler, GA 31006  
(478) 862-2803

### Section 2: General Information

Building Location (for weather data):

New Orleans, Louisiana

Heating Degree Days (base 65 degrees F):

1316

Cooling Degree Days (base 50 degrees F):

7343

Building Type for Envelope Requirements:

Non-Residential

Vertical Glazing / Wall Area Pct.:

6%

**Building Type**

Office

**Floor Area**


654

APPROVED

**RADCO**

AUG 22 2008

APPROVED



### Section 3: Requirements Checklist

Envelope PASSES Design: 2008-08-22

#### Climate-Specific Requirements:

Component Name/Description	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U-Factor
Roof 1: Attic Roof with Wood Joists	654	30.0	0.0	0.034	0.034
Exterior Wall 1: Wood Frame, Any Spacing	1083	13.0	0.0	0.089	0.089
Window 1: Metal Frame: Single Pane, Clear, Fixed, SHGC 0.25, PF 0.10	60	---	---	0.700	1.220
Door 2: Insulated Metal, Swinging	40	---	---	0.690	0.700
Floor 1: Wood-Framed	654	19.0	0.0	0.051	0.051

(a) Budget U-factors are used for software baseline calculations ONLY, and are not code requirements.

#### Insulation:

- 1. Open-blown or poured loose-fill insulation has not been used in attic roof spaces with ceiling slope greater than 3 in 12.
- 2. Wherever vents occur, they are baffled to deflect incoming air above the insulation.
- 3. Recessed lights, equipment and ducts are not affecting insulation thickness.
- 4. No roof insulation is installed on a suspended ceiling with removable ceiling panels.
- 5. All exterior insulation is covered with protective material.
- 6. Cargo and loading dock doors are equipped with weather seals.

#### Fenestration and Doors:

- 7. Windows and skylights are labeled and certified by the manufacturer for U-factor and SHGC.

- 8. Fixed windows and skylights unlabeled by the manufacturer have been site labeled using the default U-factor and SHGC.
- 9. Other unlabeled vertical fenestration, operable and fixed, that are unlabeled by the manufacturer have been site labeled using the default U-factor and SHGC. No credit has been given for metal frames with thermal breaks, low-emissivity coatings, gas fillings, or insulating spacers.


**Air Leakage and Component Certification:**

- 10. All joints and penetrations are caulked, gasketed, weather-stripped, or otherwise sealed.
- 11. Windows, doors, and skylights certified as meeting leakage requirements.
- 12. Component R-values & U-factors labeled as certified.
- 13. Insulation installed according to manufacturer's instructions, in substantial contact with the surface being insulated, and in a manner that achieves the rated R-value without compressing the insulation.

**Section 4: Compliance Statement**

*Compliance Statement:* The proposed envelope design represented in this document is consistent with the building plans, specifications and other calculations submitted with this permit application. The proposed envelope system has been designed to meet the 90.1 (2004) Standard requirements in COMcheck Version 3.5.3 and to comply with the mandatory requirements in the Requirements Checklist.

PHILIP L. WITHERINGTON, P.E.  
Name - Title

  
Signature

8/22/08  
Date

APPROVED  
RADCO  
AUG 22 2008  
APPROVED



COMcheck Software Version 3.5.3  
**Interior Lighting and Power  
 Compliance Certificate**

**90.1 (2004) Standard**

Report Date: 08/22/08

Data filename: C:\Program Files\Check\COMcheck\ECB-5103 r1 LA.cck

**Section 1: Project Information**

Project Type: **New Construction**

Project Title : ECB-5103 r1 LA Business

Construction Site:

Owner/Agent:

Eubanks Custom Builders  
 Hwy 19 North  
 Butler, GA 31006

Designer/Contractor:

Eubanks Custom Builders  
 Hwy 19 North  
 Butler, GA 31006  
 (478) 862-2803

**Section 2: General Information**

Building Use Description by:

Building Type

Office

Floor Area

654

**Section 3: Requirements Checklist**

**Interior Lighting:**

- 1. Total proposed watts must be less than or equal to total allowed watts.

Allowed Watts	Proposed Watts	Complies
654	494	YES

- 2. Exit signs 5 Watts or less per side.

**Controls, Switching, and Wiring:**

- 3. Independent manual or occupancy sensing controls for each space (remote switch with indicator allowed for safety or security).
- 4. Occupant sensing control in class rooms, conference/meeting rooms, and employee lunch and break rooms.

*Exceptions:*

Spaces with multi-scene control; shop classrooms, laboratory classrooms, and preschool through 12th grade classrooms.

- 5. Automatic shutoff control for lighting in >5000 sq.ft buildings by time-of-day device, occupant sensor, or other automatic control.

*Exceptions:*

24 hour operation lighting; patient care areas; where auto shutoff would endanger safety or security.

- 6. Master switch at entry to hotel/motel guest room.
- 7. Separate control device for display/accent lighting, case lighting, task lighting, nonvisual lighting, lighting for sale, and demonstration lighting.
- 8. Photocell/astromical time switch on exterior lights.

*Exceptions:*

Covered vehicle entrance/exit areas requiring lighting for safety, security and eye adaptation.

- 9. Tandem wired one-lamp and three-lamp ballasted luminaires (No single-lamp ballasts).

*Exceptions:*

- Electronic high-frequency ballasts;
- Luminaires not on same switch;
- Recessed luminaires 10 ft. apart or surface/pendant not continuous;

**APPROVED**  
**RADCO**  
 AUG 22 2008  
**APPROVED**

Luminaires on emergency circuits.

**Voltage Drop:**

- 10. Feeder conductors have been designed for a maximum voltage drop of 2 percent.
- 11. Branch circuit conductors have been designed for a maximum voltage drop of 3 percent.

**Section 4: Compliance Statement**

*Compliance Statement:* The proposed lighting design represented in this document is consistent with the building plans, specifications and other calculations submitted with this permit application. The proposed lighting system has been designed to meet the 90.1 (2004) Standard requirements in COMcheck Version 3.5.3 and to comply with the mandatory requirements in the Requirements Checklist.

Philip L. Witherington, P.E.  
Name - Title

  
Signature

8/22/08  
Date

**Section 5: Post Construction Compliance Statement**

**Record Drawings and Operating and Maintenance Manuals:**

- 1. Construction documents with record drawings and operating and maintenance manuals provided to the owner.

\_\_\_\_\_  
Lighting Designer or Contractor Name

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Date

APPROVED  
**RADCO**  
AUG 22 2008  
APPROVED



COMcheck Software Version 3.5.3

# Interior Lighting Application Worksheet

## 90.1 (2004) Standard

Report Date:

Data filename: C:\Program Files\Check\COMcheck\ECB-5103 r1 LA.cck

### Section 1: Allowed Lighting Power Calculation

A	B Floor Area	C Allowed Watts / ft <sup>2</sup>	D Allowed Watts
Office	654	1	654
Total Allowed Watts =			654

### Section 2: Proposed Lighting Power Calculation

A Fixture ID : Description / Lamp / Wattage Per Lamp / Ballast	B Lamps/ Fixture	C # of Fixtures	D Fixture Watt.	E (C X D)
Office (54 sq ft)				
Linear Fluorescent 1: 1: Fluorescent Lighting / 48" T12 ES 34W / Electronic	2	7	62	134
Incandescent 1: 2: Bathroom Lights / Incandescent 60W	1	1	60	60
Total Proposed Watts =				494

### Section 3: Compliance Calculation

If the Total Allowed Watts minus the Total Proposed Watts is greater than or equal to zero, the building complies.

Total Allowed Watts =	654
Total Proposed Watts =	494
Project Compliance =	160

Interior Lighting PASSES Design 24% (with 5% code)

**APPROVED**  
**RADCO**  
**AUG 22 2008**  
**APPROVED**



COMcheck Software Version 3.5.3

# Exterior Lighting Compliance Certificate

## 90.1 (2004) Standard

Report Date: 08/22/08

Data filename: C:\Program Files\Check\COMcheck\ECB-5103 r1 LA.cck

### Section 1: Project Information

Project Type: **New Construction**

Project Title : ECB-5103 r1 LA Business

Construction Site:

Owner/Agent:

Eubanks Custom Builders  
Hwy 19 North  
Builcr. GA 31006

Designer/Contractor:

Eubanks Custom Builders  
Hwy 19 North  
Butler, GA 31006  
(478) 862-2803

### Section 2: Exterior Lighting Area/Surface Power Calculation

A Exterior Area/Surface	B Quantity	C Allowed Watts / Unit	D Tradable Wattage	E Allowed Watts (C x D)	F Proposed Watts
Main entry/exit	3 ft of door width	30	Yes	90	60
Other entry/exit	3 ft of door width	20	Yes	60	60
Total Tradable Watts* =				150	120
Total Allowed Watts =				150	
Total Allowed Supplemental Watts** =				8	

\* Wattage tradeoffs are only allowed between tradable areas/surfaces.

\*\* A supplemental allowance equal to 5% of total allowed wattage may be applied toward compliance of both non-tradable and tradable areas/surfaces.

### Section 3: Exterior Lighting Fixture Schedule

A Fixture ID : Description / Lamp / Wattage Per Lamp / Ballast	B Lamps/ Fixture	C # of Fixtures	D Fixture Watt.	E (C X D)
Main entry/exit (3 ft of door width): Tradable Wattage				
Incandescent 1: Incandescent 60W	1	1	60	60
Other entry/exit (3 ft of door width): Tradable Wattage				
Incandescent 1 copy 1: Incandescent 60W	1	1	60	60
Total Tradable Proposed Watts =				120

### Section 4: Requirements Checklist

#### Lighting Wattage:

1. Within each non-tradable area/surface, total proposed watts must be less than or equal to total allowed watts. Across all tradable areas/surfaces, total proposed watts must be less than or equal to total allowed watts.

Compliance: Passes.

#### Controls, Switching, and Wiring:

2. All exemption claims are associated with fixtures that have a control device independent of the control of the nonexempt lighting.
3. All nonexempt lighting fixtures shall be controlled by a photosensor or astronomical time switch that is capable of automatically turning off the fixture when sufficient daylight is available or the lighting is not required.

Project Title: ECB-5103 r1 LA Business

Data filename: C:\Program Files\Check\COMcheck\ECB-5103 r1 LA.cck

Report date: 08/22/08

Page 6 of 11

**APPROVED**  
**RADCO**  
AUG 27 2008  
**CHENGLIN**

**Exterior Lighting Efficacy:**


- 4. All exterior building grounds luminaires that operate at greater than 100W have minimum efficacy of 60 lumens/watt.  
*Exceptions:*

Exterior Lighting PASSES Design 25% greater than code.

**Section 5: Compliance Statement**

*Compliance Statement:* The proposed exterior lighting design represented in this document is consistent with the building plans, specifications and other calculations submitted with this permit application. The proposed lighting system has been designed to meet the 90.1 (2004) Standard requirements in COMcheck Version 3.5.3 and to comply with the mandatory requirements in the Requirements Checklist.

PHILIP L. WILKINSON, P.E.  
Name - Title

  
Signature

8/22/08  
Date

APPROVED  
RADCO  
AUG 27 2008  
APPROVED



COMcheck Software Version 3.5.3

# Mechanical Compliance Certificate

## 90.1 (2004) Standard

Report Date: 08/22/08

Data filename: C:\Program Files\Check\COMcheck\ECB-5103 r1 LA.cck

## Section 1: Project Information

Project Type: **New Construction**

Project Title: ECB-5103 r1 LA Business

Construction Site:

Owner/Agent:

Eubanks Custom Builders  
Hwy 19 North  
Butler, GA 31006

Designer/Contractor:

Eubanks Custom Builders  
Hwy 19 North  
Butler, GA 31006  
(478) 862-2803

## Section 2: General Information

Building Location (for weather data): **New Orleans, Louisiana**

Heating Degree Days (base 65 degrees F): **1316**

Cooling Degree Days (base 50 degrees F): **7343**

## Section 3: Mechanical Systems List

### Quantity System Type & Description

- 1 HVAC System 1: Heating: Other, Electric, Heating Capacity <65 kBtu/h / Cooling: Other, Capacity <54 kBtu/h, Air-Cooled Condenser / Single Zone
- 1 Storage Water Heater 1: Electric Storage Water Heater, Capacity: 6 gallons

## Section 4: Requirements Checklist

### Requirements Specific To: HVAC System 1 :

- 1. Hot gas bypass limited to 50% of total cooling capacity

### Requirements Specific To: Storage Water Heater 1 :

- 1. Hot water system sized per manufacturer's sizing guide
- 2. No efficiency requirements for water heater with storage capacity less than 20 gallons.
- 3. First 8 ft of outlet piping is insulated
- 4. Hot water storage temperature adjustable down to 120 degrees F or lower
- 5. Heat traps provided on inlet and outlet of storage tanks

### Generic Requirements: Must be met by all systems to which the requirement is applicable:

- 1. Load calculations per 2001 ASHRAE Fundamentals
- 2. Thermostatic controls has 5 degrees F deadband
  - Exception: Thermostats requiring manual changeover between heating and cooling
- 3. Hot water pipe insulation: 1 in. for pipes <=1.5 in. and 2 in. for pipes >1.5 in. Chilled water/refrigerant/brine pipe insulation: 1 in. for pipes <=1.5 in. and 1.5 in. for pipes >1.5 in. Steam pipe insulation: 1.5 in. for pipes <=1.5 in. and 3 in. for pipes >1.5 in.
  - Exception: Piping within HVAC equipment
  - Exception: Fluid temperatures between 55 and 105 degrees F
  - Exception: Fluid not heated or cooled
  - Exception: Runouts <4 ft in length

**APPROVED**  
**RADCO**  
**AUG 22 2008**  
**APPROVED**

- 4. Piping, insulated to 1/2 in. if nominal diameter of pipe is <1.5 in.; Larger pipe insulated to 1 in. thickness
- 5. Lavatory faucet outlet temperatures in public restrooms limited to 110 degrees F (43 degrees C)
- 6. Where separate thermostats are used for heating and cooling, acceptable measures are used to prevent simultaneous heating and cooling
- 7. Stair and elevator shaft vents are equipped with motorized dampers
- 8. Acceptable measures used to prevent simultaneous humidification and dehumidification
  - Exception: Desiccant systems and systems for uses requiring specific humidity levels (approval required)
- 9. Automatic controls for freeze protection systems present
- 10. Automatic ventilation controls (e.g., CO2 controls) or exhaust air heat recovery present for high design occupancy areas (>100 person/1000 ft2) with >3,000 cfm outside air capacities
- 11. Duct, plenum, and piping insulation surfaces suitably protected from weather, moisture, or likely damage
- 12. Duct Sealing: Pressure sensitive tape is not used as the primary sealant. Longitudinal and transverse seams for ducts in unconditioned spaces. Longitudinal and transverse seams and duct wall penetrations for ducts outside the building. Transverse seams on buried ducts
- 13. R-6 for supply air ducts located outside the building, in ventilated attics and in unvented attic above insulated ceiling. R-3.5 for supply air ducts in unvented attic with roof insulation, unconditioned and underground spaces. R-3.5 for return air ducts located outside the building, in ventilated attics and in unvented attic above insulated ceiling
- 14. Humidistat controls prevent reheating, recooling, and mixing of mechanically heated air with mechanically cooled air
- 15. Exhaust air heat recovery included for systems 5,000 cfm or greater with more than 70% outside air fraction or specifically exempted
- 16. Kitchen hoods >5,000 cfm provided with 50% makeup air that is uncooled and heated to no more than 60 degrees F unless specifically exempted
- 17. Buildings with turn hood systems must have variable air volume hood design, exhaust heat recovery, or separate makeup air supply meeting the following: a) 75% make up air quantity, and for b) within 2 degrees F of room temperature and/or c) no humidification d) no simultaneous heating and cooling

### Section 5: Compliance Statement

*Compliance Statement:* The proposed mechanical design represented in this document is consistent with the building plans, specifications and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 90.1 (2004) Standard requirements in COMcheck Version 3.5.3 and to comply with the mandatory requirements in the Requirements Checklist.

PAUL L. WITHERINGTON, P.E.

Name - Title

*[Signature]*

Signature

8/22/08

Date

### Section 6: Post Construction Compliance Statement

- HVAC record drawings of the actual installation and performance data for each equipment provided to the owner within 90 days after system acceptance.
- HVAC O&M documents for all mechanical equipment and system provided to the owner within 90 days after system acceptance.
- Written HVAC balancing report provided to the owner.

The above post construction requirements have been completed.

Principal Mechanical Designer-Name

Signature

Date

**APPROVED**  
**RADCO**  
**AUG 21 2008**  
**APPROVED**



COMcheck Software Version 3.5.3

# Mechanical Requirements Description

## 90.1 (2004) Standard

Report Date:

Data filename: C:\Program Files\Check\COMcheck\ECB-5103 r1 LA.cck

The following list provides more detailed descriptions of the requirements in Section 4 of the Mechanical Compliance Certificate.

### Requirements Specific To: HVAC System 1 :

1. For cooling systems  $\leq 240$  kBtu/h, maximum hot gas bypass capacity must be no more than 50% total cooling capacity.

### Requirements Specific To: Storage Water Heater 1 :

1. Service water heating system design loads for the purpose of sizing systems and equipment must be determined in accordance with manufacturers' published sizing guidelines.
2. Service water heating equipment used solely for heating potable water, pool heaters, and hot water storage tanks must meet the following minimum efficiency: No efficiency requirements for water heater with storage capacity less than 20 gallons.
3. Insulation must be provided for the first 8 ft of outlet piping for a constant temperature nonrecirculating storage system and for the inlet pipe between the storage tank and a heat trap in a storage system.
4. Temperature controls must be provided that allow for storage temperature adjustment from 120 degrees F or lower to a maximum temperature compatible with the intended use except when the manufacturer's installation instructions specify a higher minimum thermostat setting to minimize condensation and resulting corrosion. Documentation of the installation instructions must be provided to be exempted from this requirement.
5. Heat traps must be provided on inlet and outlet vertical pipe risers serving storage water heaters and storage tanks not having integral heat traps and serving a nonrecirculating system. Heat traps must be installed as close as practical to the storage tank. Acceptable heat traps are either a) a device specifically designed for the purpose or b) an arrangement of tubing that forms a loop of 360 degrees F, or c) piping that from the point of connection to the water heater (inlet or outlet) includes a length of piping directed downwards before connection to the vertical piping of the supply water or hot water distribution system.

### Generic Requirements: Must be met by all systems to which the requirement is applicable:

1. Design heating and cooling loads for the building must be determined using procedures in the ASHRAE Handbook of Fundamentals or an approved equivalent calculation procedure.
2. Thermostats controlling both heating and cooling must be capable of maintaining a 5 degrees F deadband (a range of temperature where no heating or cooling is provided).
  - Exception: Deadband capability is not required if the thermostat does not have automatic changover capability between heating and cooling.
3. All pipes serving space-conditioning systems must be insulated as follows: Hot water piping for heating systems: 1 in. for pipes  $\leq 1$  1/2-in. nominal diameter 2 in. for pipes  $> 1$  1/2-in. nominal diameter. Chilled water, refrigerant, and brine piping systems: 1 in. insulation for pipes  $\leq 1$  1/2-in. nominal diameter 1 1/2 in. insulation for pipes  $> 1$  1/2-in. nominal diameter. Steam piping: 1 1/2 in. insulation for pipes  $\leq 1$  1/2-in. nominal diameter 3 in. insulation for pipes  $> 1$  1/2-in. nominal diameter.
  - Exception: Pipe insulation is not required for factory-installed piping within HVAC equipment.
  - Exception: Pipe insulation is not required for piping that conveys fluids having a design operating temperature range between 55 degrees F and 105 degrees F.
  - Exception: Pipe insulation is not required for piping that conveys fluids that have not been heated or cooled through the use of fossil fuels or electric power.
  - Exception: Pipe insulation is not required for runout piping not exceeding 4 ft in length and 1 in. in diameter between the control valve and HVAC coil.
4. Service hot water piping, where required, must be insulated to 1/2 in. if pipe less than 1.5 in. nominal diameter. Larger pipe must be insulated to 1 in.. Pipe insulation will have a conductivity of less than 0.26 Btu.in/(h-ft<sup>2</sup>-degrees F).
5. Temperature controlling means must be provided to limit the maximum temperature of water delivered from lavatory faucets in public facility restrooms to 110 degrees F.
6. Where zone heating and cooling are controlled by separate zone thermostats, means (such as limit switches, mechanical stops, or, for DDC systems, software programming) must be provided to prevent simultaneous heating and cooling to the zone.
7. Stair and elevator shaft vents must be equipped with motorized dampers capable of being automatically closed during normal building operation and interlocked to open as required by fire and smoke detection systems. All primary outdoor air supply and exhaust hoods,

vents, and ventilators must be equipped with motorized dampers that will automatically shut when the spaces served are not in use. Exceptions: - Gravity (non-motorized) dampers are acceptable in buildings less than three stories in height above grade. - Ventilation systems serving unconditioned spaces.

8. Where a zone is served by a system(s) with both humidification and dehumidification capability, means (such as limit switches, mechanical stops, or software programming) must be provided to prevent simultaneous operation of humidification and dehumidification equipment.
  - Exception: Zones served by desiccant systems, used with direct evaporative cooling in series; Systems serving zones where specific humidity levels are required.
9. All freeze protection systems, including self-regulating heat tracing, must include automatic controls capable of shutting off the systems when outside air temperatures are above 40 degrees F or when the conditions of the protected fluid will prevent freezing. Snow- and ice-melting systems must include automatic controls capable of shutting off the systems when the pavement temperature is above 50 degrees F and no precipitation is falling, and an automatic or manual control that will allow shutoff when the outdoor temperature is above 40 degrees F.
10. Systems with design outside air capacities >3,000 cfm serving areas having an average design occupancy density exceeding 100 people per 1000 ft<sup>2</sup> must include means to automatically reduce outside air intake below design rates when spaces are partially occupied. Ventilation controls must be in compliance with ASHRAE Standard 62 and local standards.
11. Duct and pipe insulation exposed to weather must be suitable for outdoor service; e.g., protected by aluminum, sheet metal, painted canvas, or plastic cover. Cellular foam insulation must be protected as above or painted with a coating that is water retardant and provides shielding from solar radiation that can cause degradation of the material. Insulation covering chilled water piping, refrigerant suction piping, or cooling ducts located outside the conditioned space must include a vapor retardant located outside the insulation (unless the insulation is inherently vapor retardant), all penetrations and joints of which must be sealed.
12. Duct Sealing Requirements: - Pressure sensitive tape prohibited as the primary sealant - Longitudinal and transverse seams for ducts in unconditioned spaces - Longitudinal and transverse seams and duct wall penetrations for ducts outside the building - Transverse seams on buried ducts
13. All supply and return ducts and plenum installed as part of an HVAC air distribution system must be thermally insulated: R-6 for supply air ducts located outside the building, in ventilated attics and in unvented attic above insulated ceiling, R-3.5 for supply air duct insulation in unvented attic with roof insulation, unconditioned and underground spaces, R-3.5 for return air ducts located outside the building, in ventilated attics and in unvented attic above insulated ceiling.
14. Where humidistat controls are provided, such controls must prevent reheating, mixing of hot and cold air streams, or other means of simultaneous heating and cooling of the same air stream. Exceptions: - capability to first reduce flow rate - cooling capacity <80 kBtu/h and capability to unload cooling equipment - cooling capacity <40 kBtu/h - rigid humidity requirements - site-recovered or site-solar energy sources or - use of a desiccant systems.
15. Individual fan systems with a design supply air capacity of 5000 cfm or greater and minimum outside air supply of 70% or greater of the supply air capacity must have an energy recovery system with at least a 50% effectiveness. Exceptions: - Systems serving spaces that are not cooled and heated to <60 degrees F. - Commercial kitchen hoods (grease) classified as Type 1 by NFPA 96 - Systems exhausting toxic, flammable, paint, or corrosive fumes or dust. If an air economizer is also required, heat recovery must be bypassed or controlled to permit air economizer operation.
16. Individual kitchen exhaust hoods larger than 5000 cfm must be provided with make-up air sized for at least 50% of exhaust air volume that is uncooled and either unheated or heated to no more than 60 degrees F. Exceptions: - Where hoods are used to exhaust ventilation air that would otherwise exfiltrate or be exhausted by other fan systems. - Certified grease extractor hoods that require a face velocity no >80 fpm.
17. Buildings with fume hood systems having a total exhaust rate >15,000 cfm must either have variable air volume hood design, exhaust air heat recovery, or separate make up air supply meeting the following makeup air requirements: - at least 75% of exhaust flow rate - heated to no more than 2 degrees F below room setpoint temperature - cooled to no lower than 2 degrees F above room setpoint temperature - no humidification added - no simultaneous heating and cooling

APPROVED  
**RADCO**  
AUG 22 2018  
APPROVED



