

MLE/MLG20PRB

EXPORT MODEL MLE/MLG20PNB

MAYTAG® COMMERCIAL
ENERGY ADVANTAGE™
STACK WASHER/DRYER



LEGENDARY MAYTAG DEPENDABILITY

Maximizing your equipment investment for over a half century.

CEE TIER III RATED

WF: 3.74
MEF: 2.49



MORE ENERGY-SAVING SOLUTIONS THAN ANY OTHER BRAND

Maytag built the first appliance ever to receive the ENERGY STAR® label. Today we offer more high-efficiency laundry appliances than any other brand—from energy-efficient dryers to highly efficient ENERGY STAR®-qualified washers—to help you save money and build profits.

MICROPROCESSOR CONTROLS

Maytag® Computer Trac® controls are easy to program and operate. Plus, they give owners the flexibility to set vend prices by day, time, water temperature and Super Cycle options.

SAVE SPACE AND CUT UTILITY COSTS

A Maytag® Commercial Energy Advantage™ stack washer/dryer gives you a full-size, high-efficiency washer and a super-capacity dryer in the space of a washer alone. Plus the ENERGY STAR® rating means you'll save on utility bills.

FOR YOUR CUSTOMERS:

- Single Payment System
- Large Capacity For Bulky Items—3.1 cu. ft. Capacity Washer/ 6.7 cu. ft. Capacity Dryer
- High-Speed Extraction Cuts Drying Time (as high as 1,000 RPMs)
- 180° Door Opening With Heavy-Duty Die-Cast Hinge, Washer Only
- Front Control Panel 20° Angle For Easy Viewing
- Easy-To-Use One-Touch Cycle Selection
- Quick Cycle Reduces Total Wash Time
- Washer is ADA-Compliant

FOR YOUR OPERATION:

- High-Efficiency Washer Meets CEE Tier III Rating
- Super Cycle Option Increases Revenue
- Accu Trac® Audit System With Two-Way Data Communication
- Automatic Load Balancing
- Built-in Oversudsing Protection
- TurboVent™ Dryer Technology
- Reversible Door, Dryer Only

BUILT-TO-LAST™ FEATURES:

- Precision Endurance Drive
- 5-Year Limited Warranty—All Parts Covered

LAUNDRY SOLUTIONS
YOU CAN *DEPEND ON.*

SAVE UP TO 60% YEARLY*
ON ENERGY, WATER AND SEWER COSTS

visit maytagcommerciallaundry.com
or call 800-662-3587

*Maytag® Commercial front-load washer compared to commercial top-load washer. Individual savings may vary.

MY120125



OUR COMMITMENT TO DEPENDABLE QUALITY

At Maytag, we believe durable goods should remain just that. That's why every Maytag® product is constructed of the highest-quality materials and with the utmost in precision craftsmanship. It's also why we stand behind our equipment with solid service and support from our professional Maytag laundry suppliers. Simply put, when you choose Maytag® products, you ensure your peace of mind.



MLE/MLG20PRB MAYTAG® COMMERCIAL ENERGY ADVANTAGE™ STACK WASHER/ DRYER MICROPROCESSOR CONTROL


WASHER SPECIFICATIONS	
MODEL	MLE/MLG20PRB
EXPORT MODELS	MLE/MLG20PNB
MOTOR	
120V, 60 Hz, variable-speed, reversible, thermoprotected, high-efficiency, controlled induction	Yes
Export models—220–240V, 50 Hz	Yes
Wash—HP (kw)	.09 (.07)
Extract—HP (kw)	.54 (.40)
Average washer energy consumption per cycle (kWh)	.054
CAPACITY	
Cylinder volume—cu.ft. (liters)	3.1 (88)
Cylinder diameter—in. (mm)	21.6 (549)
Cylinder depth—in. (mm)	13.4 (340)
WATER INLET/HOSE	
Inlet hose length/drain hose length—ft. (m)	4 (1.22)/6 (1.83)
Water supply pressure—Psi (bar)	20–100 (1–8)
APPROXIMATE WATER USAGE—GALLONS (LITERS)	
Average hot water usage, hot water cycle	3.4 (12.8)
Average hot water usage, warm water cycle	1.6 (6.1)
Average total water usage per cycle	12.4 (47)*
SPEED	
Wash speed—RPM	40
Extract speed—max RPM/max g-force	1,000/306
BREAKER/FUSE MINIMUM REQUIREMENTS	
MLE electric models—amps	30
MLE Canadian electric models—amps	40
MLG gas model/export gas model—amps	15/10
SOUND LEVEL (export model only, washer & dryer)	
Sound pressure level, Lpa (dBA) (Kpa: +/-3.6dBA)	58
DRYER SPECIFICATIONS	
MOTOR	
Variable-speed, reversible, thermoprotected, high-efficiency, controlled induction	Yes
HP (kw)	.33 (25)
Tumble speed—RPM	50 +/- 1
CAPACITY—CU. FT. (LITERS)	
	6.7 (190)
ELECTRICAL REQUIREMENTS—VOLTS/HZ	
MLE electric model—MLG gas model	240/60—120/60
Export models	220–240/50
HEATING ELEMENT RATING	
MLE electric domestic models/export models—watts	5,600/4,600
MLE electric Canadian models—watts	5,250
MLG gas domestic models—BTU/hr. (kcal/hr.)	24,000 (6,048)
MLG gas export models—BTU/hr. (kcal/hr.)	20,000 (5,040)
GAS INLET	
MDG model—in.	3/8 N.P.T.
AIRFLOW	
MDG gas models—cfm (cmm)	230 (6.5)
MDE electric models—cfm (cmm)	215 (6.1)
ADJUSTABLE LEVELING LEGS	
	Yes
COLOR	
	White
APPROXIMATE WEIGHT	
Crated—lbs (kg) electric/gas	369 (167)
Uncrated—lbs (kg) electric/gas	358 (162)
DIMENSIONS	
Width—in. (mm)	27 (686)
Depth—in. (mm)	29.5 (749)
Product height—in. (mm)	74 (1880)
Door opening—Washer—sq. in.	143
Door opening—Dryer—sq. in.	191
WARRANTY	
	5-Year

*Average based on DOE J1 testing with factory preset cycles.
Because of continuous product improvements, Maytag reserves the right to change specifications without notice.



5 YEAR LIMITED WARRANTY ALL PARTS COVERED

For a period from the date of original purchase through the time listed above, the designated parts that fail in normal commercial use will be repaired or replaced free of charge for the part itself, with the owner paying all other costs, including labor, transportation and customs duty. Chemical damage is excluded from all warranty coverage. See complete warranty for details.



NEW YORK CITY
M.E.A.

