

STATE OF LOUISIANA
Department of Public Safety and Corrections
Office of State Fire Marshal Code Enforcement and Building Safety
8181 Independence Boulevard
Baton Rouge, Louisiana 70806
225-925-4920

H "BUTCH" BROWNING
FIRE MARSHAL

NEW CONSTRUCTION

KEVIN KINCHEN
DAMMON ENGINEERING, INC.
554 OLD SPANISH TRAIL
SLIDELL, LA 70458-0000

RE: P0437655
DR. FARZAD ADULI
MARIGOLD DR
LOT 288
COVINGTON, LA 70435

NFPA 101, 2009
IBC, 2009 (CHAPTERS 9 & 10)

MERCANTILE CLASS B

Dear Applicant:

This is to advise that we have reviewed the drawings and specifications for the subject proposed construction and have determined that they appear to satisfactorily comply with the adopted laws, codes, rules and regulations of The State Fire Marshal subject to the following requirements:

1. **Scope of Work: This review is for 8,000 sq. ft. of Mercantile Occupancy.**
2. **This review does NOT apply to work in UNDEVELOPED SPACES, or NOTES referring to LEASE SPACE, indicated in drawings. Before any work is commenced in that area, plans and specifications shall be reviewed by this office.**
3. **A REVIEW FOR COMPLIANCE WITH THE FIRE PROTECTION AND EGRESS REQUIREMENTS OF CHAPTERS 9 AND 10 OF THE INTERNATIONAL BUILDING CODE IS INCLUDED IN THIS REVIEW. Review for compliance with all other requirements of the LOUISIANA STATE UNIFORM CONSTRUCTION CODE, in accordance with Act 12 of the 2005 First Extraordinary Session of the Louisiana Legislature, IS NOT INCLUDED IN THIS REVIEW. Contact the building official of the applicable political subdivision to coordinate compliance with these requirements. LRS 40:1730.23 mandates the enforcement of building codes by municipalities and parishes in Louisiana, as described by LRS 40:1730.28.**

Note: In accordance with LRS 40:1730.39.A, this office may establish contract agreements with municipalities and parishes in order to provide uniform construction code enforcement on their behalf, as provided in LRS 40:1730.24. Please visit our web site at <http://www.dps.state.la.us/sfm/index.htm> for a current list of jurisdictions requesting plan review by this office, a fee schedule, and a checklist of information required for review.

PROVIDE A DUPLICATE SET OF PLANS AND SPECIFICATIONS TO THE BUILDING OFFICIAL (OR THIRD-PARTY) FOR REVIEW AND/OR PERMITTING, THE STATE FIRE

Aug 27, 2013
P0437655 - PAGE 1

MARSHAL REVIEWED AND STAMPED DOCUMENTS SHALL NOT BE USED FOR THIS PURPOSE. ADDITIONAL MARKING OR ALTERATIONS MADE TO THE APPROVED STAMPED PLANS MAY CAUSE DELAYS IN FINAL ACCEPTANCE FOR OCCUPANCY.

4. **LRS 40:1730.45 and LAC 55:V:2601** The documentation provided for the subject facility appears to comply with The Commercial Building Energy Conservation Code based on ANSI/ASHRAE/IESNA 90.1- 2007, or the International Energy Conservation Code, 2009 edition, as applicable.

NOTE: THE COMMENTS LISTED BELOW IDENTIFY APPARENT DEFICIENCIES DETECTED IN OUR REVIEW OF THE DOCUMENTS SUBMITTED.

5. **101:36.3.6 and IBC 1018.1** Separate corridors from use areas with minimum 1-hour construction and self-closing 20 minute labeled opening protection. Wall construction shall be in accordance with 101:8.3 for fire barriers.
6. **101:8.2.2.3** Fire compartments shall be formed by fire barriers that are continuous from foundation through all intervening construction to the roof deck or floor deck, from outside wall to outside wall or from fire barrier to fire barrier, including continuity through all concealed spaces, such as those found above a ceiling, including interstitial spaces.
7. **101:8.3.5** Penetrations through rated construction shall be sealed by approved firestop systems or devices tested in accordance with ASTM E-814 or ANSI/UL 1479 or by assemblies of firestopping materials capable of preventing the passage of flames and hot gases when tested and rated in accordance with NFPA 251. (This requirement applies for elevator controls on shaft walls, electrical outlets, light switches, etc.).
 - a) Notify the District Office identified at the end of this letter for inspection of all completed fire and/or smoke barrier walls before any construction is installed that would conceal such construction and prevent a proper inspection. Access to randomly selected areas may be required by the inspector at time of final inspection if this notification is not given.
 - b) Provide detailed instructive cut sheets of the fire penetration sealing system used to the inspector at time of inspection. Random selective sampling by the contractor will be observed by the inspector.

NOTE: THE FOLLOWING COMMENTS IDENTIFY ISSUES FOR INFORMATIONAL AND CAUTIONARY PURPOSES OR ISSUES THAT COULD NOT BE VERIFIED IN THE SUBMITTED DOCUMENTS.

8. **LRS 40:1731-(Effective 10/01/11)** Provide access for persons with disabilities in accordance with the ADA-ABA Accessibility Guidelines, July 23, 2004 (also known as the 2010 Standards). This does not include a review for compliance with the Federal Americans with Disabilities (Civil Rights) Act of 1990. NOTE: As per ADA-ABA 2004, Section F103, Office of State Fire Marshal appeal determinations are not valid for facilities that are designed, constructed, altered, or operated with federal funds, or leased by a federal agency. The authority having jurisdiction over such appeals is the administrator of the General Services Administration (GSA). Compliance with state regulations and requirements does not guarantee compliance with federal law.
9. **101:7.2.1.5 and IBC 1008.1.9** Locks on doors in means of egress shall not require the use of a key, special device or special knowledge to open in the direction of egress.

Submit a "REQUEST FOR EXEMPTION" for special locking arrangements in accordance with Interpretive Memorandum 2009-03 available on our website at <http://www.dps.louisiana.gov/sfm/> under the PLAN REVIEW / FORMS section. Also see Interpretive Memorandum 2009-04 for clarification regarding "Magnetic Lock Releasing Devices & Electrified Locks/Latches", or Interpretive Memorandum 2009-05 for clarification regarding Special Healthcare Locking Arrangements.

NOTE: The "Life Safety and Property Protection Licensing Law" (LRS 40:1664 et seq.) requires locksmiths to be licensed. Contact the licensing section of this office at 225.925.7047 for guidance and assistance.

10. 101:7.2.1.5.9 and IBC 1008.1.94 through 1008.1.9.5 Doors shall be openable with ONLY one releasing operation. A two-step release, such as a knob and an independent slide bolt, is NOT acceptable.
11. 101:36.2.8 and IBC 1006 Provide illumination of means of egress in accordance with 101:7.8 and IBC 1006.
12. 101:36.2.9 and IBC 1006.3 & 1006.4 Provide emergency lighting according to 101:7.9 and IBC 1006.
13. HVAC system shall be constructed in accordance with 101:9.2.
14. Compliance with the 2011 NFPA 70, National Electrical Code (NEC), is mandated by RS 40:1730.28.A(7). Contact the local Building Official of the applicable local political subdivision or a Louisiana State Uniform Construction Code Council registered third-party provider to verify plan review and inspection requirements of the proposed electrical work.
15. Compliance with the 2011 NFPA 70, National Electrical Code (NEC), is mandated by RS 40:1730.28.A(7). Contact the local Building Official of the applicable local political subdivision or a Louisiana State Uniform Construction Code Council registered third-party provider to verify plan review and inspection requirements of the proposed electrical work.
16. NOTE: Please ENCLOSE A COPY OF THIS LETTER WITH FUTURE SUBMITTALS OR OTHER CORRESPONDENCE pertaining to this project.

Changes to construction in the field which are not consistent with the reviewed documents are not authorized unless reviewed by this office for compliance with Code. Modifications to reviewed plans must be submitted to this office by the Architect/Civil Engineer for review prior to final inspection. If an Architect or Civil Engineer is not required by RS 37:155, revisions shall be submitted by the Owner. Submittals shall include plans, completed application, a minimum \$55.00 review fee, and a copy of the most current plan review letter.

Compliance with code requirements for fire protection systems, such as Fire Alarm, Sprinkler and Suppression Systems, is determined by separate shop drawing submittal and is not included in this review.

This review shall in no way permit and/or authorize any omissions or deviations from the specific requirements of the adopted codes, rules and regulations in accordance with R.S. 40:1574.1(B).

This review is valid for 180 days from the date of this letter. Construction permits must be issued and/or construction must commence within this time period.

This office requires certification of the completed project in accordance with the approved documents (certificate enclosed).

Occupancy of the project will not be permitted until we receive the completed certificate and a satisfactory inspection of the completed construction has been made by this office.

To arrange for inspection of the project, please contact the District Office at the phone number below two (2) to three (3) weeks in advance. The plans stamped reviewed by this office must be available on job site at time of inspection. Certificate of completion must be provided to the inspecting Deputy for final inspection.

Fire Department access and water supplies within the scope of work shall be acceptable to the local fire department. Submit to the State Fire Marshal inspector, a review letter from the local fire department, stating that the access and water supply as proposed are acceptable. In lieu of a review letter, where the local fire department does not provide a formal review, the local fire department may indicate review of the access and water supplies by stating such on the plans bearing the State Fire Marshal review stamp.

REVIEWED BY:
WILLIAM EFFERSON
ARCHITECT

NOTE: Please call the REVIEWER identified above if you have any questions regarding this review.
Do not call the Inspection Office until you are ready for inspection.

CC:
Fazad Aduli
Division Of Permits & Inspections (Stam)*
New Orleans District Ofc* 5045688506