


10	101:38.2.10 and IBC 1013 Exit signs complying with 101:7.10 and IBC 1013 shall define exits and access to exits where the exit is not immediately apparent. LIGHTING PLAN, SHEET E102: PROVIDE EXIT SIGNS AT FOLLOWING LOCATIONS: AT SOUTH END OF 114 DRESSING POINTING TOWARDS 1 CORRIDOR AT 100 LOBBY, WEST SIDE, POINTING TOWARDS STAIRWELL AT CORRIDOR 2 ABOVE DOOR 08
11	101:38.2.9 and IBC 1008 Provide emergency lighting according to 101:7.9 and IBC 1008.3, including exit discharge (exterior). LIGHTING PLAN, SHEET E102: PROVIDE EMERGENCY LIGHTING, WITH BATTERY PACK OR BATTERY CIRCUIT, AT EXTERIOR SIDE OF ALL EXTERIOR EXIT DOORS. RS 40:1574 and/or RS 40:1730.39.A Additional information and/or action is required:
12	1. FLOOR PLAN, SHEET A101: PROVIDE THE FOLLOWING UL LISTED INCINERATOR CLEARANCE DIMENSIONS: A. BETWEEN INCINERATOR AND NORTH WALL AT 123 RECEIVING / CREMATORY B. BETWEEN REAR OF INCINERATOR TO FACE OF EAST WALL AT 123 RECEIVING / CREMATORY (UL LISTING SHEET DENOTES 1'-6" BUT SHOP DRAWING PLAN VIEW DENOTES 2'-8") C. BETWEEN REAR OF CHIMNEY SECTION TO FACE OF EAST WALL AT 123 RECEIVING / CREMATORY D. PROVIDE ROOM SECTION DENOTING CLEARANCE FROM TOP OF INCINERATOR TO FINISH CEILING. 2. PLEASE PROVIDE CODE REFERENCE FOR 1-HOUR RATED SEPARATION AT NORTH EXTERIOR BUILDING WALL. 3. PLEASE PROVIDE CODE REFERENCE FOR 1-HOUR RATED SEPARATION AT 123 RECEIVING / CREMATORY.

Corrections to the deficiencies identified herein are required. The review will continue upon receipt of revised drawings, addendum, change orders, or other appropriate documentation that satisfactorily addresses corrections to the listed item(s). If this information is not received by this office within 21 days of the date of this notice, the status will be identified as "Resubmittal Required" whereby a resubmittal of the project along with the applicable review fee will be required. In accordance with L.R.S. 40:1574 et seq., CONSTRUCTION IS NOT AUTHORIZED until a satisfactory review by this office has been performed by this office. As such, permits shall not be issued until the Status of this review is identified as "Released"

<b>Review Completed By</b>	
Signature:	
Name:	Jean Carter
Badge No.:	189

Distribution List		
Name	Firm Name	Role
NEW ORLEANS CITY PERMITS		Permit Office