



- 1 EXISTING FOUNDATION/000 LEVEL DEMOLITION PLAN**
1/8"=1'-0"
- 2 DEMOLITION NOTES (FOUNDATION/ 000 LEVEL)**
- 1 - INDICATES OUTLINE OF BASEMENT, EXISTING BASEMENT TO CONSIST OF 12" CONC. SLAB THROUGHOUT.
 - 2 - INDICATES EXISTING 1 PILE CAP WITH TOP OF CAP AT EL. (-)5'-0".
 - 3 - INDICATES EXISTING CONSTRUCTION.
 - 4 - INDICATES DEMOLITION OF EXISTING FRAMING. DEMOLITION SHALL NOT PROCEED UNTIL ALL PERMANENT AND/OR TEMPORARY SHORING HAS BEEN INSTALLED. SEE STRUCTURAL DRAWINGS FOR PERMANENT SHORING. CONTRACTOR TO PROVIDE TEMPORARY SHORING AS REQUIRED TO FACILITATE THE DEMOLITION WORK. SEQUENCE OF DEMOLITION SHALL BE DETERMINED BY CONTRACTOR. SEE D1, D2, ETC. REFER ALSO TO SECTIONS AND DETAILS FOR MSC. DEMOLITION REQUIREMENTS NOT SHOWN ON THIS PLAN.
 - 5 - COORDINATE ALL OTHER DEMOLITION, SITE, UTILITY, INTERIOR, ETC., WITH RESPECTIVE DISCIPLINES.
 - 6 - S1, S2, ETC. INDICATES NEW PERMANENT SUPPORT FRAMING TO BE INSTALLED PRIOR TO DEMOLITION. SEE NEW CONSTRUCTION FRAMING PLANS SHEETS S2-0, S2-1, ETC.
- 3 SHORING NOTES (FOUNDATION/ 000 LEVEL)**
- S1 - INDICATES NEW 12" CONC. WALL TO BE INSTALLED PRIOR TO DEMOLITION OF EXISTING Waffle Slab ABOVE AT LEVEL 100. SEE ALSO DS2-1.

No.	Date	Issue	No.	Date	Issue
1	12.23.10	SD PRICING SET			
2	01.18.11	100% SD SET			
3	05.18.11	LNO Meeting			
4	09.15.11	100% DD/ PRICING			

MORPHY CONSULTING ENGINEERS
336 N. Jeff Davis Pkwy.
New Orleans, LA 70119
TEL: (504) 488-1317
FAX: (504) 488-9224
WEB: www.mmi-eng.com
INCORPORATED JOB NO. 10128

Holabird & Root / Holly & Smith LLC expressly disclaims any responsibility arising from any unauthorized use of these plans, drawings and notes. Any authorization must be in writing.
This drawing copy may have been reproduced at a size different than originally drawn. The Owner and Architect assume no responsibility for use of incorrect scale. Drawings are not to be scaled.
Not published - All rights reserved.

HOLABIRD & ROOT
140 South Dearborn Avenue
Suite 500
Chicago, IL 60660
312.357.1771 (tel)
312.357.1909 (fax)
www.holabird.com

HOLLY & SMITH LLC
541 Julia Street
Suite 201
New Orleans, LA 70130
504.585.1315 (tel)
504.585.1316 (fax)
www.hollyandsmith.com

Project Number	15248.00
Drawn	RAB
Checked	JAS
Proj. Arch./Eng.	JAS

LOYOLA UNIVERSITY NEW ORLEANS
Monroe Hall Renovation

EXISTING FOUNDATION/
000 LEVEL DEMOLITION
PLAN
Sheet Name
Drawing No. **DS2-0**

PRELIMINARY
NOT FOR CONSTRUCTION