



1 EXISTING 400 LEVEL
 DEMOLITION PLAN 1/8"=1'-0"

PLAN NOTES, UNLESS NOTED OTHERWISE:

- TOP OF EXISTING SLAB EL. 38'-0".
- EXISTING CONCRETE WAFLE JOIST FLOOR SYSTEM. (14" x 3" CONCRETE SLAB + 17" TOTAL THICKNESS).
- [E] - INDICATES EXISTING CONSTRUCTION.
- [X] - INDICATES DEMOLITION OF EXISTING FRAMING. DEMOLITION SHALL NOT PROCEED UNTIL ALL PERMANENT AND/OR TEMPORARY SHORING HAS BEEN INSTALLED. SEE STRUCTURAL DRAWINGS FOR PERMANENT SHORING. CONTRACTOR TO PROVIDE TEMPORARY SHORING AS REQUIRED TO FACILITATE THE DEMOLITION WORK. SEQUENCE OF DEMOLITION SHALL BE DETERMINED BY CONTRACTOR. SEE 01, 02, ETC., REFER ALSO TO SECTIONS AND DETAILS FOR MISC. DEMOLITION REQUIREMENTS NOT SHOWN ON THIS PLAN.
- SEE 3/052-6 AND 4/052-6 FOR EXISTING TOILET ROOM DEMOLITION PART PLANS.
- COORDINATE ALL OTHER DEMOLITION, SITE, UTILITY, INTERIOR, ETC., WITH RESPECTIVE DISCIPLINES.

2 DEMOLITION NOTES
 (400 LEVEL)

- 018 - INDICATES EXISTING 9" CONC. STAIR LANDING TO BE REMOVED.
- 019 - INDICATES EXISTING CONC. STAIR TO BE REMOVED.
- 020 - INDICATES REMOVAL OF EXISTING 12" CONC. WALLS TO BE REMOVED FROM TOP OF FLOOR TO TOP OF EXISTING DOOR OPENING (+) 8'-6" SECTION OF WALL BETWEEN TOP OF EXISTING OPENING & FLOOR ABOVE TO REMAIN.
- 021 - INDICATES REMOVAL OF EXISTING 12" CONC. WALL FOR NEW ELEVATOR DOOR OPENING.
- 022 - INDICATES EXISTING 16"x24" CONC. STAIR COLUMN TO BE REMOVED.
- 023 - INDICATES EXISTING CONC. STAIR TO BE REMOVED.
- 024 - INDICATES EXISTING CONC. FLOOR LANDING TO BE REMOVED.
- 025 - INDICATES EXISTING 12" U-SHAPED CONC. STAIR COLUMN TO BE REMOVED.
- 026 - INDICATES EXISTING 12" CONC. WALL TO BE REMOVED FROM TOP OF FLOOR TO UNDERSIDE OF FLOOR FRAMING ABOVE.
- 027 - INDICATES EXISTING 4" WIDE BY 9" HIGH CONC. CURB. TO BE REMOVED.

No.	Date	Issue	No.	Date	Issue
1	12.23.10	SD PRICING SET			
2	01.18.11	100% SD SET			
3	05.18.11	LNO Meeting			
4	09.15.11	100% DD/ PRICING			

MORPHY CONSULTING ENGINEERS
 336 N. Jeff Davis Pkwy.
 New Orleans, LA 70119
MAKOFSKY TEL: (504) 488-1317
 FAX: (504) 488-9924
 WEB: www.mmi-eng.com
INCORPORATED JOB NO. 10128

Holabird & Root / Holly & Smith LLC expressly disclaims any responsibility arising from any unauthorized use of these plans, drawings and notes. Any authorization must be in writing.
 This drawing copy may have been reproduced at a size different than originally drawn. The Owner and Architect assume no responsibility for use of incorrect scale. Drawings are not to be scaled.
 Not published - All rights reserved.

HOLABIRD & ROOT | **HOLLY & SMITH LLC**
 140 South Dearborn Avenue Suite 500 Chicago, IL 60660
 541 Julia Street Suite 201 New Orleans, LA 70130
 312.357.1771 (tel) 312.357.1909 (fax) www.holabird.com
 504.585.1315 (tel) 504.585.1316 (fax) www.hollyandsmith.com

Project Number	15248.00
Drawn	RAB
Checked	JAS
Proj. Arch./Eng.	JAS

LOYOLA UNIVERSITY NEW ORLEANS
Monroe Hall Renovation

EXISTING 400 LEVEL DEMOLITION PLAN
 Sheet Name
 Drawing No. **DS2-4**

PRELIMINARY
 NOT FOR CONSTRUCTION