



- PLAN NOTES: UNLESS NOTED OTHERWISE:
1. TOP OF EXISTING SLAB EL. 48'-0".
  2. EXISTING CONCRETE WAFFLE DECK FLOOR SYSTEM (14" x 3" CONCRETE SLAB = 17" TOTAL THICKNESS).
  3. (E) - INDICATES EXISTING CONSTRUCTION.
  4. (X) - INDICATES DEMOLITION OF EXISTING FRAMING. DEMOLITION SHALL NOT PROCEED UNTIL ALL PERMANENT AND/OR TEMPORARY SHORING HAS BEEN INSTALLED. SEE STRUCTURAL DRAWINGS FOR PERMANENT SHORING. CONTRACTOR TO PROVIDE TEMPORARY SHORING AS REQUIRED TO FACILITATE THE DEMOLITION WORK. SEQUENCE OF DEMOLITION SHALL BE DETERMINED BY CONTRACTOR. SET 01, 02, ETC., REFER ALSO TO SECTIONS AND DETAILS FOR MISC. DEMOLITION REQUIREMENTS NOT SHOWN ON THIS PLAN.
  5. SEE 3/DS2-6 AND 4/DS2-6 FOR EXISTING TOILET ROOM DEMOLITION PART PLANS.
  6. COORDINATE ALL OTHER DEMOLITION, SITE, UTILITY, INTERIOR, ETC., WITH RESPECTIVE DISCIPLINES.

**1** EXISTING 500 LEVEL DEMOLITION PLAN 1/8"=1'-0"

**2** DEMOLITION NOTES (500 LEVEL)

- (012) - INDICATES EXISTING 9" x 9" CONC. STAR LANDING TO BE REMOVED.
- (013) - INDICATES EXISTING CONC. STAR TO BE REMOVED.
- (014) - INDICATES REMOVAL OF EXISTING 12" x 12" CONC. WALLS TO BE REMOVED FROM TOP OF FLOOR TO TOP OF EXISTING DOOR OPENING (1' 6"-46"). SECTION OF WALL BETWEEN TOP OF EXISTING OPENING & FLOOR ABOVE TO REMAIN.
- (015) - INDICATES REMOVAL OF EXISTING 12" x 12" CONC. WALL FOR NEW ELEVATOR DOOR OPENING.
- (016) - INDICATES EXISTING 16"x24" CONC. STAR COLUMN TO BE REMOVED.
- (018) - INDICATES EXISTING CONC. STAR TO BE REMOVED.
- (020) - INDICATES EXISTING CONC. FLOOR LANDING TO BE REMOVED.
- (021) - INDICATES EXISTING 12" x U-SHAPED CONC. STAR COLUMN TO BE REMOVED.
- (022) - INDICATES EXISTING 12" x CONC. WALL TO BE REMOVED FROM TOP OF FLOOR TO UNDERSIDE OF FLOOR FRAMING ABOVE.
- (023) - INDICATES EXISTING 4" x WIDE BY 9" x HIGH CONC. CURB. TO BE REMOVED.
- (025) - INDICATES EXISTING CONC. WAFFLE SLAB EYEBROW TO BE REMOVED.

1	12.23.10	SD PRICING SET			
2	01.18.11	100% SD SET			
3	05.18.11	LNO Meeting			
4	09.15.11	100% DD/ PRICING			
No.	Date	Issue	No.	Date	Issue

**MORPHY**  
**MAKOFSKY**  
**INCORPORATED** JOB NO. 10128

336 N. Jeff Davis Pkwy.  
 New Orleans, LA 70115  
 TEL: (504) 488-1317  
 FAX: (504) 488-8924  
 WEB: www.mmi-eng.com

Holabird & Root / Holly & Smith LLC expressly disclaims any responsibility arising from any unauthorized use of these plans, drawings and notes. Any authorization must be in writing.  
 This drawing copy may have been reproduced at a size different than originally drawn. The Owner and Architect assume no responsibility for use of incorrect scale. Drawings are not to be scaled.  
 Not published - All rights reserved.

**HOLABIRD & ROOT** | **HOLLY & SMITH LLC**

140 South Dearborn Avenue Suite 500 Chicago, IL 60660  
 312.357.1771 (tel) 312.357.1909 (fax) www.holabird.com

541 Julia Street Suite 201 New Orleans, LA 70130  
 504.585.1315 (tel) 504.585.1316 (fax) www.hollyandsmith.com

Project Number	15248.00
Drawn	RAB
Checked	JAS
Proj. Arch./Eng.	JAS

**LOYOLA UNIVERSITY**  
**NEW ORLEANS**  
**Monroe Hall**  
**Renovation**

EXISTING 500 LEVEL DEMOLITION PLAN  
 Sheet Name  
 Drawing No. **DS2-5**

**PRELIMINARY**  
 NOT FOR CONSTRUCTION