



- PLAN NOTES - UNLESS NOTED OTHERWISE**
- TOP OF SLAB EL. 13'-0".
 - EXISTING CONCRETE WAFFLE JOIST FLOOR SYSTEM. (14"x3" CONCRETE SLAB=17" TOTAL THICKNESS).
 - (E) - INDICATES EXISTING CONSTRUCTION.
 - (N) - INDICATES NEW CONSTRUCTION.
 - INDICATES FLOOR SYSTEM TO CONSIST OF LIGHT WEIGHT CONCRETE (115PCF, f'c=4,000 psi) ON 18" DEEP 20 GAGE GALVANIZED COMPOSITE METAL DECKING. TOTAL THICKNESS=6".
 - INDICATES NEW IN-FILL SLAB TO CONSIST OF 3" THICK CONCRETE SLAB THROUGHOUT (f'c=4,000PSI, NORMAL WEIGHT). TOP OF SLAB EL. TO MATCH EXIST. COORD. WITH EXIST. FINISHES.
 - INDICATES NEW SLAB EXTENSION TO CONSIST OF 6" THICK CONCRETE SLAB THROUGHOUT (f'c=4,000PSI, NORMAL WEIGHT). TOP OF SLAB EL. TO MATCH EXIST. COORD. WITH EXIST. FINISHES.
 - INDICATES FLOOR SYSTEM TO CONSIST OF LIGHT WEIGHT CONCRETE (115PCF, f'c=4,000 psi) ON 18" DEEP 20 GAGE GALVANIZED COMPOSITE METAL DECKING. TOTAL THICKNESS=6".
 - INDICATES FLOOR SYSTEM TO CONSIST OF LIGHT WEIGHT CONCRETE (115PCF, f'c=4,000 psi) ON 18" DEEP 20 GAGE GALVANIZED COMPOSITE METAL DECKING. TOTAL THICKNESS=6".
 - INDICATES NEW EPOXY TOPPING SLAB AT EXISTING DEPRESSION.
 - INDICATES DIRECTION OF SPAN OF STEEL DECKING.
 - INDICATES X-BRACING. SEE 2/S2-7.
 - INDICATES K-BRACING. SEE 3/S2-7.
 - INDICATES 8" OR 12" CMU WALLS. SEE -/- REINFORCING.

1 200 LEVEL FRAMING PLAN
1/8"=1'-0"

PRELIMINARY
NOT FOR CONSTRUCTION

No.	Date	Issue	No.	Date	Issue
1	12.23.10	SD PRICING SET			
2	01.18.11	100% SD SET			
3	05.18.11	LNO Meeting			
4	09.15.11	100% DD/ PRICING			

MORPHY CONSULTING ENGINEERS
336 N. Jeff Davis Pkwy.
New Orleans, LA 70119
TEL: (504) 488-1317
FAX: (504) 488-8924
WEB: www.mmi-eng.com
INCORPORATED JOB NO. 10128

Holabird & Root / Holly & Smith LLC expressly disclaims any responsibility arising from any unauthorized use of these plans, drawings and notes. Any authorization must be in writing.
This drawing copy may have been reproduced at a size different than originally drawn. The Owner and Architect assume no responsibility for use of incorrect scale. Drawings are not to be scaled.
Not published - All rights reserved.

HOLABIRD & ROOT | **HOLLY & SMITH LLC**
140 South Dearborn Avenue, Suite 500, Chicago, IL 60660
541 Julia Street, Suite 201, New Orleans, LA 70130
312.357.1771 (tel), 312.357.1909 (fax)
504.585.1315 (tel), 504.585.1316 (fax)
www.holabird.com | www.hollyandsmith.com

Project Number	15248.00
Drawn	RAB
Checked	JAS
Proj. Arch./Eng.	JAS

LOYOLA UNIVERSITY NEW ORLEANS
Monroe Hall Renovation

200 LEVEL FRAMING PLAN
Sheet Name
Drawing No. S2-2