

Tammany Utilities

March 31, 2011

Re: North 7th St.

To Whom It May Concern:

Please Note: This is an estimate for the water and sewer line extensions only. The number of services will need to be determined at a later date. Water and sewer capacity will be based on number of connections as well.

***Additional Costs:**

Water Capacity

Sewer Capacity

Line Extension Drawings

Fusing Machine

Trackhoe

Surveys

The following costs are associated with the installation of water and sewer along North 7th St., Pearl River, LA.

6" Water Line:

<u>Materials:</u>	\$89,461.00
1,400 ft 6" HDPE, 1,400ft 6" Bore, 3- hydrants with check valves, 9-MJxMJ gate valves w/ access., 3- 6" MJxMJxMJ tees w/ access., 4x4" tapping sleeve, 4" MJxFlange valve w/ access., valve housing, 6"x4" MJxMJ reducer, 70ft 6" SDR 35 pipe, 7-6" megalugs, 6"trans gaskets	
<u>Equipment:</u>	\$1,650.00
Trackhoe x 5 days= \$900	
Fusing Machine x 5 days= \$750	
<u>Labor:</u>	\$18,000.00
3 Weeks	
Water Capacity, Equipment, Surveys, Drawings:	To Be Determined
Water Line:	\$109,111.00* +

Tammany Utilities

Please note: Crossgates currently has a manhole at the corner of Haas Road and North 7th St. The additional flow from this area will need to pump into the pressurized system.

*Any tie-ins will be required to have a lift station.

4”Sewer Force Main:

<u>Materials:</u>	\$42,000.00
1,400 ft 4” HDPE, 1,400 ft 4” Bore	
<u>Lift Station:</u>	\$25,000.00
Lift Station: \$25,000.00	
<u>Labor:</u>	\$18,000.00
3 Weeks	
<u>Sewer Capacity, Equipment, Surveys, Drawings:</u>	To Be Determined
Sewer Line:	\$85,000.00* +

Yours Truly,

Melanie Verdin

Field Compliance Coordinator

St. Tammany Parish Government – Tammany Utilities