



Mighty-Mate 50 Series

Submersible pump for dewatering (sump) or effluent (septic tank systems).

-
- Float-operated, submersible, 2-pole mechanical switch and variable level, long-cycle systems available
- Corrosion-resistant, powder-coated epoxy finish
- No sheet metal parts to rust or corrode
- Stainless steel screws, switch arm, guard and handle
- No screens to clog
- Watertight, neoprene square ring between motor and pump housing
- Solid, buoyant, polypropylene float
- Oil-filled, hermetically-sealed, automatic reset thermal overload protected motor
- Upper and lower sleeve bearings running in bath of oil
- Entire unit pressure-tested after assembly
- Carbon and ceramic shaft seal
- Maximum temperature for effluent or dewatering: 130° F (54° C)
- Passes ½" (13 mm) spherical solids
- 1½" NPT discharge
- On point: 7¼" (18 cm)
- Off point: 3" (8 cm)
- Major width: 10-3/32" (26.2 cm)
- Major height: 10-1/16" (25.6 cm)
- Watertight and dust-tight
- Permanently oiled bearings