

**Sec. 7-107. Minimum requirements for housing animals for continuous periods of thirty days or longer.** The following are minimum requirements for housing animals for continuous periods of thirty (30) days or longer:

TABLE INSET:

Species	Or Age	Minimum Cage Dimensions (inches)		Height	Minimum Cage or Run Floor Area per Animal (square feet)		Maximum Number of Animals Per Cage or Run (2)
		Width	Depth		Singles	Group	
Adult dogs	0--35 lb.	30	30	30	8	6	4
in cages	35--65 lb.	36 (1)	36 (1)	36 (1)	12	10	3
	Over 65-lb.	36 (1)	36 (1)	36 (1)	12	10	2
Puppies in cages	0--15 lb.	30	30	24	6	2	8
Adult cats in cages	Any	24	24	24	4	3	4
Kittens in cages	Up to 4 months	24	24	24	4	2	6
Rabbits in cages	Any	24	24	24	4	3	6
Guinea pigs and hamsters in cages	Any	12	12	12	1	1	6
Adult dogs in runs (2)	Any	48	72	--	24	12	4

(1) These dimensions may require modification to conform to the body sizes of certain breeds. In no case should the cage height be less than six (6) inches plus the height of the dog at the withers, nor should the width or depth be less than six (6) inches plus the length of the dog from the tip of the nose to the base of the tail.

(2) Where outdoor runs are provided for the housing of dogs or other animals, each run shall have a covered portion for protection against sunlight and rain. This covered portion shall have a raised floor area per animal at least equal to the minimum cage floor area as provided for in this table for the particular size of animal.

(Code 1961, § 4-15(Table A))

**Sec. 7-108. Minimum requirements for housing animals for periods from twenty-four hours up to thirty days.** The following are minimum requirements for housing animals for periods from twenty-four (24) hours up to thirty (30) days:

TABLE INSET:

Species	Weight	Width	Minimum Cage Dimensions (inches)		Minimum Cage or Run Floor Area per Animal (square feet)		Maximum Number of Animals Per Cage or Run (2)
	Or Age		Depth	Height	Singles	Group	
Adult dogs	0--35 lb.	20	30	24	5	4	4
in cages	35--50 lb.	30 (1)	30 (1)	30 (1)	7	6	3
	Over 65 lb.	30 (1)	36 (1)	36 (1)	10	8	2
Puppies in cages	0--15 lb.	20	20	24	3	2	8
Adult cats in cages	Any	20	20	24	3	2 1/2	4
Kittens in cages	Up to 4 months	20	20	24	2	1 1/2	6
Rabbits in cages	Any	20	20	24	3	2 1/2	6
Guinea pigs and hamsters in cages	Any	12	12	12	1	1	6
Adult dogs in runs (2)	Any	36	72	--	15	8	4

(1) These dimensions may require modification to conform to the body sizes of certain breeds. In no case should the cage height be less than six (6) inches plus the height of the dog at the withers, nor should the width or depth be less than six (6) inches plus the length of the dog from the tip of the nose to the base of the tail.

(2) Where outdoor runs are provided for the housing of dogs or other animals, each run shall have a covered portion for protection against sunlight and rain. This covered portion shall have a raised floor area per animal at least equal to the minimum cage floor area as provided for in this table for the particular size of animal.

(Code 1961, § 4.15(Table B))

**Sec. 7-109. Minimum requirements for housing animals for periods up to twenty-four hours.** The following are minimum requirements for housing animals for periods up to twenty-four (24) hours:

TABLE INSET:

	Weight	Minimum Cage Dimensions (inches)			Minimum Cage or Run Floor Area per Animal (square feet)		Maximum Number of Animals Per
		Width	Depth	Height	Singles	Group	
Species	Or Age						Cage or Run (2)
Adult dogs	0--35 lb.	30	30	30	8	6	4
in cages	35--65 lb.	36 (1)	36 (1)	36 (1)	12	10	3
	Over 65-lb.	36 (1)	36 (1)	36 (1)	12	10	2
Puppies in cages	0--15 lb.	30	30	24	6	2	8
Adult cats in cages	Any	24	24	24	4	3	4
Kittens in cages	Up to 4 months	24	24	24	4	2	6
Rabbits in cages	Any	24	24	24	4	3	6
Guinea pigs and hamsters in cages	Any	12	12	12	1	1	6
Adult dogs in runs (2)	Any	48	72	--	24	12	4

(1) These dimensions may require modification to conform to the body sizes of certain breeds. In no case should the cage height be less than six (6) inches plus the height of the dog at the withers, nor should the width or depth be less than six (6) inches plus the length of the dog from the tip of the nose to the base of the tail.

(2) Where outdoor runs are provided for the housing of dogs or other animals, each run shall have a covered portion for protection against sunlight and rain. This covered portion shall have a raised floor area per animal at least equal to the minimum cage floor area as provided for in this table for the particular size of animal.

(Code 1961 § 4.15(Table C))