DOOR SCHEDULE

DOOR NO.	LOCATION				DOOR								FRAME						SOUND RATING	LABEL (MIN.)	HW SET	FLOOD BARRIER / WATER TIGHT	REMARKS
	TO		FROM		NEW / EXIST.	DIMENSION			NO. OF LEAVES	TYPE	MATERIAL	FINISH	MATERIAL	TYPE	DETAILS								
	NAME	NO.	NAME	NO.		W	H	THK							HEAD	JAMB	SILL	ASTRAGAL					
00 BASEMENT LEVEL																							
001A	PATIO LOBBY	001			NEW	3'-0"	6'-8"	0'-1 3/4"	1	F6	HM	DEC. PTD.	HM	FR1	HD15	JB15	SL14	------	------	90 MIN.	17	------	
003A	LADIES' ROOM	003	LADIES' LOUNGE	002	NEW	3'-0"	7'-4"	0'-1 3/4"	1	B1	WD	STN.	WD	FR2	HD4	JB4	SL15	------	------	------	69	------	REPLICATE DOOR AND TRIM TO MATCH DOOR 006A
004A	LADIES' ROOM	003	JANITOR	004	NEW	2'-8"	7'-4"	0'-1 3/4"	1	C1	WD	STN.	WD	FR3	HD4	JB4	SL16	------	------	------	75	------	REPLICATE DOOR AND TRIM TO MATCH DOOR 007A
006A	MEN'S ROOM	006	MEN'S LOUNGE	005	NEW	3'-0"	7'-4"	0'-1 3/4"	1	B1	WD	STN.	WD	FR2	HD4	JB4	SL15	------	------	------	69	------	REPLICATE DOOR AND TRIM FROM SALVAGED EXISTING DOOR
007A	MEN'S ROOM	006	JANITOR	007	NEW	2'-8"	7'-4"	0'-1 3/4"	1	C1	WD	STN.	WD	FR3	HD4	JB4	SL16	------	------	------	75	------	REPLICATE DOOR AND TRIM FROM SALVAGED EXISTING DOOR
008A	CORRIDOR	022	CORRIDOR	008	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL1	------	------	45 MIN	16	------	
009A	USHERS & FOH STAFF	009	CORRIDOR	008	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL5	------	------	45 MIN	41	------	
011A	SERVER ROOM	011	CORRIDOR	022	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL1	------	------	------	28	------	
012A	CONCESS. MGR	012	CORRIDOR	022	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL5	------	------	------	40	------	
013A	CORRIDOR	022	CONCESSION STORAGE	013	NEW	6'-0"	7'-0"	0'-1 3/4"	2	A2	HM	PTD.	HM	FR1	HD2	JB2	SL11	------	------	------	31	------	
014A	LINEN STORAGE	014	CONCESSION STORAGE	013	NEW	6'-0"	7'-0"	0'-1 3/4"	2	A2	HM	PTD.	HM	FR1	HD2	JB2	SL1	------	------	------	32	------	
015A	CONCESSION STORAGE	013	STORAGE	015	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL1	------	------	------		------	
017A	STORAGE	017	CORRIDOR	022	NEW	6'-0"	7'-0"	0'-1 3/4"	2	A2	HM	PTD.	HM	FR1	HD2	JB2	SL1	------	------	------	32	------	
018A	CORRIDOR	022	STAIR 11	18.1	NEW	7'-0"	7'-0"	0'-1 3/4"	2	A10	HM	PTD.	HM	FR1	HD2	JB2	SL9	------	STC 49	------			
019A	JANITORIAL STORAGE	019	MAINT. SHOP	018	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL1	------	------	------	28	------	
020A	TOOL ROOM	020	MAINT. SHOP	018	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL1	------	------	------	28	------	
021A	SUMP PUMP	021	CORRIDOR	022	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD10	JB10	SL9	------	STC 49	------	34	------	
023A	CREW RM.	023	CORRIDOR	022	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL5	------	------	------	40	------	
024A	TECH. DIRECTOR / ASST.	024	CORRIDOR	022	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL5	------	------	------	40	------	
025A	DIRECTOR OF OPERATIONS	025	CORRIDOR	022	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL5	------	------	------	40	------	
026A	VISIT PROD. OFFICE.	026	CORRIDOR	022	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL5	------	------	------	40	------	
027A	WOMEN'S TOILET	027	CORRIDOR	022	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL12	------	------	------	65	------	
028A	MEN'S TOILET	028	CORRIDOR	022	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL12	------	------	------	65	------	
029A	TRASH	029	CORRIDOR	022	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL1	------	------	45 MIN	35	------	
030A	CORRIDOR	022			NEW	4'-0"	7'-0"	0'-1 3/4"	1	A6	HM	PTD.	HM	FR1	HD2	JB2	SL1	------	------	------	72	WT-2	
033A	ORGAN BLOWER	033	CORRIDOR	031	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD10	JB10	SL9	------	STC 49	------	34	------	
034A	JANITOR	034	CORRIDOR	035	NEW	2'-6"	7'-0"	0'-1 3/4"	1	A3	WD	PTD.	HM	FR1	HD2	JB2	SL1	------	------	45 MIN	33	------	
036A	STAIR 7	036	CORRIDOR	037	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD6	JB6	SL9	------	GASK-1	90 MIN.	15	------	
037A	CORRIDOR	037	CORRIDOR	031	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD15	JB15	SL1	------	------	90 MIN.	16	------	
038A	CORRIDOR	037	LAUNDRY	038	NEW	3'-6"	7'-0"	0'-1 3/4"	1	A8	HM	PTD.	HM	FR1	HD6	JB6	SL9	------	GASK-1	45 MIN	60	------	
040A	STAGE MGR.	040	CORRIDOR	043	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL5	------	------	45 MIN	41	------	
041A	STAR DRESSING ROOM 'A'	041	CORRIDOR	043	NEW	3'-6"	7'-0"	0'-1 3/4"	1	A8	HM	PTD.	HM	FR1	HD11	JB11	SL7	------	GASK-1	45 MIN	60	------	
042A	STAR DRESSING ROOM 'A'	041	TOILET	042	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD1	JB1	SL2	------	------	------	61	------	
045A	STAR DRESSING ROOM 'B'	045	CORRIDOR	043	NEW	3'-6"	7'-0"	0'-1 3/4"	1	A8	HM	PTD.	HM	FR1	HD11	JB11	SL7	------	GASK-1	45 MIN	60	------	
046A	TOILET	046	STAR DRESSING ROOM 'B'	045	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD1	JB1	SL2	------	------	------	61	------	
047A	RECEIVING	044	MULTIPURPOSE ROOM	047	NEW	7'-0"	8'-0"	0'-1 3/4"	2	A7	HM	PTD.	HM	FR1	HD6	JB6	SL9	------	GASK-1	90 MIN.	50	------	PROVIDE 180 DEGREE SWING
047B	CORRIDOR	043	MULTIPURPOSE ROOM	047	NEW	7'-0"	8'-0"	0'-1 3/4"	2	A7	HM	PTD.	HM	FR1	HD6	JB6	SL9	------	GASK-1	90 MIN.	50	------	PROVIDE 180 DEGREE SWING
047C	CORRIDOR	043	MULTIPURPOSE ROOM	047	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD6	JB6	SL5	------	GASK-1	90 MIN.	60	------	
048A	CORRIDOR	035			NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD12	JB12	SL9	------	STC 49	90 MIN.	13	------	
048B	MULTIPURPOSE ROOM	047	ORCHESTRA PIT	048	NEW	7'-0"	8'-0"	0'-1 3/4"	2	A7	HM	PTD.	HM	FR1	HD13	JB13	SL9	------	STC 49	90 MIN.	51	------	PROVIDE 180 DEGREE SWING
048C	STAIR 25	059			NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD12	JB12	SL9	------	STC 49	90 MIN.	18	------	
050A	CHORUS DRESSING ROOM 'B'	050	CORRIDOR	043	NEW	3'-6"	7'-0"	0'-1 3/4"	1	A8	WD	PTD.	HM	FR1	HD11	JB11	SL5	------	GASK-1	45 MIN	60	------	
051A	SEWAGE EJECTOR / SUMP	051	CORRIDOR	043	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD10	JB10	SL9	------	STC 49	45 MIN	34	------	
052A	TOILET	052	CORRIDOR	055	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL12	------	------	45 MIN	63	------	
053A	PRINCIPAL DRESSING ROOM	053	CORRIDOR	043	NEW	3'-6"	7'-0"	0'-1 3/4"	1	A8	HM	PTD.	HM	FR1	HD11	JB11	SL5	------	GASK-1	45 MIN	60	------	
056A	CHORUS DRESSING ROOM "A"	056	CORRIDOR	043	NEW	3'-6"	7'-0"	0'-1 3/4"	1	A8	HM	PTD.	HM	FR1	HD11	JB11	SL5	------	GASK-1	45 MIN	60	------	
058A	COMP. MGR / ASST. MGR.	058	CORRIDOR	055	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD2	JB2	SL5	------	------	45 MIN	41	------	
060A	STAIR 25	059	STAIR 6	060	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD6	JB6	SL9	------	GASK-1	90 MIN.	19	------	
060B	STAIR 6	060	CORRIDOR	010	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD6	JB6	SL9	------	GASK-1	90 MIN.	19	------	
01 ORCHESTRA LEVEL																							
100A			CANAL STREET ARCADE	100	NEW	6'-0"	7'-0"	0'-1 3/4"	2	M1	MTL. CLAD	BRONZE	MTL. CLAD	A-5.17	A-5.17	A-5.17	A-5.17		------		3		
100B			CANAL STREET ARCADE	100	NEW	6'-0"	7'-0"	0'-1 3/4"	2	M1	MTL. CLAD	BRONZE	MTL. CLAD	A-5.17	A-5.17	A-5.17	A-5.17		------		3		
101A			CROSS ARCADE	101	NEW	6'-0"	7'-0"	0'-1 3/4"	2	M1	MTL. CLAD	PTD.	MTL. CLAD	A-5.17	A-5.17	A-5.17	A-5.17		------		3		
101B			CROSS ARCADE	101	NEW	6'-0"	7'-0"	0'-1 3/4"	2	M1	MTL. CLAD	PTD.	MTL. CLAD	A-5.17	A-5.17	A-5.17	A-5.17		------		3		
101C	CROSS ARCADE	101			NEW	6'-0"	7'-1 3/8"	0'-1 3/4"	2	M1	MTL. CLAD	PTD.	MTL. CLAD	A-5.17	A-5.17	A-5.17	A-5.17		------		5		
101D	CROSS ARCADE	101			NEW	6'-0"	7'-1 3/8"	0'-1 3/4"	2	M1	MTL. CLAD	PTD.	MTL. CLAD	A-5.17	A-5.17	A-5.17	A-5.17		------		4		
103A	ELEV. LOBBY	102	COMPANION TOILET	103	NEW	3'-0"	7'-0"	0'-1 3/4"	1	F1	WD	PTD.	WD	FR5	HD7	JB7	SL1	------	------	------	64	------	
104A	CONCESSION	105	JAN. CL.	104	NEW	2'-6"	7'-0"	0'-1 3/4"	1	F2	WD	PTD.	WD	FR5	HD7	JB7	SL1	------	------	------	36	------	
105A	CONCESSION	105	ELEV. LOBBY	102	NEW	3'-0"	7'-0"	0'-1 3/4"	1	F1	WD	PTD.	WD	FR5	HD7	JB7	SL13	------	------	------	43	------	
106A	WOMEN'S ROOM	106	ELEV. LOBBY	102	NEW	3'-0"	7'-0"	0'-1 3/4"	1	F1	WD	PTD.	WD	FR5	HD7	JB7	SL13	------	------	------	70	------	
107A	MEN'S ROOM	107	ELEV. LOBBY	102	NEW	3'-0"	7'-0"	0'-1 3/4"	1	F1	WD	PTD.	WD	FR5	HD7	JB7	SL13	------	------	------	70	------	
108A	H.C. ENTRY	108			NEW	3'-0"	7'-0"	0'-1 3/4"	1	M4	MTL. CLAD	PTD.	MTL. CLAD	A-5.17	A-5.17	A-5.17	SL11	------	------	------	1	------	
109A			TRANSFORMER VAULT	109	NEW	14'-1"	11'-2"	0'-4"	2 (@ 3'-0")	CUSTOM	HM	PTD.	HM	5/A-4.20	5/A-4.20	3/A-4.19	5/A-4.20	------	------	------	MFR.	------	HARDWARE BY MANUFACTURER
109B			TRANSFORMER VAULT	109	NEW	14'-1"	11'-2"	0'-4"	2 (@ 3'-0")	CUSTOM	HM	PTD.	HM	5/A-4.20	5/A-4.20	3/A-4.19	5/A-4.20	------	------	------	MFR.	------	HARDWARE BY MANUFACTURER
110A			STAIR 23	110	NEW	3'-0"	8'-10"	0'-1 3/4"	1	A-4.16	ALUM.	PTD.	ALUM.	A-4.17	A-4.17	A-4.17	A-4.17	------	------	------	73	------	
110B	STAIR 23	110	GREASE RECEPTOR	110A	NEW	3'-0"	7'-0"	0'-1 3/4"	1	A1	HM	PTD.	HM	FR1	HD1	JB1	SL9	------	------	90 MIN.	35	------	
111A	CANAL STREET ARCADE	100	TENANT SPACE		NEW	3'-0"	7'-0"	0'-1 3/4"	2	M4	WD	PTD.	WD	FR5	HD7	JB7	SL7	------	------	------	42	------	
112A	CANAL STREET ARCADE	100	CANAL STREET ARCADE	100	NEW	3'-0"	7'-0"	0'-1 3/4"	1	F1	WD	PTD.	WD	FR5	HD7	JB7	SL2	------	------	------	43	------	
113A	STORAGE	113	CANAL STREET ARCADE	100	NEW	3'-0"	7'-0"	0'-1 3/4"	1	F1	WD	PTD.	WD	FR5	HD4	JB4	SL3	------	------	------	37	------	
114A	STAIR 24	114			NEW	3'-0"	9'-1"	0'-1 3/4"	1	A-4.16	ALUM.	PTD.	ALUM.	A-4.16	A-4.16	A-4.16	SL7	------	------	------	73	------	
114B	TENANT SPACE				NEW	6'-0"	9'-1 7/8"	0'-1 3/4"	2	A-4.16	ALUM.	PTD.	ALUM.	A-4.16	A-4.16	A-4.16	SL7	------	------	------	73	------	
115A	LOBBY	116	INFO. BOOTH	115	EXIST.	3'-0"	7'-0"	0'-1 3/4"	1	F1	WD	PTD.	WD	EXIST.	HD4	JB4	SL2	------	------	------	44	------	
116A			LOBBY	116	NEW	5'-2"	7'-1"	0'-1 3/4"	2	M2	MTL. CLAD	PTD.	MTL. CLAD	A-5.17	A-5.17	A-5.17	SL6	------	GASK-1	------	14	------	PROVIDE DOOR DRAPERY, SEE 6/A-5.47
116B	CROSS ARCADE	101	LOBBY	116	EXIST.	6'-0"	7'-1"	0'-1 3/4"	2	E1	WD	PTD.	WD	FR4	HD5	JB5	SL6	------	GASK-1	------	20	------	
116C	CROSS ARCADE	101	LOBBY	116	EXIST.	6'-0"	7'-1"	0'-1 3/4"	2	E1	WD	PTD.	WD	FR4	HD5	JB5	SL6	------	GASK-1	------	20	------	
116D	CROSS ARCADE	101	LOBBY	116	EXIST.	6'-0"	7'-1"	0'-1 3/4"	2	E1	WD	PTD.	WD	FR4	HD5	JB5	SL6	------	GASK-1	------	21	------	
116E			LOBBY	116	NEW	5'-2"	7'-1"	0'-1 3/4"	2	M2	MTL. CLAD	PTD.	MTL. CLAD	A-5.17	A-5.17	A-5.17	SL6	------	GASK-1	------	14	FB-1	PROVIDE DOOR DRAPERY, SEE 6/A-5.47
117A			HOUSE RIGHT AISLE	117	NEW	5'-0"	8'-0"	0'-1 3/4"	2	G1	HM	PTD.	HM	FR1	HD14	JB16	SL20	AS-1	STC 51	------	8	WT-1, FB-1	
117B			HOUSE RIGHT AISLE	117	NEW	5'-0"	8'-0"	0'-1 3/4"	2	G1	HM	PTD.	HM	FR1	HD14	JB16	SL20	AS-1	STC 51	------	8	WT-1, FB-1	
118A	LOBBY	116	HOUSE RIGHT AISLE	117	EXIST.	5'-0"	7'-0"	0'-1 3/4"	2	H1	WD	PTD.	WD	EXIST.	HD5	JB5	SL4	------	GASK-1	------	68	------	REMOVE PLASTIC GLAZING, REPLACE W/ BEVELED GLASS; PROVIDE DOOR DRAPERY - SEE 6/A-5.47
118B	LOBBY	116	ORCHESTRA SEATING	118	EXIST.	5'-0"	7'-0"	0'-1 3/4"	2	H1	WD	PTD.	WD	EXIST.	HD5	JB5	SL4	------	GASK-1	------	68	------	REMOVE PLASTIC GLAZING, REPLACE W/ BEVELED GLASS; PROVIDE DOOR DRAPERY - SEE 6/A-5.47
118C	LOBBY	116	ORCHESTRA SEATING	118	EXIST.	5'-0"	7'-0"	0'-1 3/4"	2	H1	WD	PTD.	WD	EXIST.	HD5	JB5	SL4	------	GASK-1	------	68	------	REMOVE PLASTIC GLAZING, REPLACE W/ BEVELED GLASS; PROVIDE DOOR DRAPERY - SEE 6/A-5.47

DOOR GENERAL NOTES

1. ALL EXISTING DOOR DIMENSIONS ARE APPROXIMATE. VERIFY ACTUAL DOOR SIZES IN FIELD.
2. ALL EXISTING OPENINGS TO RECEIVE NEW DOORS ARE APPROXIMATE. VERIFY ACTUAL DOOR SIZES IN FIELD.
3. GASK-1 = ACOUSTICAL GASKETED DOOR WITH 5 LBS/SF SURFACE WEIGHT AND FULLY ADJUSTABLE NEOPRENE GASKETS WITH NEOPRENE BULB SEALS.
4. WT-1 = ACOUSTICAL WATERTIGHT DOOR. (SEE PROJECT MANUAL)
5. WT-2 = NON-ACOUSTICAL WATERTIGHT DOOR. (SEE PROJECT MANUAL)
6. DOOR NUMBERS SHOWN ON THE PLANS THAT BEGIN WITH THE LETTER "G" ARE WROUGHT IRON GATES AND ARE SHOWN ON THE INTERIOR GATE SCHEDULE ON SHEET A-5.30.
7. ALL DOORS TO RECEIVE CUSTOM APPLIED MOLDING, MUST BE COORDINATED WITH LOCATION OF PANIC HARDWARE. REVIEW WITH ARCHITECT PRIOR TO PRODUCTION.
8. ALL NEW FRAMES WITHIN EXISTING OPENINGS ARE TO MATCH THE EXISTING FRAME WIDTH.

THE SAENGER THEATRE RENEWAL PROJECT

142 North Rampart Street
New Orleans, LA

Client
Saenger Theatre Redevelopment Company
1800 Post Oak Boulevard, 6 Boulevard Place, Suite 450, Houston, TX 77056

Architect
MARTINEZ+JOHNSON ARCHITECTURE
1412 Eye St., NW
Washington, DC 20005
202.333.4480

Structural Engineer
Lundy & Franke Engineering, Inc.
549 Heimer Road, San Antonio, TX 78232
210.979.7900

Theatre Consultant
Schuler Shook
123 Third Street North #210, Minneapolis, MN 55401
612.339.5958

Acoustical Engineer
Akustiks
93 North Main Street, South Norwalk, CT 06854
203.299.1904

MEP Engineer
JBA Consulting Engineers, Inc.
3525 N. Causeway BLVD. Suite 500 Metairie, LA 70002
504.830.0139

Civil Engineer
Linfield, Hunter, & Junius, Inc.
3606 18th Street Suite 200, Metairie, LA 70002
504.833.5300

Architectural Historian
EHT Traceries, Inc.
1121 Fifth Street NW Washington, DC 20001
202.393.1199

THESE DRAWINGS, SPECIFICATIONS, AND OTHER DOCUMENTS, (COLLECTIVELY, THE "DOCUMENTS") INCLUDING WITHOUT LIMITATION ELECTRONIC VERSIONS THEREOF AND THE IDEAS, DESIGNS, AND ARRANGEMENTS REPRESENTED THEREBY, ARE AND SHALL REMAIN THE PROPERTY OF MARTINEZ & JOHNSON ARCHITECTURE PC, AS DEFINED BY APPLICABLE CONTRACTUAL AGREEMENTS ("THE AGREEMENTS") AND AS PROTECTED BY THE COPYRIGHT STATUTES OF THE UNITED STATES. USE OF THE DOCUMENTS SHALL BE STRICTLY LIMITED TO THE PROJECT FOR WHICH THEY WERE PREPARED AND DEVELOPED ("THE PROJECT") PER THE TERMS OF THE AGREEMENTS. NO PART OF THE DOCUMENTS SHALL BE COPIED, DISCLOSED TO OTHERS, OR USED IN CONNECTION WITH ANY OTHER WORK OR PROJECT, OR BY ANY OTHER PERSONS FOR ANY PURPOSES, OTHER THAN THE COMPLETION OF THE PROJECT, WITHOUT THE SPECIFIC WRITTEN AUTHORIZATION OF MARTINEZ & JOHNSON ARCHITECTURE PC. THE DOWNLOADING, OPENING, OR VIEWING OF ELECTRONIC VERSIONS OF THE DOCUMENTS OR VISUAL CONTACT WITH ANY PRINTED FORM THEREOF SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

7502

DATE:	No.:	REVISION:

DATE:	ISSUE:
02.19.10	PERMIT SET
04.02.10	GMP CONTRACT SET
11.11.10	CONTRACT SET

SHEET TITLE:
DOOR SCHEDULE

A-5.10

© 2010 M+J