FINISH SCHEDULE - PRINT 1

RM. NO.	ROOM NAME	WALL				FLOOR	BASE	CEILING	CLG. HT.	REMARKS
		NORTH	SOUTH	EAST	WEST					
00 BASEMENT LEVEL										
001	PATIO LOBBY	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING STONE/TERRAZZO	EXIST. STONE	EXIST. PLASTER		REF. HP-SERIES FOR FINISHES SCOPE
001.1	STAIR 2	EXISTING	EXISTING	EXISTING	EXISTING	CONC-1	EXISTING	EXISTING		
001.2	STAIR 1	EXISTING	EXISTING	EXISTING	EXISTING	CONC-1	EXISTING	EXISTING		
002	LADIES' LOUNGE	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING STONE/TERRAZZO	EXIST. STONE	EXIST. PLASTER		
003	LADIES' ROOM	ST-2, STR-2, PT-6	ST-2, STR-2, PT-6	ST-2, STR-2, PT-6	ST-2, STR-2, PT-6	ST-2	ST-1	2-LYR M.R. GWB	9'-0"	
004	JANITOR	PT-6	PT-6	PT-6	PT-6	CONC-1	RB-1	EXPOSED	-	
005	MEN'S LOUNGE	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING STONE/TERRAZZO	EXIST. STONE	EXISTING	-	
006	MEN'S ROOM	ST-2, STR-2, TL-19, PT-6	ST-2, STR-2, TL-19, PT-6	ST-2, STR-2, TL-19, PT-6	ST-2, STR-2, TL-19, PT-6		ST-1	2-LYR M.R. GWB	9'-0"	
007	JANITOR	PT-6	PT-6	PT-6	PT-6	CONC-1	RB-1	EXPOSED	-	
008	CORRIDOR	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	ACT-1	-	
008.1	STAIR 3	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	EXPOSED		
009	USHERS & FOH STAFF	PT-1	PT-1	PT-1	PT-1	LFC-1	MB-1	ACT-1	9'-0"	
011	SERVER ROOM	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	ACT-1	8'-0"	
012	CONCESS. MGR	PT-1	PT-1	PT-1	PT-1	LFC-1	MB-1	ACT-1	9'-0"	
013	CONCESSION STORAGE	PT-2	PT-2	PT-2	PT-2	TL-18	TL-18	ACT-1	8'-0"	
014	LINEN STORAGE	PT-1	PT-1	PT-1	PT-1	TL-18	TL-18	ACT-1	9'-0"	
015	STORAGE	PT-2	PT-2	PT-2	PT-2	TL-18	TL-18	2-LYR GWB	8'-0"	
017	STORAGE	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	EXPOSED	8'-0"	
018	MAINT. SHOP	PT-4	PT-4	PT-4	PT-4	CONC-1	RB-1	2-LYR GWB	-	
18.1	STAIR 11	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	EXPOSED		
019	JANITORIAL STORAGE	PT-2	PT-2	PT-2	PT-2	CONC-1	RB-1	EXPOSED	-	
020	TOOL ROOM	PT-2	PT-2	PT-2	PT-2	CONC-1	RB-1	EXPOSED	-	
021	SUMP PUMP	PT-4	PT-4	PT-4	PT-4	CONC-1	RB-1	2-LYR GWB	8'-0"	
022	CORRIDOR	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	EXPOSED	-	
023	CREW RM.	PT-1	PT-1	PT-1	PT-1	CFC-1	MB-1	ACT-1	8'-0"	
024	TECH. DIRECTOR / ASST.	PT-1	PT-1	PT-1	PT-1	CFC-1	MB-1	ACT-1	9'-0"	
025	DIRECTOR OF OPERATIONS	PT-1	PT-1	PT-1	PT-1	CFC-1	MB-1	ACT-1	8'-0"	
026	VISIT PROD. OFFICE.	PT-1	PT-1	PT-1	PT-1	CFC-1	MB-1	ACT-1	8'-0"	
027	WOMEN'S TOILET	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-15, PT-22	TL-14	TL-14	M.R.GWB	8'-0"	
028	MEN'S TOILET	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-14	TL-14	M.R.GWB	8'-0"	
029	TRASH					CONC-1	RB-1	2-LYR GWB	8'-0"	
030	RECEIVING	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1			
031	CORRIDOR	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	ACT-2	-	
032	STORAGE	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	EXPOSED	-	
033	ORGAN BLOWER	4" DUCT LINER	PT-1	4" DUCT LINER	PT-1	CONC-1	RB-1	2-LYR GWB 4" DUCTLINER	8'-0"	
035	CORRIDOR	PT-4	PT-4	PT-4	PT-4	CONC-1	RB-1	EXPOSED	-	ALL SURFACES, INCLUDING FLOORS AND DOORS PAINTED BLACK
036	STAIR 7	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	EXPOSED		
037	CORRIDOR	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	ACT-1	-	
038	LAUNDRY		4" DUCT LINER	4" DUCT LINER		CONC-1	RB-1	ACT-1	8'-0"	
040	STAGE MGR.	PT-1	PT-1	PT-1	PT-1	LFC-1	MB-1	ACT-1		
041	STAR DRESSING ROOM 'A'	PT-1	PT-1	PT-1, PLAM-1	PT-1	CPT-2	RB-1	ACT-1	8'-0"	
042	TOILET	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-14	TL-14	M.R.GWB	8'-0"	
043	CORRIDOR	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	ACT-1	-	
044	RECEIVING	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	ACT-1		
045	STAR DRESSING ROOM 'B'	PT-1	PT-1	PT-1	PT-1, PLAM-1	CPT-2	RB-1	ACT-1	8'-0"	
046	TOILET	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-14	TL-14	M.R.GWB	8'-0"	
047	MULTIPURPOSE ROOM	PT-4	PT-1	PT-4	PT-4	CONC-1	RB-1	EXPOSED	-	DARK FINISHES REQ'D ON NORTH, EAST + WEST WALLS. MARMOLEUM @ KITCHEN SEE A-6.16 RE KITCHEN DETAILS
048	ORCHESTRA PIT	PT-4	PT-4	PT-4	PT-4	PLY-1		PT-4		REF A-5.48 + TR-7.01 RE DRAPERY DETAILS
049	TOILET	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-14	TL-14	M.R.GWB	8'-0"	
050	CHORUS DRESSING ROOM 'B'	PT-1, PLAM-1	PT-1, PLAM-1	PT-1, PLAM-1	PT-1, PLAM-1	LFC-1	MB-1	ACT-1	8'-0"	
051	SEWAGE EJECTOR / SUMP		4" DUCT LINER		4" DUCT LINER	CONC-1	RB-1	2-LYR M.R. GWB	8'-0"	
052	TOILET	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-14	TL-14	M.R.GWB	8'-0"	
053	PRINCIPAL DRESSING ROOM	PT-1, PLAM-1	PT-1, PLAM-1	PT-1, PLAM-1	PT-1, PLAM-1	LFC-1	RB-1	ACT-1	8'-0"	
054	TOILET	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-14	TL-14	M.R.GWB	8'-0"	
055	CORRIDOR	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	ACT-1		

FINISH SCHEDULE - PRINT 1

RM. NO.	ROOM NAME	WALL				FLOOR	BASE	CEILING	CLG. HT.	REMARKS
		NORTH	SOUTH	EAST	WEST					
056	CHORUS DRESSING ROOM "A"	PT-1, PLAM-1	PT-1, PLAM-1	PT-1, PLAM-1	PT-1, PLAM-1	LFC-1	MB-1	ACT-1	8'-0"	
057	TOILET	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-14	TL-14	M.R.GWB		
058	COMP. MGR / ASST. MGR.	PT-1	PT-1	PT-1	PT-1	LFC-1	MB-1	ACT-1	8'-0"	
059	STAIR 25	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	EXPOSED		
060	STAIR 6	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	EXPOSED		
01 ORCHESTRA LEVEL										
100	CANAL STREET ARCADE	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING STONE/TERRAZZO	EXIST. STONE	EXISTING	EXISTING	SALVAGED MARBLE WITH NEW TERRAZZO
101	CROSS ARCADE	EXISTING	EXISTING	EXISTING	EXISTING	EXISTING STONE/TERRAZZO	EXIST. STONE	EXISTING		
102	ELEV. LOBBY	ST-6, PT-5	ST-6, PT-5	ST-6, PT-5	ST-6, PT-5	TL-1	ST-6	GWB	10'-0"	
103	COMPANION TOILET	TL-3, TL-5	TL-3, TL-5	TL-3, TL-5	TL-3, TL-5	TL-1	TL-1	M.R.GWB		SEE A-6.22 RE DETAILS+ELEVATIONS
104	JAN. CL.	PT-1	PT-1	PT-1	PT-1	TL-18	TL-18	ACT-1		
105	CONCESSION	FRP	FRP	FRP	FRP	TL-18	TL-18	M.R.GWB		
106	WOMEN'S ROOM	TL-4, TL-6	TL-4, TL-6	TL-4, TL-6	TL-4, TL-6	TL-2	TL-2	M.R.GWB		
107	MEN'S ROOM	TL-3, TL-5	TL-3, TL-5	TL-3, TL-5	TL-3, TL-5	TL-1	TL-1	M.R.GWB		
108	H.C. ENTRY	ST-6, PT-5	ST-6, PT-5	ST-6, PT-5	ST-6, PT-5	TL-1	TL-1	GWB		
109	TRANSFORMER VAULT			4" DUCT LINER	4" DUCT LINER	CONC-1	RB-1	2-LYR GWB 4" DUCTLINER	-	
110	STAIR 23	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1			
111	LOBBY	ST-6, PT-5	ST-6, PT-5	ST-6, PT-5	ST-6, PT-5	TL-1	ST-6	GWB		
112	BOX OFFICE	PT-5	PT-5	PT-5	PT-5	LFC-1	WDTR-5	GWB	9'-0"	SEE A-6.40 RE ELEV + DETAILS
113	STORAGE	PT-5	PT-5	PT-5	PT-5	LFC-1	MB-1	GWB		
114	STAIR 24	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	EXPOSED		
115	INFO. BOOTH									
116	LOBBY	DPT	DPT	DPT	DPT		STONE	EXIST. PLASTER	-	
117	HOUSE RIGHT AISLE	DPT	DPT	DPT	DPT	CPT-1B (FOH)	STONE	EXIST. PLASTER	-	
118	ORCHESTRA SEATING						-		-	
119	HOUSE LEFT AISLE					CPT-1B (FOH)	EXISTING	EXISTING	-	
120	SOLOIST STAGE	DPT	DPT	DPT	DPT	CONC-1				
121	FOUNTAIN	DPT	DPT	DPT	DPT	CONC-1	EXISTING	EXISTING	-	PAINTED CONC.
122	STAIR 9	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1			
124	STAIR 6	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1			
125	STAGE	PT-4	PT-4	PT-4	PT-4	PLY-1		EXPOSED	-	PAINT-4 TO BOTTOM OF GRID. NO PAINT REQ'D ON WALLS OR ROOF DECK ABOVE +75'-0" GRID LEVEL
126	STAGE TOILET	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-15, PT-2	TL-14	TL-14	M.R.GWB	-	
127	STAIR 7	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1			
128	STAGE DOOR	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	EXISTING	-	
130	A/V RACK	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1	ACT-1	8'-0"	
131	STAIR 8	PT-1	PT-1	PT-1	PT-1	CONC-1				
01.5 BACK OF HOUSE - LEVEL 2										
150	STAIR 7	PT-1	PT-1	PT-1	PT-1	CONC-1	RB-1			
151	PRINCIPAL DRESSING ROOM	PT-1	PT-1	PT-1	PT-1	LFC-1	MB-1	ACT-1	8'-0"	
152	ELEV. LOBBY	PT-1	PT-1	PT-1	PT-1	LFC-1	MB-1	ACT-1	8'-0"	
153	TOILET	PT-2	PT-2	PT-2	PT-2	TL-14	TL-14	M.R.GWB	8'-0"	

GENERAL FINISH NOTES:

1. SEE A-5.42 FOR MATERIAL INDENTIFICATION AND DESCRIPTION.
2. SEE SHEETS A-1.20 TO A-1.30 FOR ADDITIONAL CEILING INFORMATION.
3. SEE HP SHEETS FOR DETAILED PRESERVATION AND RESTORATION INFORMATION.
4. SEE A-9.00 FOR ELEVATOR FINISH INFORMATION AND SCHEDULE.
5. ALL FABRICS MUST BE MADE FIREPROOF, FIRE TREATED OR FLAME RETARDANT UNDER ALL ASTM, NFPA701 SMALL AND LARGE SCALE TESTS, ALL OTHER APPLICABLE TESTS, AND COLOR FASTNESS TESTS.

THE SAENGER THEATRE RENEWAL PROJECT

142 North Rampart Street
New Orleans, LA

Client
Saenger Theatre Redevelopment Company
1800 Post Oak Boulevard, 6 Boulevard Place, Suite 450, Houston, TX 77056

Architect
MARTINEZ+JOHNSON ARCHITECTURE
1412 Eye St., NW
Washington, DC 20005
202.333.4480

Structural Engineer
Lundy & Franke Engineering, Inc.
549 Heimer Road, San Antonio, TX 78232
210.979.7900

Theatre Consultant
Schuler Shook
123 Third Street North #210, Minneapolis, MN 55401
612.339.5958

Acoustical Engineer
Akustiks
93 North Main Street, South Norwalk, CT 06854
203.299.1904

MEP Engineer
JBA Consulting Engineers, Inc.
3525 N. Causeway BLVD. Suite 500 Metairie, LA 70002
504.830.0139

Civil Engineer
Linfield, Hunter, & Junius, Inc.
3606 18th Street Suite 200, Metairie, LA 70002
504.833.5300

Architectural Historian
EHT Traceries, Inc.
1121 Fifth Street NW Washington, DC 20001
202.393.1199

THESE DRAWINGS, SPECIFICATIONS, AND OTHER DOCUMENTS, (COLLECTIVELY, THE "DOCUMENTS") INCLUDING WITHOUT LIMITATION ELECTRONIC VERSIONS THEREOF AND THE IDEAS, DESIGNS, AND ARRANGEMENTS REPRESENTED THEREBY, ARE AND SHALL REMAIN THE PROPERTY OF MARTINEZ & JOHNSON ARCHITECTURE PC, AS DEFINED BY APPLICABLE CONTRACTUAL AGREEMENTS ("THE AGREEMENTS") AND AS PROTECTED BY THE COPYRIGHT STATUTES OF THE UNITED STATES. USE OF THE DOCUMENTS SHALL BE STRICTLY LIMITED TO THE PROJECT FOR WHICH THEY WERE PREPARED AND DEVELOPED ("THE PROJECT") PER THE TERMS OF THE AGREEMENTS. NO PART OF THE DOCUMENTS SHALL BE COPIED, DISCLOSED TO OTHERS, OR USED IN CONNECTION WITH ANY OTHER WORK OR PROJECT, OR BY ANY OTHER PERSONS FOR ANY PURPOSES, OTHER THAN THE COMPLETION OF THE PROJECT, WITHOUT THE SPECIFIC WRITTEN AUTHORIZATION OF MARTINEZ & JOHNSON ARCHITECTURE PC. THE DOWNLOADING, OPENING, OR VIEWING OF ELECTRONIC VERSIONS OF THE DOCUMENTS OR VISUAL CONTACT WITH ANY PRINTED FORM THEREOF SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

7502

DATE:	No.:	REVISION:

DATE:	ISSUE:
02.19.10	PERMIT SET
04.02.10	GMP CONTRACT SET
11.11.10	CONTRACT SET

SHEET TITLE:
FINISH SCHEDULE

A-5.40

© 2010 M+J