DRAPERY SCHEDULE

Drapery Level	DRAPE NO.	ROOM NAME	ROOM NUMBER	DRAPE FABRIC	WIDTH	LENGTH	TRIM TYPE	HARDWARE	VALANCE	REMARKS
01 BASEMENT LEVEL										
01 BASEMENT LEVEL	DP-CR2	ORCHESTRA PIT		FB-5	REF TR-7.01	REF TR-7.01				
01 ORCHESTRA LEVEL										
01 ORCHESTRA LEVEL	DP-9	AUDIENCE CHAMBER ENTRY DOORS		FB-9	2'-1" VIF	6'-0" VIF	NA			TO BE APPROVED BY ARCHITECT
01 ORCHESTRA LEVEL	DP-CR1	STAGE PROSCENIUM		FB-4	REF TR-7.01	REF TR-7.01				TO BE APPROVED BY ARCHITECT
02 LOGE LEVEL										
02 LOGE LEVEL	DP-1	VOMITORIES		FB-9	6'-0" VIF	9'-0" VIF	FTR-11	REF A-5.47	SELF	TO BE APPROVED BY ARCHITECT
02 LOGE LEVEL	DP-2	AUD CHAMBER HOUSE LEFT		FB-##	8'-0" VIF	9'-0" VIF	FBTR-##	REF A-5.47	YES	TO BE APPROVED BY ARCHITECT
02 LOGE LEVEL	DP-3	AUD CHAMBER HOUSE RIGHT		FB-6	3'-3" VIF	5'-0" + 10 1/4"	FTR-9	REF A-5.47	YES	TO BE APPROVED BY ARCHITECT
02 LOGE LEVEL	DP-4	AUD CHAMBER HOUSE RIGHT		FB-8	1'-4" VIF	10" VIF	FTR-11	REF A-5.47	YES	TO BE APPROVED BY ARCHITECT
02 LOGE LEVEL	DP-5	AUD CHAMBER HOUSE LEFT		FB-7	5-'0" PAIR VIF	10'-3" VIF	FTR-10	REF A-5.47	NA	TO BE APPROVED BY ARCHITECT
02B 1101 CANAL 2ND LEVEL										
02B 1101 CANAL 2ND LEVEL	DP-6	VIP LOUNGE		FB-10 + FB-11	2 2' PANELS VIF	9' VIF	NA	AS REQ.	NA	TO BE APPROVED BYARCHITECT
04 UPPER BALCONY LEVEL										
04 UPPER BALCONY LEVEL	DP-7	STAIR 19								
04 UPPER BALCONY LEVEL	DP-8	STAIR 19		FB-##	3'-6" PAIR VIF	10'-3" VIF	FBTR-##	REF A-5.47	NA	

ACOUSTIC WALL PANEL SCHEDULE

TAG. NO	LOCATION	MANUFACTURER	DESCRIPTION	FINISH	REMARKS
AWP-1	ARCADE, SIDE LOUNGES, LOGGIA, VOMITORY, STAIR 18 AND 19	WHISPER WALLS	1" THICK	FB-13	ACOUSTICALY TRANSPARENT STRETCH FABRIC TO BE DEVELOPED IN COLLABORATION WITH OWNER'S DECORATIVE FINISHES CONTRACTOR AND ACOUSTIC PANEL MANUFACTURER. FABRIC TO BE APPROVED BY ARCHITECT AND ACOUSTICIAN PRIOR TO FINALPRODUCTION.
AWP-2	ORCHESTRA LEVEL SEATING	WHISPER WALLS	2" THICK	FB-13	ACOUSTICALY TRANSPARENT STRETCH FABRIC TO BE DEVELOPED IN COLLABORATION WITH OWNER'S DECORATIVE FINISHES CONTRACTOR AND ACOUSTIC PANEL MANUFACTURER. FABRIC TO BE APPROVED BY ARCHITECT AND ACOUSTICIAN PRIOR TO FINALPRODUCTION.
AWP-3	FOLLOW SPOT ROOM	WHISPER WALLS	1" THICK	FB-14	ACOUSTICALY TRANSPARENT STRETCH FABRIC TO BE DEVELOPED IN COLLABORATION WITH OWNER'S DECORATIVE FINISHES CONTRACTOR AND ACOUSTIC PANEL MANUFACTURER. FABRIC TO BE APPROVED BY ARCHITECT AND ACOUSTICIAN PRIOR TO FINALPRODUCTION.

DRAPERY HARDWARE SCHEDULE

TAG NO	HARDWARE TYPE	COLOR	ITEM NO.	MANUFACTURER	REMARKS
DH-1	DRAPERY ROD	770 BLACK	56359	KIRSCH OR EQUAL	COORDINATE W/ DP-1, DP-2, DP-3, DP-4, DP-5
DH-2	WALL-MOUNT BRACKET	770 BLACK	56368	KIRSCH OR EQUAL	COORDINATE W/ DP-4, DP-5
DH-3	INSIDE MOUNT SOCKET	770 BLACK	56370	KIRSCH OR EQUAL	COORDINATE W/ DP-1, DP-2, DP-3
DH-4	FINIAL	770 BLACK	56356	KIRSCH OR EQUAL	COORDINATE W/ DP-4, DP-5
DH-5	SASH ROD	025 WHITE	6412	KIRSCH OR EQUAL	COORDINATE W/ DP-9
DH-6	MEDALLION HOLDBACK	006 BLACK	54906	KIRSCH OR EQUAL	COORDINATE W/ DP-5
DH-7	DECORATIVE HOOK	03 BRASS	7618B	KIRSCH OR EQUAL	COORDINATE W/ DP-1
DH-8	SWIVEL SOCKET	770 BLACK	56367	KIRSCH OR EQUAL	COORDINATE W/ DP-2, DP-3
DH-CR2	HEAVY DUTY HANGING ROD	BRONZE			COORDINATE W DP-CR2
DH-CR3	HEAVY DUTY HANGING ROD	BRONZE			COORDINATE W DP-CR3

THE SAENGER THEATRE RENEWAL PROJECT

142 North Rampart Street
New Orleans, LA

Client
Saenger Theatre Redevelopment Company
1800 Post Oak Boulevard, 6 Boulevard Place, Suite 450, Houston, TX 77056

Architect
MARTINEZ+JOHNSON ARCHITECTURE
1412 Eye St., NW
Washington, DC 20005
202.333.4480

Structural Engineer
Lundy & Franke Engineering, Inc.
549 Heimer Road, San Antonio, TX 78232
210.979.7900

Theatre Consultant
Schuler Shook
123 Third Street North #210, Minneapolis, MN 55401
612.339.5958

Acoustical Engineer
Akustiks
93 North Main Street, South Norwalk, CT 06854
203.299.1904

MEP Engineer
JBA Consulting Engineers, Inc.
3525 N. Causeway BLVD. Suite 500 Metairie, LA 70002
504.830.0139

Civil Engineer
Linfield, Hunter, & Junius, Inc.
3608 18th Street Suite 200, Metairie, LA 70002
504.833.5300

Architectural Historian
EHT Traceries, Inc.
1121 Fifth Street NW
Washington, DC 20001
202.393.1199

THESE DRAWINGS, SPECIFICATIONS, AND OTHER DOCUMENTS, (COLLECTIVELY, THE "DOCUMENTS") INCLUDING WITHOUT LIMITATION ELECTRONIC VERSIONS THEREOF AND THE IDEAS, DESIGNS, AND ARRANGEMENTS REPRESENTED THEREBY, ARE AND SHALL REMAIN THE PROPERTY OF MARTINEZ & JOHNSON ARCHITECTURE PC, AS DEFINED BY APPLICABLE CONTRACTUAL AGREEMENTS ("THE AGREEMENTS") AND AS PROTECTED BY THE COPYRIGHT STATUTES OF THE UNITED STATES. USE OF THE DOCUMENTS SHALL BE STRICTLY LIMITED TO THE PROJECT FOR WHICH THEY WERE PREPARED AND PUBLISHED AS SPECIFIED IN THE TERMS OF THE AGREEMENTS. NO PART OF THE DOCUMENTS SHALL BE COPIED, DISCLOSED TO OTHERS, OR USED IN CONNECTION WITH ANY OTHER WORK OR PROJECT, OR BY ANY OTHER PERSONS FOR ANY PURPOSES, OTHER THAN THE COMPLETION OF THE PROJECT, WITHOUT THE SPECIFIC WRITTEN AUTHORIZATION OF MARTINEZ & JOHNSON ARCHITECTURE PC. THE DOWNLOADING, OPENING, OR VIEWING OF ELECTRONIC VERSIONS OF THE DOCUMENTS OR VISUAL CONTACT WITH ANY PRINTED FORM THEREOF SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

7502

DATE:	No.:	REVISION:

DATE:	ISSUE:
02.19.10	PERMIT SET
04.02.10	GMP CONTRACT SET
11.11.10	CONTRACT SET

SHEET TITLE:
DRAPERY AND ACOUSTIC PANEL SCHEDULE AND ASSOCIATED HARDWARE

A-5.45

© 2010 M+J